

Is it a “Good” Encoding of Mixed Choice? (Technical Report) *

Kirstin Peters and Uwe Nestmann

TU Berlin, Germany

Abstract. This technical report contains the proofs to the lemmata and theorems of [PN12] as well as some additional material. As main contributions [PN12] presents an encoding of mixed choice in the context of the π -calculus and a criterion to measure whether the degree of distribution in process networks is preserved.

1 Technical Preliminaries

1.1 The π -Calculus

Our source language is the monadic π -calculus as described for instance in [SW01]. As already demonstrated in [Pal03] the most interesting operator for a comparison of the expressive power between the full π -calculus and its asynchronous variant is mixed choice, i.e., choice between input and output capabilities. Thus we denote the full π -calculus also by π_m . Let $\mathcal{N}$ denote a countably infinite set of names with $\tau \notin \mathcal{N}$ and $\overline{\mathcal{N}}$ the set of co-names, i.e., $\overline{\mathcal{N}} = \{\overline{n} \mid n \in \mathcal{N}\}$. We use lower case letters $a, a', a_1, \dots, x, y, \dots$ to range over names.

Definition 1 (π_m). *The set of process terms of the synchronous π -calculus (with mixed choice), denoted by $\mathcal{P}_m$, is given by*

$$P ::= (\nu n)P \mid P_1 \mid P_2 \mid [a = b]P \mid y^*(x).P \mid \sum_{i \in I} \pi_i.P_i$$

where $\pi ::= y(x) \mid \overline{y}\langle z \rangle \mid \tau$ for some names $n, a, b, x, y, z \in \mathcal{N}$ and a finite index set I .

The interpretation of the defined process terms is as usual. Moreover we consider two subcalculi of π_m . The process terms $\mathcal{P}_s$ of π_s —the π -calculus with separate choice—are obtained by restricting the choice primitive, such that in each choice either no input guarded or no output guarded alternatives appear.

Definition 2 (π_s). *The set of process terms of the π -calculus (with separate choice), denoted by $\mathcal{P}_s$, is given by*

$$P ::= (\nu n)P \mid P_1 \mid P_2 \mid [a = b]P \mid y^*(x).P \mid \sum_{i \in I} \pi_i^I.P_i \mid \sum_{i \in I} \pi_i^O.P_i$$

where $\pi^I ::= y(x) \mid \tau$ and $\pi^O ::= \overline{y}\langle z \rangle \mid \tau$ for some names $n, a, b, x, y, z \in \mathcal{N}$ and a finite index set I .

Finally, the process terms $\mathcal{P}_a$ of the *asynchronous* π -calculus π_a [Bou92, HT91] are obtained by restricting each sum to be of length zero or one and requiring, that outputs can only guard the empty sum.

Definition 3 (π_a). *The set of process terms of the asynchronous π -calculus, denoted by $\mathcal{P}_a$, is given by*

$$P ::= \mathbf{0} \mid (\nu n)P \mid P_1 \mid P_2 \mid [a = b]P \mid \overline{y}\langle \tilde{z} \rangle.P \mid y(\tilde{x}).P \mid \tau.P \mid y^*(\tilde{x}).P$$

for some names $n, a, b, y \in \mathcal{N}$ and some finite sequences of names $\tilde{x}, \tilde{z} \subset \mathcal{N}$.

Note that we augment all three variants of the π -Calculus with matching, because we need it at least in π_a to encode mixed choice. Of course, the presence of match influences the expressive power of π_a . However, we do not know, whether the use of match in the encoding of mixed choice can be circumvented, although there are reasons indicating that this is indeed not possible. We left the consideration of this problem to further research.

We use capital letters $P, P', P_1, \dots, Q, R, \dots$ to range over processes. Let $\text{fn}(P)$, $\text{bn}(P)$, and $\text{n}(P)$ denotes the sets of free names, bound names and all names occurring in P , respectively. Their definitions are completely standard. Given an input prefix $y(x)$ or an output prefix $\overline{y}\langle x \rangle$ we call y the subject and x the object of the action. Moreover we denote the subject of an action also as link or channel name, while we denote the object as value or parameter. Note

* This work was supported by the DFG (German Research Foundation), grant NE-1505/2-1.

that in case the object does not matter we omit it, i.e., we abbreviate an input guarded term $y(x).P$ or an output guarded term $\overline{y}\langle x \rangle.P$ such that $x \notin \text{fn}(P)$ by $y.P$ or $\overline{y}.P$, respectively. Moreover we denote the empty sum with $\mathbf{0}$ and often omit it in continuations. As usual we sometimes notate a sum $\sum_{i \in \{i_1, \dots, i_n\}} \pi_i.P_i$ by $\pi_{i_1}.P_{i_1} + \dots + \pi_{i_n}.P_{i_n}$.

We use $\sigma, \sigma', \sigma_1, \dots$ to range over substitutions. A substitution is a mapping $\{x_1/y_1, \dots, x_n/y_n\}$ from names to names. The application of a substitution on a term $\{x_1/y_1, \dots, x_n/y_n\}(P)$ is defined as the result of simultaneously replacing all free occurrences of y_i by x_i for $i \in \{1, \dots, n\}$, possibly applying alpha-conversion to avoid capture or name clashes. For all names $\mathcal{N} \setminus \{y_1, \dots, y_n\}$ the substitution behaves as the identity mapping. Let id denote identity, i.e. id is the empty substitution. We naturally extend substitutions to co-names, i.e. $\forall \overline{n} \in \overline{\mathcal{N}}. \sigma(\overline{n}) = \overline{\sigma(n)}$ for all substitutions σ .

Moreover, let $\tilde{x}$ denote a sequence of names. For simplicity, we occasionally treat $\tilde{x}$ as a set. So $\tilde{x} \subset M$ denotes a sequence of names of the set M , $|\tilde{x}|$ is the length of the sequence $\tilde{x}$, and $y \in \tilde{x}$ denotes that y is one of the names within the sequence $\tilde{x}$. Accordingly, we use the notion of sequence to abbreviate multiple restrictions, i.e., $(\nu \tilde{x})P \triangleq (\nu x_1) \dots (\nu x_n)P$ for a sequence of names $\tilde{x} = x_1, \dots, x_n$. Moreover we naturally extend substitutions to sequences of names, i.e., $\sigma(\tilde{x}) \triangleq \sigma(x_1), \dots, \sigma(x_n)$ and $\{\tilde{x}/\tilde{y}\}P \triangleq \{x_1/y_1, \dots, x_n/y_n\}P$ for two sequences of names $\tilde{x} = x_1, \dots, x_n$ and $\tilde{y} = y_1, \dots, y_n$.

$P \equiv Q$ if Q can be obtained from P by renaming one or more of the bound names in P , silently avoiding name clashes

$$P \mid \mathbf{0} \equiv P \quad P \mid Q \equiv Q \mid P \quad P \mid (Q \mid R) \equiv (P \mid Q) \mid R \quad [a = a]P \equiv P$$

$$(\nu n)\mathbf{0} \equiv \mathbf{0} \quad (\nu n)(\nu m)P \equiv (\nu m)(\nu n)P \quad P \mid (\nu n)Q \equiv (\nu n)(P \mid Q) \text{ if } n \notin \text{fn}(P)$$

Fig. 1. Structural congruence.

The *reduction semantics* of π_m , π_s , and π_a are jointly given by the transition rules in Figure 2, where *structural congruence*, denoted by $\equiv$, is given by the rules in Figure 1. Note that the rule COM_a for communication in π_a is a simplified version of the rule $\text{COM}_{m,s}$ for communication in π_m or π_s . The differences between these two rules result from the differences in the syntax, i.e. the lack of choice and the fact that only input can be used as guard in π_a . The same can be observed for the rules TAU_a and REP_a . As usual, we use $\equiv_\alpha$ if we refer to alpha-conversion (the first rule of Figure 1) only.

$$\text{TAU}_{m,s} \quad \dots + \tau.P + \dots \mapsto P \quad \text{TAU}_a \quad \tau.P \mapsto P$$

$$\text{COM}_{m,s} \quad (\dots + y(x).P + \dots) \mid (\dots + \overline{y}\langle z \rangle.Q + \dots) \mapsto \{z/x\}P \mid Q$$

$$\text{COM}_a \quad y(\tilde{x}).P \mid \overline{y}\langle \tilde{z} \rangle \mapsto \{\tilde{z}/\tilde{x}\}P \quad \text{if } |\tilde{x}| = |\tilde{z}|$$

$$\text{REP}_{m,s} \quad y^*(x).P \mid (\dots + \overline{y}\langle z \rangle.Q + \dots) \mapsto \{z/x\}P \mid Q \mid y^*(x).P$$

$$\text{REP}_a \quad y^*(\tilde{x}).P \mid \overline{y}\langle \tilde{z} \rangle \mapsto \{\tilde{z}/\tilde{x}\}P \mid y^*(\tilde{x}).P \quad \text{if } |\tilde{x}| = |\tilde{z}|$$

$$\text{PAR} \quad \frac{P \mapsto P'}{P \mid Q \mapsto P' \mid Q} \quad \text{RES} \quad \frac{P \mapsto P'}{(\nu x)P \mapsto (\nu x)P'} \quad \text{CONG} \quad \frac{P \equiv P' \quad P' \mapsto Q' \quad Q' \equiv Q}{P \mapsto Q}$$

Fig. 2. Concurrent reduction semantics.

Let $P \mapsto (P \not\mapsto)$ denote existence (non-existence) of a step from P , i.e. there is (no) $P' \in \mathcal{P}$ such that $P \mapsto P'$. Moreover, let $\mapsto$ be the reflexive and transitive closure of $\mapsto$ and let $\mapsto^\infty$ define an infinite sequence of steps.

In Section 1.3, we present several criteria to measure the quality of an encoding. The first of these criteria relies on the notion of a context. A *context* $\mathcal{C}([\cdot]_1, \dots, [\cdot]_n)$ is a π -term, i.e., a π_a -term in case of Definition 7, with n so-called holes. Plugging the π_a -terms $P_1, \dots, P_n$ in this order into the holes $[\cdot]_1, \dots, [\cdot]_n$ of the context, respectively, yields a term denoted $\mathcal{C}(P_1, \dots, P_n)$. Therefore, we consider a context as a function from terms into terms, e.g., the context $\mathcal{C}([\cdot]_1, \dots, [\cdot]_n) \in \mathcal{P}_a \times \dots \times \mathcal{P}_a \rightarrow \mathcal{P}_a$ maps n π_a -terms onto a π_a -term. Sometimes, we refer to $P_1, \dots, P_n$ as the parameters of the context $\mathcal{C}$. Note that a context may bind some free names of $P_1, \dots, P_n$. The *arity* of a context is the number of its holes.

As usual we will use equivalence relations to compare π -terms by means of their behaviour. Moreover, as explained in Section 1.3, we use an equivalence to abstract from junk, i.e., remains of encoded terms that are no longer of any use. Since we use a reduction semantics, a standard equivalence to compare π_m -terms is barbed congruence, denoted by $\cong$. Its definition relies on the notion of an *observable* or *barb* (we refer to [SW01] for a detailed explanation).

Definition 4 (Observable). Let $P \in \mathcal{P}_m$. Then P has an input observable y , denoted by $P \downarrow_y$, if P can perform an input on y , i.e.,

$$\exists P', P'' \in \mathcal{P}_m . \exists \tilde{x} \subset \mathcal{N} . \exists z \in \mathcal{N} . P \equiv (\nu \tilde{x}) (P' \mid y(z).P'') \wedge y \notin \tilde{x}$$

and P has an output observable y , denoted by $P \downarrow_{\bar{y}}$, if P can perform an output on y , i.e.,

$$\exists P', P'' \in \mathcal{P}_m . \exists \tilde{x} \subset \mathcal{N} . \exists z \in \mathcal{N} . P \equiv (\nu \tilde{x}) (P' \mid \bar{y}\langle z \rangle.P'') \wedge y \notin \tilde{x}.$$

1.2 Abbreviations

To shorten the presentation and ease the readability of the rather lengthy encoding function in the next section, we use some abbreviations on π_a -terms. First note that we defined only monadic versions of the calculi π_m , π_s , and π_a , where over any link exactly one value is transmitted. However, within the presented encoding functions, we treat the target language π_a as if it allows for polyadic communication. More precisely, we allow asynchronous links to carry any number of values from zero to five, of course under the requirement that within each π_a -term no link name is used twice with different multiplicities. Note that these polyadic actions can be simply translated into monadic actions by a standard encoding as given in [SW01]. Thus, we silently use the polyadic version of π_a in the following. Second, as already done in [Nes00], we use the following abbreviations to define boolean values and a conditional construct.

Definition 5 (Tests on Booleans). Let $\mathbb{B} \triangleq \{\top, \perp\}$ be the set of boolean values, where $\top$ denotes true and $\perp$ denotes false.

Let $l, t, f \in \mathcal{N}$ and $P, Q \in \mathcal{P}_a$. Then a boolean instantiation of l , i.e., the allocation of a boolean value to a link l , and a test-statement on a boolean instantiation are defined by

$$\begin{aligned} \bar{l}\langle \top \rangle &\triangleq l(t, f). \bar{t} \\ \bar{l}\langle \perp \rangle &\triangleq l(t, f). \bar{f} \\ \text{test } l \text{ then } P \text{ else } Q &\triangleq (\nu t, f) (\bar{l}\langle t, f \rangle \mid t.P \mid f.Q) \end{aligned}$$

for some $t, f \notin \text{fn}(P) \cup \text{fn}(Q)$.

Finally, we define forwarders, i.e., a simple process to forward each received message along some specified set of links.

Definition 6 (Forwarder). Let I be a finite index set and for all $i \in I$ let y and y_i be channel names with multiplicity $n \in \mathbb{N}$, then a forwarder is given by:

$$y \rightarrow \{y_i \mid i \in I\} \triangleq y^*(x_1, \dots, x_n) . \left(\prod_{i \in I} \bar{y}_i \langle x_1, \dots, x_n \rangle \right)$$

In case of a singleton set we omit the brackets, i.e., $y \rightarrow y' \triangleq y \rightarrow \{y'\}$.

1.3 Quality Criteria for Encodings

Within this paper we consider two encodings, (1) an encoding from π_s into π_a presented in [Nes00], denoted by $\llbracket \cdot \rrbracket_a^s$, and (2) a new encoding from π_m into π_a , denoted by $\llbracket \cdot \rrbracket_a^m$. To measure the quality of such an encoding, Gorla [Gor10] suggested five criteria well suited for language comparison. Accordingly, we consider an encoding to be “good”, if it satisfies Gorla’s five criteria.

As in [Gor10], an encoding is a mapping from a source into a target language; in our case, π_m and π_s are source languages and π_a is the target language. To distinguish terms on these languages or definitions for the respective encodings, we use m, s, and a as super- and subscripts. Thereby, the superscript usually refers to the source and the subscript the target language. Moreover, we use $S, S', S_1, \dots$ to range over terms of the source languages and $T, T', T_1, \dots$ to range over terms of the target language.

The five conditions are divided into two structural and three semantic criteria. The structural criteria include (1) *compositionality* and (2) *name invariance*. The semantic criteria include (3) *operational correspondence*, (4) *divergence reflection* and (5) *success sensitiveness*. Note that for the definition of name invariance and operational correspondence a behavioural equivalence $\asymp$ on the target language is assumed. Its purpose is to describe the abstract behaviour of a target process, where abstract basically means with respect to the behaviour of the source term.

Intuitively, an encoding is compositional if the translation of an operator depends only on the translation of its parameters. To mediate between the translations of the parameters the encoding defines a unique context for each operator, whose arity is the arity of the operator. Moreover, the context can be parametrised on the free names of the corresponding source term.

Definition 7 (Criterion 1: Compositionality). *The encoding $\llbracket \cdot \rrbracket$ is compositional if, for every k -ary operator $\mathbf{op}$ of π_m and for every subset of names N , there exists a k -ary context $\mathcal{C}_{\mathbf{op}}^N([\cdot]_1, \dots, [\cdot]_k)$ such that, for all $S_1, \dots, S_k$ with $\text{fn}(S_1) \cup \dots \cup \text{fn}(S_k) = N$, it holds that*

$$\llbracket \mathbf{op}(S_1, \dots, S_k) \rrbracket = \mathcal{C}_{\mathbf{op}}^N(\llbracket S_1 \rrbracket, \dots, \llbracket S_k \rrbracket).$$

If the context is again the original operator, i.e., if an operator is translated by encoding its parameters and apply the renaming policy, as in $\llbracket (\nu x) P \rrbracket = (\nu \varphi_{\llbracket \cdot \rrbracket}(x)) \llbracket P \rrbracket$, we call this encoding *rigid*. Note that Gorla requires that the parallel composition operator “|” is binary and unique in the source as well as in the target language. Thus, compositionality prevents from introducing a global coordinator or to use global knowledge, i.e., knowledge about surrounding source terms or the structure of the parameters.

The second structural criterion states that the encoding should not depend on specific names used in the source term. This is important, since sometimes it is necessary to translate a source term name into a sequences of names or reserve some names for the encoding function. To ensure that there are no conflicts between these reserved names and the source term names, the encoding is equipped with a renaming policy $\varphi_{\llbracket \cdot \rrbracket}$, i.e., a substitution from names into sequences of names¹. Since we translate source term names only into single names, the renaming policies introduced by $\llbracket \cdot \rrbracket_a^s$ and $\llbracket \cdot \rrbracket_a^m$ are injective substitutions from names into names. Based on such a renaming policy an encoding is independent of specific names if it preserves all substitutions σ on source terms by a substitution σ' on target terms such that σ' respects the changes made by the renaming policy.

Definition 8 (Criterion 2: Name Invariance). *The encoding $\llbracket \cdot \rrbracket$ is name invariant if, for every S and σ , it holds that*

$$\llbracket \sigma(S) \rrbracket \begin{cases} \equiv_{\alpha} \sigma'(\llbracket S \rrbracket) & \text{if } \sigma \text{ is injective} \\ \asymp \sigma'(\llbracket S \rrbracket) & \text{otherwise} \end{cases}$$

where σ' is such that $\varphi_{\llbracket \cdot \rrbracket}(\sigma(n)) = \sigma'(\varphi_{\llbracket \cdot \rrbracket}(n))$ for every $n \in \mathcal{N}$.

The first semantic criterion and usually the most elaborate one to prove is operational correspondence, which consists of a soundness and a completeness condition. *Completeness* requires that every computation of a source term can be emulated by its translation, i.e., the translation does not reduce the computations of the source term. Note that encodings often translate single source term steps into a sequence of target term steps. We call such a sequence an *emulation* of the corresponding source term step. *Soundness* requires that every computation of a target term corresponds to some computation of the corresponding source term, i.e., the translation does not introduce new computations.

¹ To keep distinct names distinct Gorla assumes that $\forall n, m \in \mathcal{N} . n \neq m$ implies $\varphi_{\llbracket \cdot \rrbracket}(n) \cap \varphi_{\llbracket \cdot \rrbracket}(m) = \emptyset$, where $\varphi_{\llbracket \cdot \rrbracket}(x)$ is simply considered as set here.

Definition 9 (Criterion 3: Operational Correspondence). Let $\llbracket \cdot \rrbracket$ be an arbitrary encoding. Then, two operational criteria are defined as follows.

Completeness: For all $S \Longrightarrow S'$, it holds that $\llbracket S \rrbracket \Longrightarrow \asymp \llbracket S' \rrbracket$.
Soundness: For all $\llbracket S \rrbracket \Longrightarrow T$, there exists an S' such that $S \Longrightarrow S'$ and $T \Longrightarrow \asymp \llbracket S' \rrbracket$.

Note that the definition of operational correspondence relies on the equivalence $\asymp$ to get rid of junk possibly left over within computations of target terms (compare to Section 2.4 for a discussion of that equivalence). Sometimes, we refer to the completeness criterion of operational correspondence as *operational completeness* and, accordingly, for the soundness criterion as *operational soundness*.

The next criterion concerns the role of infinite computations in encodings.

Definition 10 (Criterion 4: Divergence Reflection). The encoding $\llbracket \cdot \rrbracket$ reflects divergence if, for every S , $\llbracket S \rrbracket \mapsto^\omega$ implies $S \mapsto^\omega$.

The last criterion links the behaviour of source terms to the behaviour of their encodings. With Gorla [Gor10], we assume a *success* operator $\checkmark$ as part of the syntax of both the source and the target language, i.e., of π_m , π_s , and π_a . Since $\checkmark$ can not be further reduced, the operational semantics is left unchanged in all three cases. Moreover, note that $n(\checkmark) = fn(\checkmark) = bn(\checkmark) = \emptyset$, so also interplay of $\checkmark$ with the rules of structural congruence is smooth and does not require explicit treatment. The test for reachability of success is standard.

Definition 11 (Success). A process $P \in \mathcal{P}$ may lead to success, denoted as $P \Downarrow_{\checkmark}$, if (and only if) it is reducible to a process containing a top-level unguarded occurrence of $\checkmark$, i.e. $\exists P', P'' \in \mathcal{P} . P \Longrightarrow P' \wedge P' \equiv P'' \mid \checkmark$.

Note that we choose may-testing here. Finally, an encoding preserves the abstract behaviour of the source term if it and its encoding answer the tests for success in exactly the same way.

Definition 12 (Criterion 5: Success Sensitiveness). The encoding $\llbracket \cdot \rrbracket$ is success sensitive if, for every S , $S \Downarrow_{\checkmark}$ if and only if $\llbracket S \rrbracket \Downarrow_{\checkmark}$.

This criterion only links the behaviours of source terms and their literal translations, but not of their continuations. To do so, Gorla relates success sensitiveness and operational correspondence by requiring that the equivalence on the target language never relates two processes with different success behaviours.

Definition 13 (Success Respecting). $\asymp \subseteq \mathcal{P}_a \times \mathcal{P}_a$ is success respecting if, for every P and Q with $P \Downarrow_{\checkmark}$ and $Q \not\Downarrow_{\checkmark}$, it holds that $P \not\asymp Q$.

2 Correctness of the Encodings

Let us first present the full representations of the encodings $\llbracket \cdot \rrbracket_a^s$ in Figure 3 and $\llbracket \cdot \rrbracket_a^m$ in Figure 4. Note that in [Nes00, NP00] slightly different version of π_s and π_a are used, namely τ is no prefix and there are neither a match operator nor a success operator in the syntax of π_s and π_a . We choose the respective encodings to be rigid except for source terms guarded by τ . Since τ guarded terms can reduce without a communication partner, we implement their translation by a simple test-statement on their sum lock in both encodings.

In the following we will argue for the correctness of these encodings with respect to the criteria of Gorla presented in Section 1.3.

2.1 Structural Criteria

The first two criteria to prove are the structural criteria; compositionality and name invariance. An encoding is compositional if it defines a fixed context for each operator including holes for the translation of its parameters. By Definition 7 of compositionality the context is allowed to depend on the free names of the parameters. However, both presented encodings, $\llbracket \cdot \rrbracket_a^s$ and $\llbracket \cdot \rrbracket_a^m$, do not use that feature, i.e., the contexts do not depend on any names. By Figure 3 and Figure 4 both encodings are obviously compositional.

Let us have a closer look at the contexts. In the encodings of restriction, matching and success the context is used only to translate source term names according to the renaming policy. Apart from that the encodings are rigid. The encoding of the sum operator inserts a positive instantiation of a fresh sum lock and splits up the encodings of the summands in parallel because there is no sum operator in the target language. Therefore of course we have

$$\begin{aligned}
\llbracket (\nu x) P \rrbracket_a^s &\triangleq (\nu \varphi_a^s(x)) \llbracket P \rrbracket_a^s \\
\llbracket P \mid Q \rrbracket_a^s &\triangleq \llbracket P \rrbracket_a^s \mid \llbracket Q \rrbracket_a^s \\
\llbracket [a = b] P \rrbracket_a^s &\triangleq [\varphi_a^s(a) = \varphi_a^s(b)] \llbracket P \rrbracket_a^s \\
\left[\left[\sum_{i \in I} \pi_i . P_i \right] \right]_a^s &\triangleq (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I} \llbracket \pi_i . P_i \rrbracket_a^s \right) \\
\llbracket \tau . P \rrbracket_a^s &\triangleq \text{test } l \text{ then } (\bar{l} \langle \perp \rangle \mid \llbracket P \rrbracket_a^s) \text{ else } \bar{l} \langle \perp \rangle \\
\llbracket \overline{y} \langle z \rangle . P \rrbracket_a^s &\triangleq (\nu s) \left(\overline{\varphi_a^s(y)} \langle l, s, \varphi_a^s(z) \rangle \mid s . \llbracket P \rrbracket_a^s \right) \\
\llbracket y(x) . P \rrbracket_a^s &\triangleq (\nu r) \left(\bar{r} \mid r^* . \varphi_a^s(y) (l', s, \varphi_a^s(x)) . \text{test } l \text{ then test } l' \text{ then } \bar{l} \langle \perp \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \mid \llbracket P \rrbracket_a^s \right. \\
&\quad \left. \text{else } \bar{l} \langle \top \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{r} \right. \\
&\quad \left. \text{else } \bar{l} \langle \perp \rangle \mid \overline{\varphi_a^s(y)} \langle l', s, \varphi_a^s(x) \rangle \right) \\
\llbracket y^*(x) . P \rrbracket_a^s &\triangleq \varphi_a^s(y)^*(l, s, \varphi_a^s(x)) . \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \bar{s} \mid \llbracket P \rrbracket_a^s \text{ else } \bar{l} \langle \perp \rangle \\
\llbracket \checkmark \rrbracket_a^s &\triangleq \checkmark
\end{aligned}$$

Here φ_a^s is some arbitrary injective substitution such that $\forall n \in \mathcal{N} . \varphi_a^s(n) \cap \{l, l', r, s\} = \emptyset$.

Fig. 3. Encoding from π_s into π_a .

to consider the sum operator as binary operator with an index set and a set of its summands as parameters, or as unary operator with the set or list² of its summands as parameter. We left the question whether there is an encoding from π_m into π_a with the binary sum operator as an open question to further research. The encodings of input and output guarded terms and the encoding of terms guarded by τ introduce rather small contexts. However, in case of $\llbracket \cdot \rrbracket_a^m$ the contexts introduced to translate the binary parallel operator and replicated input are rather complicated and huge. Remember that we claim in Section 1.3 that the parallel operator is binary. Comparing its encoding with the encoding of the sum operator we observe that this claim may be crucial because it forbids the introduction of a global coordinator for all parallel terms as the sum lock is for all the summands of a sum.

Name invariance follows by the fact that names are translated into single names again and that conflicts between names used by the encoding functions and translated source term names are ruled out by the renaming policy.

Lemma 1. *The encoding $\llbracket \cdot \rrbracket_a^s$ is name invariant.*

Proof. By Definition 8 it suffice to show, that:

$$\forall S \in \mathcal{P}_s . \forall \sigma \subseteq \mathcal{N} . \exists \sigma' \subseteq \mathcal{N} . \llbracket \sigma(S) \rrbracket_a^s \equiv_\alpha \sigma'(\llbracket S \rrbracket_a^s) \wedge \forall z \in \mathcal{N} . \varphi_a^s(\sigma(z)) = \sigma'(\varphi_a^s(z))$$

Without loss of generality let $\sigma = \{y_1/x_1, \dots, y_n/x_n\}$ for some $n \in \mathbb{N}$. We choose

$$\sigma' \triangleq \left\{ \varphi_a^s(y_1)/\varphi_a^s(x_1), \dots, \varphi_a^s(y_n)/\varphi_a^s(x_n) \right\}.$$

So $\forall z \in \mathcal{N} . \varphi_a^s(\sigma(z)) = \sigma'(\varphi_a^s(z))$. We proceed with an induction over the structure of S .

Base Case: Since $\mathbf{n}(\checkmark) = \emptyset = \mathbf{n}(\mathbf{0})$ and $\mathbf{fn}((\nu l) \bar{l} \langle \top \rangle) = \emptyset$, we have $\llbracket \sigma(\checkmark) \rrbracket_a^s = \llbracket \checkmark \rrbracket_a^s = \checkmark = \sigma'(\checkmark) = \sigma'(\llbracket \checkmark \rrbracket_a^s)$ and $\llbracket \sigma(\mathbf{0}) \rrbracket_a^s = \llbracket \mathbf{0} \rrbracket_a^s = (\nu l) \bar{l} \langle \top \rangle = \sigma'((\nu l) \bar{l} \langle \top \rangle) = \sigma'(\llbracket \mathbf{0} \rrbracket_a^s)$.

Induction Hypothesis: $\forall S \in \mathcal{P}_s . \forall \sigma \subseteq \mathcal{N} . \exists \sigma' \subseteq \mathcal{N} . \llbracket \sigma(S) \rrbracket_a^s \equiv_\alpha \sigma'(\llbracket S \rrbracket_a^s)$

² Usually an unordered set of summands suffice to describe a sum since usually we consider sums as being reflexive and symmetric, i.e., $A + A = A$ and $A + B = B + A$. If for some reasons we have to abandon reflexivity and/or symmetry, e.g. in case of a randomised version of the calculi, an ordered list might be the better choice to describe a sum.

$$\begin{aligned}
\llbracket (\nu x) P \rrbracket_a^m &\triangleq (\nu \varphi_a^m(x)) \llbracket P \rrbracket_a^m \\
\llbracket P \mid Q \rrbracket_a^m &\triangleq (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i) (\\
&\quad (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid p_i \rightarrow \{m_i, p_i, up\} \mid p_o \rightarrow \{m_o, p_o, up\}) \\
&\quad \mid (\nu p_o, p_i) (\llbracket Q \rrbracket_a^m \\
&\quad \mid \overline{c_o} \langle m_i \rangle \mid c_o^* (m_i) . p_o (y, l_s, s, z) . (\\
&\quad \quad (\nu m_{i, up}) (m_i^* (y', l_r, r) . ([y' = y] \bar{r} \langle l_r, l_s, l_s, s, z \rangle \mid \overline{m_{i, up}} \langle y', l_r, r \rangle)) \\
&\quad \quad \mid (\nu m_i) (m_{i, up} \rightarrow m_i \mid \overline{c_o} \langle m_i \rangle)) \\
&\quad \mid \overline{p_o, up} \langle y, l_s, s, z \rangle) \\
&\quad \mid \overline{c_i} \langle m_o \rangle \mid c_i^* (m_o) . p_i (y, l_r, r) . (\\
&\quad \quad (\nu m_{o, up}) (m_o^* (y', l_s, s, z) . ([y' = y] \bar{r} \langle l_s, l_r, l_s, s, z \rangle \mid \overline{m_{o, up}} \langle y', l_s, s, z \rangle)) \\
&\quad \quad \mid (\nu m_o) (m_{o, up} \rightarrow m_o \mid \overline{c_i} \langle m_o \rangle)) \\
&\quad \mid \overline{p_{i, up}} \langle y, l_r, r \rangle)) \\
&\quad \mid p_o, up \rightarrow p_o \mid p_{i, up} \rightarrow p_i) \\
\llbracket [a = b] P \rrbracket_a^m &\triangleq [\varphi_a^m(a) = \varphi_a^m(b)] \llbracket P \rrbracket_a^m \\
\llbracket \sum_{i \in I} \pi_i . P_i \rrbracket_a^m &\triangleq (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I} \llbracket \pi_i . P_i \rrbracket_a^m \right) \\
\llbracket \tau . P \rrbracket_a^m &\triangleq \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \llbracket P \rrbracket_a^m \text{ else } \bar{l} \langle \perp \rangle \\
\llbracket \bar{y} \langle z \rangle . P \rrbracket_a^m &\triangleq (\nu s) (\overline{p_o} \langle \varphi_a^m(y), l, s, \varphi_a^m(z) \rangle \mid s . \llbracket P \rrbracket_a^m) \\
\llbracket y(x) . P \rrbracket_a^m &\triangleq (\nu r) (\overline{p_i} \langle \varphi_a^m(y), l, r \rangle \mid r^* (l_1, l_2, -, s, \varphi_a^m(x)) . \\
&\quad \text{test } l_1 \text{ then } (\text{test } l_2 \text{ then } \bar{l}_1 \langle \perp \rangle \mid \bar{l}_2 \langle \perp \rangle \mid \bar{s} \mid \llbracket P \rrbracket_a^m \text{ else } \bar{l}_1 \langle \top \rangle \mid \bar{l}_2 \langle \perp \rangle) \text{ else } \bar{l}_1 \langle \perp \rangle) \\
\llbracket y^*(x) . P \rrbracket_a^m &\triangleq (\nu l, r, c_{r1}, c_{r2}, r_o, r_i) (\\
&\quad \overline{p_i} \langle \varphi_a^s(y), l, r \rangle \mid r^* (-, -, l_s, s, \varphi_a^s(x)) . \text{test } l_s \text{ then } \bar{l}_s \langle \perp \rangle \mid \bar{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x) \rangle \text{ else } \bar{l}_s \langle \perp \rangle \\
&\quad \mid \overline{r_i} \langle \varphi_a^s(y), l, r \rangle \mid \bar{l} \langle \top \rangle \mid \overline{c_{r2}} \langle r_o, r_i \rangle \\
&\quad \mid c_{r1}^* (\varphi_a^m(x)) . c_{r2} (r_o, r_i) . (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_{i, up}) (\\
&\quad \quad r_o \rightarrow \{m_o, r_o, up\} \mid r_i \rightarrow \{m_i, r_i, up\} \\
&\quad \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \\
&\quad \mid \overline{c_o} \langle m_i \rangle \mid c_o^* (m_i) . p_o (y, l_s, s, z) . (\\
&\quad \quad (\nu m_{i, up}) (m_i^* (y', l_r, r) . ([y = y'] \bar{r} \langle l_r, l_s, l_s, s, z \rangle \mid \overline{m_{i, up}} \langle y', l_r, r \rangle)) \\
&\quad \quad \mid (\nu m_i) (m_{i, up} \rightarrow m_i \mid \overline{c_o} \langle m_i \rangle)) \\
&\quad \mid \overline{p_o, up} \langle y, l_s, s, z \rangle) \\
&\quad \mid \overline{c_i} \langle m_o \rangle \mid c_i^* (m_o) . p_i (y, l_r, r) . (\\
&\quad \quad (\nu m_{o, up}) (m_o^* (y', l_s, s, z) . ([y = y'] \bar{r} \langle l_s, l_r, l_s, s, z \rangle \mid \overline{m_{o, up}} \langle y', l_s, s, z \rangle)) \\
&\quad \quad \mid (\nu m_o) (m_{o, up} \rightarrow m_o \mid \overline{c_i} \langle m_o \rangle)) \\
&\quad \mid \overline{p_{i, up}} \langle y, l_r, r \rangle) \\
&\quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o, r_i \rangle \mid p_o, up \rightarrow \{p_o, r_o\} \mid r_o, up \rightarrow r_o \mid p_{i, up} \rightarrow \{p_i, r_i\} \mid r_{i, up} \rightarrow r_i)) \\
\llbracket \check \rrbracket_a^s &\triangleq \check
\end{aligned}$$

Here φ_a^m is some arbitrary injective substitution such that $\forall n \in \mathcal{N} . \varphi_a^m(n) \cap N = \emptyset$, where N is the set of reserved names, i.e., $N = \{p_o, p_i, p_o, up, p_i, up, m_o, m_i, m_o, up, m_i, up, c_o, c_i, l, l_s, l_r, l_1, l_2, s, r, c_{r1}, c_{r2}, r_i, r_o, r_{i, up}, r_o, up, y, y', z, t, f\}$.

Fig. 4. Encoding $\llbracket \cdot \rrbracket_a^m$ from π_m into π_a .

Induction Step: Let $x' \in \mathcal{N}$ be such that $x' \notin \mathbf{n}(\sigma) \cup \mathbf{fn}(P)$. Then $\varphi_a^m(x') \notin \mathbf{n}(\sigma)$. Moreover, since $\forall n \in \mathcal{N} \cdot \varphi_a^m(n) \notin \{l, l', r, s\}$, we have $\mathbf{n}(\sigma') \cap \{l, l', r, s\} = \emptyset$. Note that:

$$\begin{aligned}
\llbracket \sigma \left(\left\{ x'/x \right\} (P) \right) \rrbracket_a^s &= \llbracket \left\{ x'/x, y_i/x_i \mid y_i/x_i \in \sigma \wedge x_i \neq x \right\} (P) \rrbracket_a^s \\
&\equiv_\alpha \left\{ \varphi_a^s(x')/\varphi_a^s(x), \varphi_a^s(y_i)/\varphi_a^s(x_i) \mid y_i/x_i \in \sigma \wedge x_i \neq x \right\} (\llbracket P \rrbracket_a^s) && \text{by IH} \\
&= \left\{ \varphi_a^s(x')/\varphi_a^s(x), \varphi_a^s(y_i)/\varphi_a^s(x_i) \mid \varphi_a^s(y_i)/\varphi_a^s(x_i) \in \sigma' \wedge \varphi_a^s(x_i) \neq \varphi_a^s(x) \right\} (\llbracket P \rrbracket_a^s) \\
&= \sigma' \left(\left\{ \varphi_a^s(x')/\varphi_a^s(x) \right\} (\llbracket P \rrbracket_a^s) \right)
\end{aligned}$$

We proceed by a case split.

Case of $S = (\nu x) P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^s &= \llbracket \sigma((\nu x) P) \rrbracket_a^s \equiv_\alpha \llbracket \sigma((\nu x') \left\{ x'/x \right\} (P)) \rrbracket_a^s = \llbracket (\nu x') \sigma \left(\left\{ x'/x \right\} (P) \right) \rrbracket_a^s \\
&= (\nu \varphi_a^s(x')) \llbracket \sigma \left(\left\{ x'/x \right\} (P) \right) \rrbracket_a^s \equiv_\alpha (\nu \varphi_a^s(x')) \sigma' \left(\left\{ \varphi_a^s(x')/\varphi_a^s(x) \right\} (\llbracket P \rrbracket_a^s) \right) \\
&= \sigma' \left((\nu \varphi_a^s(x')) \left\{ \varphi_a^s(x')/\varphi_a^s(x) \right\} (\llbracket P \rrbracket_a^s) \right) \equiv_\alpha \sigma'((\nu \varphi_a^s(x)) \llbracket P \rrbracket_a^s) = \sigma'(\llbracket S \rrbracket_a^s).
\end{aligned}$$

Case of $S = P \mid Q$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^s &= \llbracket \sigma(P \mid Q) \rrbracket_a^s = \llbracket \sigma(P) \mid \sigma(Q) \rrbracket_a^s = \llbracket \sigma(P) \rrbracket_a^s \mid \llbracket \sigma(Q) \rrbracket_a^s \equiv_\alpha \sigma'(\llbracket P \rrbracket_a^s) \mid \sigma'(\llbracket Q \rrbracket_a^s) \\
&= \sigma'(\llbracket P \rrbracket_a^s \mid \llbracket Q \rrbracket_a^s) = \sigma'(\llbracket P \mid Q \rrbracket_a^s).
\end{aligned}$$

Case of $S = [a = b] P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^s &= \llbracket \sigma([a = b] P) \rrbracket_a^s = \llbracket [\sigma(a) = \sigma(b)] \sigma(P) \rrbracket_a^s = [\varphi_a^s(\sigma(a)) = \varphi_a^s(\sigma(b))] \llbracket \sigma(P) \rrbracket_a^s \\
&\equiv_\alpha [\sigma'(\varphi_a^s(a)) = \sigma'(\varphi_a^s(b))] \sigma'(\llbracket P \rrbracket_a^s) = \sigma'([\varphi_a^s(a) = \varphi_a^s(b)] \llbracket P \rrbracket_a^s) = \sigma'(\llbracket S \rrbracket_a^s).
\end{aligned}$$

Case of $S = \sum_{i \in I} \pi_i.P_i$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^s &= \llbracket \sigma \left(\sum_{i \in I} \pi_i.P_i \right) \rrbracket_a^s = \llbracket \sum_{i \in I} \sigma(\pi_i.P_i) \rrbracket_a^s = (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I} \llbracket \sigma(\pi_i.P_i) \rrbracket_a^s \right) \\
&\equiv_\alpha (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I} \sigma'(\llbracket \pi_i.P_i \rrbracket_a^s) \right) = \sigma' \left((\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I} \llbracket \pi_i.P_i \rrbracket_a^s \right) \right) = \sigma'(\llbracket S \rrbracket_a^s).
\end{aligned}$$

Case of $S = \tau.P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^s &= \llbracket \sigma(\tau.P) \rrbracket_a^s = \llbracket \tau.\sigma(P) \rrbracket_a^s = \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \llbracket \sigma(P) \rrbracket_a^s \text{ else } \bar{l} \langle \perp \rangle \\
&\equiv_\alpha \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \sigma'(\llbracket P \rrbracket_a^s) \text{ else } \bar{l} \langle \perp \rangle = \sigma'(\text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \llbracket P \rrbracket_a^s \text{ else } \bar{l} \langle \perp \rangle) \\
&= \sigma'(\llbracket S \rrbracket_a^s).
\end{aligned}$$

Case of $S = \bar{y} \langle z \rangle . P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^s &= \llbracket \sigma(\bar{y} \langle z \rangle . P) \rrbracket_a^s = \llbracket \overline{\sigma(y)} \langle \sigma(z) \rangle . \sigma(P) \rrbracket_a^s \\
&= (\nu s) \left(\overline{\varphi_a^s(\sigma(y))} \langle l, s, \varphi_a^s(\sigma(x)) \rangle \mid \text{test } s \text{ then } \llbracket \sigma(P) \rrbracket_a^s \text{ else } \mathbf{0} \right) \\
&\equiv_\alpha (\nu s) \left(\overline{\sigma'(\varphi_a^s(y))} \langle l, s, \sigma'(\varphi_a^s(x)) \rangle \mid \text{test } s \text{ then } \sigma'(\llbracket P \rrbracket_a^s) \text{ else } \mathbf{0} \right) \\
&= \sigma' \left((\nu s) \left(\overline{\varphi_a^s(y)} \langle l, s, \varphi_a^s(x) \rangle \mid \text{test } s \text{ then } \llbracket P \rrbracket_a^s \text{ else } \mathbf{0} \right) \right) = \sigma'(\llbracket S \rrbracket_a^s).
\end{aligned}$$

Case of $S = y(x).P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^s &= \llbracket \sigma(y(x).P) \rrbracket_a^s \equiv_\alpha \llbracket \sigma\left(y(x') \cdot \left\{x'/x\right\}(P)\right) \rrbracket_a^s = \llbracket \sigma(y)(x') \cdot \sigma\left(\left\{x'/x\right\}(P)\right) \rrbracket_a^s \\
&= (\nu r) (\bar{r} \mid r^* \cdot \varphi_a^s(\sigma(y))(l', s, \varphi_a^s(x')) \cdot \\
&\quad \text{test } l \text{ then test } l' \text{ then } \bar{l} \langle \perp \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \langle \top \rangle \mid \llbracket \sigma\left(\left\{x'/x\right\}(P)\right) \rrbracket_a^s \text{ else } \bar{l} \langle \top \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \mid \bar{r} \\
&\quad \text{else } \bar{l} \langle \perp \rangle \mid \overline{\varphi_a^s(\sigma(y))} \langle l', s, \varphi_a^s(x') \rangle) \\
&\equiv_\alpha (\nu r) (\bar{r} \mid r^* \cdot \sigma'(\varphi_a^s(y))(l', s, \varphi_a^s(x')) \cdot \\
&\quad \text{test } l \text{ then test } l' \text{ then } \bar{l} \langle \perp \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \langle \top \rangle \mid \sigma'\left(\left\{\varphi_a^s(x')/\varphi_a^s(x)\right\}(\llbracket P \rrbracket_a^s)\right) \\
&\quad \text{else } \bar{l} \langle \top \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \mid \bar{r} \\
&\quad \text{else } \bar{l} \langle \perp \rangle \mid \overline{\sigma'(\varphi_a^s(y))} \langle l', s, \varphi_a^s(x') \rangle) \\
&= \sigma'((\nu r) (\bar{r} \mid r^* \cdot \varphi_a^s(y)(l', s, \varphi_a^s(x')) \cdot \\
&\quad \text{test } l \text{ then test } l' \text{ then } \bar{l} \langle \perp \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \langle \top \rangle \mid \left\{\varphi_a^s(x')/\varphi_a^s(x)\right\}(\llbracket P \rrbracket_a^s) \\
&\quad \text{else } \bar{l} \langle \top \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \mid \bar{r} \\
&\quad \text{else } \bar{l} \langle \perp \rangle \mid \overline{\varphi_a^s(y)} \langle l', s, \varphi_a^s(x') \rangle)) \\
&\equiv_\alpha \sigma'((\nu r) (\bar{r} \mid r^* \cdot \varphi_a^s(y)(l', s, \varphi_a^s(x')) \cdot \\
&\quad \text{test } l \text{ then test } l' \text{ then } \bar{l} \langle \perp \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \langle \top \rangle \mid \llbracket P \rrbracket_a^s \text{ else } \bar{l} \langle \top \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \mid \bar{r} \\
&\quad \text{else } \bar{l} \langle \perp \rangle \mid \overline{\varphi_a^s(y)} \langle l', s, \varphi_a^s(x') \rangle)) \\
&= \sigma'(\llbracket S \rrbracket_a^s).
\end{aligned}$$

Case of $S = y^*(x).P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^s &= \llbracket \sigma(y^*(x).P) \rrbracket_a^s \equiv_\alpha \llbracket \sigma\left(y^*(x') \cdot \left\{x'/x\right\}(P)\right) \rrbracket_a^s = \llbracket \sigma(y)^*(x') \cdot \sigma\left(\left\{x'/x\right\}(P)\right) \rrbracket_a^s \\
&= \varphi_a^s(\sigma(y))^*(l, s, \varphi_a^s(x')) \cdot \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \mid \llbracket \sigma\left(\left\{x'/x\right\}(P)\right) \rrbracket_a^s \text{ else } \bar{l} \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \\
&\equiv_\alpha \sigma'(\varphi_a^s(y))^*(l, s, \varphi_a^s(x')) \cdot \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \mid \sigma'\left(\left\{\varphi_a^s(x')/\varphi_a^s(x)\right\}(\llbracket P \rrbracket_a^s)\right) \text{ else } \bar{l} \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \\
&= \sigma'\left(\varphi_a^s(y)^*(l, s, \varphi_a^s(x')) \cdot \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \mid \left\{\varphi_a^s(x')/\varphi_a^s(x)\right\}(\llbracket P \rrbracket_a^s) \text{ else } \bar{l} \langle \perp \rangle \mid \bar{s} \langle \perp \rangle\right) \\
&\equiv_\alpha \sigma'\left(\varphi_a^s(y)^*(l, s, \varphi_a^s(x')) \cdot \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \bar{s} \langle \perp \rangle \mid \llbracket P \rrbracket_a^s \text{ else } \bar{l} \langle \perp \rangle \mid \bar{s} \langle \perp \rangle\right) \\
&= \sigma'(\llbracket S \rrbracket_a^s).
\end{aligned}$$

□

Lemma 2. The encoding $\llbracket \cdot \rrbracket_a^m$ is name invariant.

Proof. By Definition 8 it suffice to show, that:

$$\forall S \in \mathcal{P}_m. \forall \sigma \subseteq \mathcal{N}. \exists \sigma' \subseteq \mathcal{N}. \llbracket \sigma(S) \rrbracket_a^m \equiv_\alpha \sigma'(\llbracket S \rrbracket_a^m) \wedge \forall z \in \mathcal{N}. \varphi_a^m(\sigma(z)) = \sigma'(\varphi_a^m(z))$$

Without loss of generality let $\sigma = \{y^1/x_1, \dots, y^n/x_n\}$ for some $n \in \mathbb{N}$. We choose

$$\sigma' \triangleq \left\{ \varphi_a^m(y_1)/\varphi_a^m(x_1), \dots, \varphi_a^m(y_n)/\varphi_a^m(x_n) \right\}.$$

So $\forall z \in \mathcal{N}. \varphi_a^m(\sigma(z)) = \sigma'(\varphi_a^m(z))$. We proceed with an induction over the structure of S .

Base Case: Since $n(\checkmark) = \emptyset = n(\mathbf{0})$ and $\text{fn}((\nu l) \bar{l} \langle \top \rangle) = \emptyset$, we have $\llbracket \sigma(\checkmark) \rrbracket_a^m = \llbracket \checkmark \rrbracket_a^m = \checkmark = \sigma'(\checkmark) = \sigma'(\llbracket \checkmark \rrbracket_a^m)$ and $\llbracket \sigma(\mathbf{0}) \rrbracket_a^m = \llbracket \mathbf{0} \rrbracket_a^m = (\nu l) \bar{l} \langle \top \rangle = \sigma'((\nu l) \bar{l} \langle \top \rangle) = \sigma'(\llbracket \mathbf{0} \rrbracket_a^m)$.

Induction Hypothesis: $\forall S \in \mathcal{P}_m. \forall \sigma \subseteq \mathcal{N}. \exists \sigma' \subseteq \mathcal{N}. \llbracket \sigma(S) \rrbracket_a^m \equiv_\alpha \sigma'(\llbracket S \rrbracket_a^m)$

Induction Step: Let $x' \in \mathcal{N}$ be such that $x' \notin n(\sigma) \cup \text{fn}(P)$. Then $\varphi_a^m(x') \notin n(\sigma)$. Moreover, since $\forall z \in \mathcal{N}. \varphi_a^m(z) \notin N$, where

$$N = \{p_o, p_i, p_{o,up}, p_{i,up}, m_o, m_i, m_{o,up}, m_{i,up}, c_o, c_i, l, l_s, l_r, l_1, l_2, s, r, c_{r1}, c_{r2}, r_i, r_o, r_{i,up}, r_{o,up}, y, y', z, t, f\},$$

we have $n(\sigma') \cap N = \emptyset$. Note that:

$$\begin{aligned}
\llbracket \sigma \left(\left\{ x'/x \right\} (P) \right) \rrbracket_a^m &= \llbracket \left\{ x'/x, y_i/x_i \mid y_i/x_i \in \sigma \wedge x_i \neq x \right\} (P) \rrbracket_a^m \\
&\equiv_\alpha \left\{ \varphi_a^m(x')/\varphi_a^m(x), \varphi_a^m(y_i)/\varphi_a^m(x_i) \mid y_i/x_i \in \sigma \wedge x_i \neq x \right\} (\llbracket P \rrbracket_a^m) && \text{by IH} \\
&= \left\{ \varphi_a^m(x')/\varphi_a^m(x), \varphi_a^m(y_i)/\varphi_a^m(x_i) \mid \varphi_a^m(y_i)/\varphi_a^m(x_i) \in \sigma' \wedge \varphi_a^m(x_i) \neq \varphi_a^m(x) \right\} (\llbracket P \rrbracket_a^m) \\
&= \sigma' \left(\left\{ \varphi_a^m(x')/\varphi_a^m(x) \right\} (\llbracket P \rrbracket_a^m) \right)
\end{aligned}$$

We proceed by a case split.

Case of $S = (\nu x) P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^m &= \llbracket \sigma((\nu x) P) \rrbracket_a^m \equiv_\alpha \llbracket \sigma \left((\nu x') \left\{ x'/x \right\} (P) \right) \rrbracket_a^m = \llbracket (\nu x') \sigma \left(\left\{ x'/x \right\} (P) \right) \rrbracket_a^m \\
&= (\nu \varphi_a^m(x')) \llbracket \sigma \left(\left\{ x'/x \right\} (P) \right) \rrbracket_a^m \equiv_\alpha (\nu \varphi_a^m(x')) \sigma' \left(\left\{ \varphi_a^m(x')/\varphi_a^m(x) \right\} (\llbracket P \rrbracket_a^m) \right) \\
&= \sigma' \left((\nu \varphi_a^m(x')) \left\{ \varphi_a^m(x')/\varphi_a^m(x) \right\} (\llbracket P \rrbracket_a^m) \right) \equiv_\alpha \sigma' ((\nu \varphi_a^m(x)) \llbracket P \rrbracket_a^m) = \sigma' (\llbracket S \rrbracket_a^m).
\end{aligned}$$

Case of $S = P \mid Q$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^m &= \llbracket \sigma(P \mid Q) \rrbracket_a^m = \llbracket \sigma(P) \mid \sigma(Q) \rrbracket_a^m \\
&= (\nu c, m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad \bar{c} \mid (\nu p_o, p_i) (\llbracket \sigma(P) \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \mid (\nu p_o, p_i) (\llbracket \sigma(Q) \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid \text{pushReq}) \\
&\equiv_\alpha (\nu c, m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad \bar{c} \mid (\nu p_o, p_i) (\sigma(\llbracket P \rrbracket_a^m) \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \mid (\nu p_o, p_i) (\sigma'(\llbracket Q \rrbracket_a^m) \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid \text{pushReq}) \\
&= \sigma' \left((\nu c, m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\right. \\
&\quad \bar{c} \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \mid (\nu p_o, p_i) (\llbracket Q \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \left. \mid \text{pushReq}) \right) \\
&= \sigma' (\llbracket S \rrbracket_a^m).
\end{aligned}$$

Case of $S = [a = b] P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^m &= \llbracket \sigma([a = b] P) \rrbracket_a^m = \llbracket [\sigma(a) = \sigma(b)] \sigma(P) \rrbracket_a^m = [\varphi_a^m(\sigma(a)) = \varphi_a^m(\sigma(b))] \llbracket \sigma(P) \rrbracket_a^m \\
&\equiv_\alpha [\sigma'(\varphi_a^m(a)) = \sigma'(\varphi_a^m(b))] \sigma'(\llbracket P \rrbracket_a^m) = \sigma'([\varphi_a^m(a) = \varphi_a^m(b)] \llbracket P \rrbracket_a^m) = \sigma'(\llbracket S \rrbracket_a^m).
\end{aligned}$$

Case of $S = \sum_{i \in I} \pi_i.P_i$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^m &= \llbracket \sigma \left(\sum_{i \in I} \pi_i.P_i \right) \rrbracket_a^m = \llbracket \sum_{i \in I} \sigma(\pi_i.P_i) \rrbracket_a^m = (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I} \llbracket \sigma(\pi_i.P_i) \rrbracket_a^m \right) \\
&\equiv_\alpha (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I} \sigma'(\llbracket \pi_i.P_i \rrbracket_a^m) \right) = \sigma' \left((\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I} \llbracket \pi_i.P_i \rrbracket_a^m \right) \right) = \sigma'(\llbracket S \rrbracket_a^m).
\end{aligned}$$

Case of $S = \tau.P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^m &= \llbracket \sigma(\tau.P) \rrbracket_a^m = \llbracket \tau.\sigma(P) \rrbracket_a^m = \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \llbracket \sigma(P) \rrbracket_a^m \text{ else } \bar{l} \langle \perp \rangle \\
&\equiv_\alpha \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \sigma'(\llbracket P \rrbracket_a^m) \text{ else } \bar{l} \langle \perp \rangle = \sigma'(\text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \llbracket P \rrbracket_a^m \text{ else } \bar{l} \langle \perp \rangle) \\
&= \sigma'(\llbracket S \rrbracket_a^m).
\end{aligned}$$

Case of $S = \overline{y} \langle z \rangle . P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^m &= \llbracket \sigma(\overline{y} \langle z \rangle . P) \rrbracket_a^m = \llbracket \overline{\sigma(y)} \langle \sigma(z) \rangle . \sigma(P) \rrbracket_a^m \\
&= (\nu s) (\overline{p_o} \langle \varphi_a^m(\sigma(y)) \rangle, l, s, \varphi_a^m(\sigma(z))) \mid s. \llbracket \sigma(P) \rrbracket_a^m \\
&\equiv_\alpha (\nu s) (\overline{p_o} \langle \sigma'(\varphi_a^m(y)) \rangle, l, s, \sigma'(\varphi_a^m(z))) \mid s. \sigma'(\llbracket P \rrbracket_a^m) \\
&= \sigma'((\nu s) (\overline{p_o} \langle \varphi_a^m(y) \rangle, l, s, \varphi_a^m(z))) \mid s. \llbracket P \rrbracket_a^m = \sigma'(\llbracket S \rrbracket_a^m).
\end{aligned}$$

Case of $S = y(x) . P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^m &= \llbracket \sigma(y(x) . P) \rrbracket_a^m \equiv_\alpha \llbracket \sigma(y(x') . \{x'/x\}(P)) \rrbracket_a^m = \llbracket \sigma(y)(x') . \sigma(\{x'/x\}(P)) \rrbracket_a^m \\
&= (\nu r) (\overline{p_i} \langle \varphi_a^m(\sigma(y)) \rangle, l, r) \mid r^*(l_1, l_2, -, s, \varphi_a^m(x')). \\
&\quad \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1} \langle \perp \rangle \mid \overline{l_2} \langle \perp \rangle \mid \overline{s} \mid \llbracket \sigma(\{x'/x\}(P)) \rrbracket_a^m \text{ else } \overline{l_1} \langle \top \rangle \mid \overline{l_2} \langle \perp \rangle \\
&\quad \text{else } \overline{l_1} \langle \perp \rangle) \\
&\equiv_\alpha (\nu r) (\overline{p_i} \langle \sigma'(\varphi_a^m(y)) \rangle, l, r) \mid r^*(l_1, l_2, -, s, \varphi_a^m(x')). \\
&\quad \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1} \langle \perp \rangle \mid \overline{l_2} \langle \perp \rangle \mid \overline{s} \mid \sigma'(\{ \varphi_a^m(x') / \varphi_a^m(x) \} (\llbracket P \rrbracket_a^m)) \text{ else } \overline{l_1} \langle \top \rangle \mid \overline{l_2} \langle \perp \rangle \\
&\quad \text{else } \overline{l_1} \langle \perp \rangle) \\
&= \sigma'((\nu r) (\overline{p_i} \langle \varphi_a^m(y) \rangle, l, r) \mid r^*(l_1, l_2, -, s, \varphi_a^m(x')). \\
&\quad \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1} \langle \perp \rangle \mid \overline{l_2} \langle \perp \rangle \mid \overline{s} \mid \{ \varphi_a^m(x') / \varphi_a^m(x) \} (\llbracket P \rrbracket_a^m) \text{ else } \overline{l_1} \langle \top \rangle \mid \overline{l_2} \langle \perp \rangle \\
&\quad \text{else } \overline{l_1} \langle \perp \rangle)) \\
&\equiv_\alpha \sigma'((\nu r) (\overline{p_i} \langle \varphi_a^m(y) \rangle, l, r) \mid r^*(l_1, l_2, -, s, \varphi_a^m(x')). \\
&\quad \text{test } l_1 \text{ then (test } l_2 \text{ then } \overline{l_1} \langle \perp \rangle \mid \overline{l_2} \langle \perp \rangle \mid \overline{s} \mid \llbracket P \rrbracket_a^m \text{ else } \overline{l_1} \langle \top \rangle \mid \overline{l_2} \langle \perp \rangle) \text{ else } \overline{l_1} \langle \perp \rangle)) \\
&= \sigma'(\llbracket S \rrbracket_a^m).
\end{aligned}$$

Case of $S = y^*(x) . P$: Then

$$\begin{aligned}
\llbracket \sigma(S) \rrbracket_a^m &= \llbracket \sigma(y^*(x) . P) \rrbracket_a^m \equiv_\alpha \llbracket \sigma(y^*(x') . \{x'/x\}(P)) \rrbracket_a^m = \llbracket \sigma(y)^*(x') . \sigma(\{x'/x\}(P)) \rrbracket_a^m \\
&= (\nu l, r, c_{r1}, c_{r2}, r_o, r_i) (\\
&\quad \overline{p_i} \langle \varphi_a^m(\sigma(y)) \rangle, l, r) \mid r^*(-, -, l_s, s, \varphi_a^m(x')) . \text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x') \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\
&\quad \mid \overline{r_i} \langle \varphi_a^m(\sigma(y)) \rangle, l, r) \mid \overline{l} \langle \top \rangle \mid \overline{c_{r2}} \langle r_o, r_i \rangle \\
&\quad \mid c_{r1}^*(\varphi_a^m(x')) . c_{r2}(r_o, r_i) . (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad \text{pushReqIn} \\
&\quad \mid (\nu p_o, p_i) (\llbracket \sigma(\{x'/x\}(P)) \rrbracket_a^m \\
&\quad \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o, r_i \rangle \mid \text{pushReqOut}))) \\
&\equiv_\alpha (\nu l, r, c_{r1}, c_{r2}, r_o, r_i) (\\
&\quad \overline{p_i} \langle \sigma'(\varphi_a^m(y)) \rangle, l, r) \mid r^*(-, -, l_s, s, \varphi_a^m(x')) . \text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x') \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\
&\quad \mid \overline{r_i} \langle \sigma'(\varphi_a^m(y)) \rangle, l, r) \mid \overline{l} \langle \top \rangle \mid \overline{c_{r2}} \langle r_o, r_i \rangle \\
&\quad \mid c_{r1}^*(\varphi_a^m(x')) . c_{r2}(r_o, r_i) . (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad \text{pushReqIn} \\
&\quad \mid (\nu p_o, p_i) (\sigma'(\{ \varphi_a^m(x') / \varphi_a^m(x) \} (\llbracket P \rrbracket_a^m)) \\
&\quad \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o, r_i \rangle \mid \text{pushReqOut})))
\end{aligned}$$

$$\begin{aligned}
&= \sigma' \Big((\nu l, r, c_{r1}, c_{r2}, r_o, r_i) \Big(\\
&\quad \overline{p_i} \langle \varphi_a^m(y), l, r \rangle \mid r^* (-, -, l_s, s, \varphi_a^m(x')) . \text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x') \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\
&\quad \mid \overline{r_i} \langle \varphi_a^m(y), l, r \rangle \mid \overline{l} \langle \top \rangle \mid \overline{c_{r2}} \langle r_o, r_i \rangle \\
&\quad \mid c_{r1}^* (\varphi_a^m(x')) . c_{r2} (r_o, r_i) . (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) \Big(\\
&\quad \text{pushReqIn} \\
&\quad \mid (\nu p_o, p_i) \Big(\left\{ \varphi_a^m(x') / \varphi_a^m(x) \right\} (\llbracket P \rrbracket_a^m) \\
&\quad \mid \text{procRightOutReq} \mid \text{procRightInReq} \Big) \\
&\quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o, r_i \rangle \mid \text{pushReqOut}) \Big) \Big) \\
&\equiv_\alpha \sigma' \Big((\nu l, r, c_{r1}, c_{r2}, r_o, r_i) \Big(\\
&\quad \overline{p_i} \langle \varphi_a^m(y), l, r \rangle \mid r^* (-, -, l_s, s, \varphi_a^m(x)) . \text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x) \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\
&\quad \mid \overline{r_i} \langle \varphi_a^m(y), l, r \rangle \mid \overline{l} \langle \top \rangle \mid \overline{c_{r2}} \langle r_o, r_i \rangle \\
&\quad \mid c_{r1}^* (\varphi_a^m(x)) . c_{r2} (r_o, r_i) . (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) \Big(\\
&\quad \text{pushReqIn} \\
&\quad \mid (\nu p_o, p_i) \Big(\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq} \Big) \\
&\quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o, r_i \rangle \mid \text{pushReqOut}) \Big) \Big) \\
&= \sigma' (\llbracket S \rrbracket_a^m).
\end{aligned}$$

□

Analysing these proofs we observe (1) that σ' depends only on σ and the respective renaming policy, and (2) that we can prove the first case of name invariance (compare to Definition 8) for all kinds of substitutions σ , i.e., it suffice to consider equivalence modulo alpha conversion.

Corollary 1 (Encoding substitutions). *For all substitutions $\sigma = \{y_1/x_1, \dots, y_n/x_n\}$ it holds that*

$$\forall S \in \mathcal{P}_s . \llbracket \sigma(S) \rrbracket_a^s \equiv_\alpha \varphi_a^s(\sigma) (\llbracket S \rrbracket_a^s) \quad \text{and} \quad \forall S \in \mathcal{P}_m . \llbracket \sigma(S) \rrbracket_a^m \equiv_\alpha \varphi_a^m(\sigma) (\llbracket S \rrbracket_a^m),$$

where $\varphi_a^s(\sigma) = \{\varphi_a^s(y_1)/\varphi_a^s(x_1), \dots, \varphi_a^s(y_n)/\varphi_a^s(x_n)\}$ and $\varphi_a^m(\sigma) = \{\varphi_a^m(y_1)/\varphi_a^m(x_1), \dots, \varphi_a^m(y_n)/\varphi_a^m(x_n)\}$.

2.2 Basic Properties

In the following we prove correctness with respect to the three semantical criteria. We observe, that in order to do so we do not have to prove conditions on arbitrary π_a -terms but on encoded source terms and their derivatives. To simplify the argumentation we will denote such terms as *target terms*.

Definition 14 (Target Terms). *Let $T \in \mathcal{P}_a$. Then T is a target term, denoted by $T \in \mathcal{P}_a^\dagger \llbracket \cdot \rrbracket_a^m$ (or $T \in \mathcal{P}_a^\dagger \llbracket \cdot \rrbracket_a^s$), if $\exists S \in \mathcal{P}_m . T \equiv \llbracket S \rrbracket_a^m \vee \llbracket S \rrbracket_a^m \Longrightarrow T$ (or $\exists S \in \mathcal{P}_s . T \equiv \llbracket S \rrbracket_a^s \vee \llbracket S \rrbracket_a^s \Longrightarrow T$).*

Requests. Note that the encoding $\llbracket \cdot \rrbracket_a^s$ translates source term observables by adding an instantiation of a sum lock (except from observables due to replicated inputs) to keep track of the information, whether this observable is still active, i.e., whether the corresponding in- or output can still be used to emulate a source term step. Besides that additional information $\llbracket \cdot \rrbracket_a^s$ does not change the observables. In contrast, the encoding $\llbracket \cdot \rrbracket_a^m$ translates source term observables into requests, which are again augmented by sum locks. Requests are outputs with either three or four parameters. Input requests, i.e., requests that originate from the translation of an input guarded term or replicated input, are outputs with three parameters. Output requests, i.e., requests that originate from the translation of an output guarded term, are outputs with four parameters. Note that we can indeed consider any output of three or four parameters as request, because the encoding function does not use these multiplicities for other purposes (compare to Figure 4).

Definition 15 (Request). *An input request is an unguarded output with three parameters, i.e., an output of kind $\overline{y} \langle x_1, x_2, x_3 \rangle$ for some $y, x_1, x_2, x_3 \in \mathcal{N}$, and an output request is an unguarded output with four parameters, i.e., an output of kind $\overline{y} \langle x_1, x_2, x_3, x_4 \rangle$ for some $y, x_1, x_2, x_3, x_4 \in \mathcal{N}$. We refer to guarded variants of those outputs as guarded requests and to y as request channel.*

Note that the channels introduced by the encoding function are somehow well typed in the sense, that each name once used as link with multiplicity n will never appear as link with a multiplicity different from n . Because of that, it make sense to denote the channel y here as request channel, because whenever it is used as link name a request is transferred above that link. Moreover note, that the first parameter x_1 of a request is always the translation of the respective source term channel and the second parameter x_2 always refers to the sum lock that is connected to that requests, i.e., that covers the information about the liveness of the corresponding observable. Note that in case of an input request that originate from an replicated input the second parameter refers to a fake sum lock, which is never checked. In case of an input request the third parameter x_3 refers to the corresponding receiver lock and in case of an output request the third parameter x_3 refers to the corresponding sender lock and the fourth parameter x_4 is the translation of the send value.

An interesting fact is, that requests are preserved by the encoding function, i.e., each derivative of a target term has all the requests of its predecessor. Note that we consider here two requests that only differ by their link name but not their values as the same request. Requests are pushed upwards along and from right to left within the parallel structure of the term but they are never completely consumed. If the message refers to an inactive observable the respective sum lock is instantiated false to ensure that such a request can no longer be used to emulate a source term step. The corresponding output messages of the encoding, i.e., the requests, remain as junk (compare to Lemma 25).

Lemma 3 ($\llbracket \cdot \rrbracket_a^m$ preserves requests).

$$\begin{aligned} \forall T_1, T_2 \in \mathcal{P}_{al} \llbracket \cdot \rrbracket_a^m . \forall p_i, y, l, r \in \mathcal{N} . (\exists T'_1 \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . T_1 \equiv (\nu \tilde{x}) (T'_1 \mid \overline{p_i} \langle y, l, r \rangle)) \wedge T_1 \Longrightarrow T_2 \\ \text{implies } (\exists T'_2 \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \exists p_i' \in \mathcal{N} . T_2 \equiv (\nu \tilde{x}) (T'_2 \mid \overline{p_i'} \langle y, l, r \rangle)) \end{aligned}$$

and

$$\begin{aligned} \forall T_1, T_2 \in \mathcal{P}_{al} \llbracket \cdot \rrbracket_a^m . \forall p_o, y, l, s, z \in \mathcal{N} . (\exists T'_1 \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . T_1 \equiv (\nu \tilde{x}) (T'_1 \mid \overline{p_o} \langle y, l, s, z \rangle)) \wedge T_1 \Longrightarrow T_2 \\ \text{implies } (\exists T'_2 \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \exists p_o' \in \mathcal{N} . T_2 \equiv (\nu \tilde{x}) (T'_2 \mid \overline{p_o'} \langle y, l, s, z \rangle)) \end{aligned}$$

Proof. First note, that due to Figure 4 the translations of source term names are used as values only. So any in- or output of a target term is generated by the encoding function on special names reserved for the encoding. In case $T_1 = T_2$, i.e., in case the sequence $T_1 \Longrightarrow T_2$ is empty, the lemma holds trivially. Let us consider the case of a single step, i.e., $T_1 \mapsto T_2$. The Lemma then follows by induction over the number of steps in the sequence $T_1 \Longrightarrow T_2$.

Analysing the encoding function in Figure 4 we observe, that any input with three or four parameters is due to the encoding of the parallel operator or a replicated input. In case of a forwarder the lemma again trivially holds, because each forwarder immediately restores each consumed message. The only remain inputs in the encoding of a parallel operator or a replicated input are due to the processing of right requests, i.e., due to `procRightOutReq` and `procRightInReq`.

$$\begin{aligned} \text{procRightOutReq} \triangleq \overline{c_o} \langle m_i \rangle \mid c_o^* (m_i) . p_o (y, l_s, s, z) . (\\ (\nu m_{i,up}) (m_i^* (y', l_r, r) . ([y' = y] \overline{r} \langle l_r, l_s, l_s, s, z \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle) \\ \mid (\nu m_i) (m_{i,up} \rightarrow m_i \mid \overline{c_o} \langle m_i \rangle)) \\ \mid \overline{p_{o,up}} \langle y, l_s, s, z \rangle) \end{aligned}$$

In case of `procRightOutReq` there are two inputs on request channels, namely $p_o (y, l_s, s, z)$ and $m_i^* (y', l_r, r)$. In the first case, whenever a request is consumed by $p_o (y, l_s, s, z)$ it is immediately restored by $\overline{p_{o,up}} \langle y, l_s, s, z \rangle$. In the second case any consumed request is immediately restored by $\overline{m_{i,up}} \langle y', l_r, r \rangle$. So the Lemma holds. The argumentation for `procRightInReq` is similar. $\square$

A closer look at this proof and the encoding function in Figure 4 reveals, that (1) any initial request is due to the encoding of a guarded term or a replicated input and (2) any other request is a copy of an existing request. Because of that, as long as we are only interested in the values a request may carry and do not concern the link over it is currently transmitted, then we can conclude that any request originate to the encoding of a guarded term or a replicated input.

Corollary 2. Any request originates to the encoding of a guarded term or a replicated input.

Sum locks. Sum locks—for both considered encodings—are channels carrying a boolean value. They are used by the encoding functions to ensure that at most one summand of each sum is chosen for communication. Note that any channel used to transport a boolean value is a sum lock. However, since by Definition 5 at page 3 booleans and test-statements are just abbreviations, we use some simple type informations to unambiguously identify sum locks in both encodings. So, to be precise, instantiations on sum locks are inputs carrying two values, that are links with multiplicity zero. So sum locks are the only channels of multiplicity two, that carry only values of multiplicity zero.

Definition 16 (Sum lock). *Let $T \in \mathcal{P}_a[\cdot]_a^m$ (or $T \in \mathcal{P}_a[\cdot]_a^s$). A sum lock of T is a name l that is used in T as link with multiplicity two carrying two links with multiplicity zero.*

Let l be a sum lock. Then we refer to unguarded occurrences of $\bar{l}\langle\top\rangle$ as positive instantiation and accordingly to unguarded occurrences of $\bar{l}\langle\perp\rangle$ as negative instantiation of l . An instantiation of a sum lock l is either a positive or negative instantiation of l .

Note that in most of the following definitions and proofs we hide the definition of booleans as well as of the corresponding test-statement. To show that sum locks meet our intuition we prove that in each target term T there is at most one instantiation of each sum lock.

Lemma 4. *For each target term each sum lock is instantiated at most once, i.e.,*

$$\forall T \in \mathcal{P}_a[\cdot]_a^m \text{ (or } T \in \mathcal{P}_a[\cdot]_a^s) . \forall l \in \mathcal{N} . \forall T' \in \mathcal{P}_a . \forall \tilde{x} \subset \mathcal{N} . \forall b_1, b_2 \in \mathbb{B} . T \not\equiv (\nu \tilde{x}) (T' \mid \bar{l}\langle b_1 \rangle \mid \bar{l}\langle b_2 \rangle) .$$

Proof. By Figure 3 and Figure 4 this condition holds for all encoded source terms, i.e., for all target terms $\llbracket S \rrbracket_a^s$ for some $S \in \mathcal{P}_s$ or $S \in \mathcal{P}_m$, because for each sum there is exactly one positive instantiation of each sum lock and, since all sum locks appear restricted, the sum locks of different sums are different. All remaining instantiations of sum locks are guarded by a test-statement. To prove the condition for arbitrary target terms we take a closer look on these test-statements. We observe that for both encodings for each test-statement and for each of its possible outcomes the reduction of a test-statement unguards exactly one instantiation of a each sum lock that has to be consumed to reduce the respective test-statement. So for each new unguarded instantiation of a sum lock a former instantiation of the same lock was consumed.

[Nes00] proves that the encoding $\llbracket \cdot \rrbracket_a^s$ does not introduce deadlock, i.e., whenever a test-statement consumes a sum lock a new instantiation of the same lock is eventually unguarded. Moreover, it shows that a complete ordering of the sum locks as implemented in $\llbracket \cdot \rrbracket_a^m$ suffice to ensure that even in the case of source terms from $\mathcal{P}_m$ the test-statements can not cause a deadlock. So again for each consumed instantiation of a sum lock a new instantiation of the same lock is eventually unguarded. $\square$

Note that, analysing the encoding functions obviously any instantiation of a sum lock is a positive or negative instantiation. The prove of Lemma 4 also shows that (1) all instantiations of sum locks in encoded source terms are positive—negative instantiations are only due to reduction steps, (2) all sum locks are initially instantiated, and (3) for each consumed instantiation of a sum lock eventually a new instantiation is unguarded.

Corollary 3. *Any sum lock is initially instantiated positive, i.e.,*

$$\forall S \in \mathcal{P}_s . \forall l \in \mathcal{N} . \forall b \in \mathbb{B} . \forall T \in \mathcal{P}_a . \forall \tilde{x} \subset \mathcal{N} . \llbracket S \rrbracket_a^s \equiv (\nu \tilde{x}) (T \mid \bar{l}\langle b \rangle) \text{ implies } b = \top$$

and

$$\forall S \in \mathcal{P}_m . \forall l \in \mathcal{N} . \forall b \in \mathbb{B} . \forall T \in \mathcal{P}_a . \forall \tilde{x} \subset \mathcal{N} . \llbracket S \rrbracket_a^m \equiv (\nu \tilde{x}) (T \mid \bar{l}\langle b \rangle) \text{ implies } b = \top .$$

Corollary 4. *Let T be a target term, i.e., $T \in \mathcal{P}_a[\cdot]_a^s$ or $T \in \mathcal{P}_a[\cdot]_a^m$, and let $L \subset \mathcal{N}$ be the set of all sum locks of T . Then*

$$\forall l \in L . \exists T' \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \exists b \in \mathbb{B} . T \implies (\nu \tilde{x}) (T' \mid \bar{l}\langle b \rangle) .$$

In the proof of Lemma 4 we observe that new instantiations of sum locks are unguarded by test-statements. So reducing a test-statement is the only possibility to change an instantiation of sum lock. A closer look reveals that positive instantiations can be changed into negative but never the other way around.

Lemma 5. *A negative instantiation of a sum lock can not be changed into a positive instantiation, i.e.,*

$$\begin{aligned} & \forall T_1, T_2 \in \mathcal{P}_a[\cdot]_a^m \text{ (or } T_1, T_2 \in \mathcal{P}_a[\cdot]_a^s) . \forall l \in \mathcal{N} . \forall T'_1, T'_2 \in \mathcal{P}_a . \forall \tilde{x}_1, \tilde{x}_2 \subset \mathcal{N} . \forall b \in \mathbb{B} . \\ & T_1 \equiv (\nu \tilde{x}_1) (T'_1 \mid \bar{l}\langle \perp \rangle) \wedge T_1 \implies T_2 \wedge T_2 \equiv (\nu \tilde{x}_2) (T'_2 \mid \bar{l}\langle b \rangle) \text{ implies } b = \perp \end{aligned}$$

Proof. Revisiting the argumentation in the proof of Lemma 4 we observe that the reduction of a test-statement is the only way to change the instantiation of a sum lock. A closer look at the test-statements in Figure 4 and Figure 3 reveals that for both encoding functions and for each test-statements the then-case can change a positive instantiation of sum lock into negative instantiation but the else-cases always simply restore all consumed instances. Note that in case of the nested test-statement of the encoding of an input guarded term a positive instantiation of the first tested lock is changed only if the second tested lock is again positive instantiated. In this case both instantiations are changed into negative instantiations. Moreover note that all the other (single) test-statements change any consumed positive instantiation into a negative one. Because of that, it is possible to change a positive instantiation into a negative one but not the other way around. $\square$

Sender and Receiver Locks. The third parameter of an output request refers to a sender lock, while the third parameter of an input request refers to a receiver lock. In both encodings, sender and receiver locks are used to guard the encoded continuation of output or input guarded source terms or replicated inputs. Sender locks are links with multiplicity zero in both encodings, in opposite receiver locks are links with multiplicity zero in $\llbracket \cdot \rrbracket_a^s$ and five in $\llbracket \cdot \rrbracket_a^m$. Note that in $\llbracket \cdot \rrbracket_a^m$ only sender locks appear as third parameter of an output request. Since by Lemma 3 the encoding function $\llbracket \cdot \rrbracket_a^m$ preserves requests, they unambiguously define sender locks. In the encoding $\llbracket \cdot \rrbracket_a^s$ also receiver locks are links that never transport any values (compare to Figure 3). Moreover, the reserved names t and f —necessary to implement booleans—are used as links without parameters in both encodings. To distinguish them in $\llbracket \cdot \rrbracket_a^s$ note, that sender locks are used as input links, while receiver locks are used as replicated inputs only, and that in each case of a test-statement there is an unrestricted instantiation of a sum lock, whereas all instantiations of sum locks within an encoded source term appear restricted.

Definition 17 (Sender Lock). *Let $T \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^s$. Then any name s is a sender lock of T if*

$$\exists T', T'' \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . T \Longrightarrow (\nu \tilde{x}) (T' \mid s.T'') \quad \text{and} \quad \forall l \in \text{fn}(T'') . \forall b \in \mathbb{B} . \forall T''' \in \mathcal{P}_a . T'' \not\equiv (T''' \mid \bar{l}(b)) .$$

Let $T \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$. Then any name s is a sender lock of T if

$$\exists T' \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \exists p_o, y, l, z \in \mathcal{N} . T \equiv (\nu \tilde{x}) (T' \mid \overline{p_o}(y, l, s, z)) .$$

An instantiation of a sender lock is an output on a sender lock.

Beside the blocking of the encoded continuation, in $\llbracket \cdot \rrbracket_a^m$ the receiver lock is used by the encoding of the parallel operator and its pendant in the encoding of a replicated input to transmit the order of the sum locks back to the encoding of an input guarded source term. Remember, that the encoding of an input guarded source term tests these sum locks to emulate a communication step of the source term and that the ordering of sum locks is necessary to avoid deadlock. In case of $\llbracket \cdot \rrbracket_a^m$, receiver locks are again unambiguous identified by input requests. However they are also the only links in $\llbracket \cdot \rrbracket_a^m$ carrying five parameters. In $\llbracket \cdot \rrbracket_a^s$ receiver locks are the only links of multiplicity zero, that are used as replicated inputs.

Definition 18 (Receiver lock). *Let $T \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^s$. Then any name r is a receiver lock of T if*

$$\exists T', T'' \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . T \equiv (\nu \tilde{x}) (T' \mid r^*.T'') .$$

Let $T \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$. Then any name r is a receiver lock of T if

$$\exists T' \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \exists p_i, y, l \in \mathcal{N} . T \equiv (\nu \tilde{x}) (T' \mid \overline{p_i}(y, l, r)) .$$

An instantiation of a receiver lock is an output on a receiver lock.

Note that—for both encodings—for each input or output guarded source term exactly one receiver or sender lock is generated. Similarly, for each sum a unique sum lock is generated. However, since a sum may contain several input and/or output guarded summands, the encodings of different input or output guarded terms may share the same sum lock. But each encoded guarded term is connected to exactly one sum lock. The encoding $\llbracket \cdot \rrbracket_a^m$ is obviously more complex than the encoding $\llbracket \cdot \rrbracket_a^s$. But on the other hand the existence of requests outlines the connection between sum locks and sender or receiver locks—and with it to the corresponding encodings of guarded terms—more clearly.

Definition 19. Let $T \in \mathcal{P}_{\text{al}}[\![\cdot]\!]_{\text{a}}^{\text{m}}$ and let $l, r, s \in \mathcal{N}$. If T contains an unguarded input request with l as second and r as third parameter, i.e., if

$$\exists T' \in \mathcal{P}_{\text{a}} \cdot \exists \tilde{x} \subset \mathcal{N} \cdot \exists p_i, y \in \mathcal{N} \cdot T \equiv (\nu \tilde{x}) (T' \mid \overline{p_i} \langle y, l, r \rangle),$$

then we call the sum lock l and the receiver lock r connected. Sometime we also say that l is the sum lock of the receiver lock r .

Accordingly, if T contains an unguarded output request with l as second and s as third parameter, i.e., if

$$\exists T' \in \mathcal{P}_{\text{a}} \cdot \exists \tilde{x} \subset \mathcal{N} \cdot \exists p_o, y, z \in \mathcal{N} \cdot T \equiv (\nu \tilde{x}) (T' \mid \overline{p_o} \langle y, l, s, z \rangle),$$

then we call the sum lock l and the sender lock s connected. Sometime we also say that l is the sum lock of the sender lock s .

Of course, the connection of sum locks to sender or receiver locks is unambiguous.

Lemma 6. Let $T \in \mathcal{P}_{\text{al}}[\![\cdot]\!]_{\text{a}}^{\text{m}}$ be a target term. Then each receiver lock r and each sender lock s of T is connected to exactly one sum lock l of T , i.e.,

$$\begin{aligned} \forall T_1, T_2 \in \mathcal{P}_{\text{al}}[\![\cdot]\!]_{\text{a}}^{\text{m}} \cdot \forall r, p_{i1}, p_{i2}, y_1, y_2, l_1, l_2 \in \mathcal{N} \cdot \forall T'_1, T'_2 \in \mathcal{P}_{\text{a}} \cdot \forall \tilde{x}_1, \tilde{x}_2 \subset \mathcal{N} \cdot \\ T_1 \equiv (\nu \tilde{x}_1) (T'_1 \mid \overline{p_{i1}} \langle y_1, l_1, r \rangle) \wedge T_1 \implies T_2 \wedge T_2 \equiv (\nu \tilde{x}_2) (T'_2 \mid \overline{p_{i2}} \langle y_2, l_2, r \rangle) \text{ implies } y_1 = y_2 \wedge l_1 = l_2 \end{aligned}$$

and

$$\begin{aligned} \forall T_1, T_2 \in \mathcal{P}_{\text{al}}[\![\cdot]\!]_{\text{a}}^{\text{m}} \cdot \forall s, p_{o1}, p_{o2}, y_1, y_2, l_1, l_2, z_1, z_2 \in \mathcal{N} \cdot \forall T'_1, T'_2 \in \mathcal{P}_{\text{a}} \cdot \forall \tilde{x}_1, \tilde{x}_2 \subset \mathcal{N} \cdot \\ T_1 \equiv (\nu \tilde{x}_1) (T'_1 \mid \overline{p_{o1}} \langle y_1, l_1, s, z_1 \rangle) \wedge T_1 \implies T_2 \wedge T_2 \equiv (\nu \tilde{x}_2) (T'_2 \mid \overline{p_{o2}} \langle y_2, l_2, s, z_2 \rangle) \\ \text{implies } y_1 = y_2 \wedge l_1 = l_2 \wedge z_1 = z_2. \end{aligned}$$

Proof. Analysing the encoding function $[\![\cdot]\!]_{\text{a}}^{\text{m}}$ in Figure 4 we observe that initially, i.e., for each target term $[\![S]\!]_{\text{a}}^{\text{m}}$ for some source term $S \in \mathcal{P}_{\text{m}}$, for each receiver lock, i.e., for each encoding of an input guarded term or a replicated input, and for each sender lock, i.e., for each encoding of an output guarded term, exactly one request is generated. Since the receiver and sender locks are generated under restriction, for each encoded source term there are not two requests with the same receiver or the same sender lock, i.e., no two requests share their third parameter. Because of that the lemma holds for all $T_1 = T_2 = [\![S]\!]_{\text{a}}^{\text{m}}$ for some source term $S \in \mathcal{P}_{\text{m}}$. By Corollary 2 then the lemma holds for all target terms T_1 and T_2 such that $T_1 \implies T_2$. $\square$

Note that this lemma does not only shows that the connection between sum locks and sender or receiver locks is unambiguous but moreover that the information carried by requests is persistent. It does not change while requests wander to the structure of the encoded term generated by the parallel operator nesting of the corresponding source term.

Since, in case of $[\![\cdot]\!]_{\text{a}}^{\text{m}}$ receiver locks are not only used to guard the encoding of the continuation of an input guarded term or replicated input but also to send the order of the locks back to the corresponding test-statement, they carry all necessary informations to perform the test.

Lemma 7. Let $T \in \mathcal{P}_{\text{al}}[\![\cdot]\!]_{\text{a}}^{\text{m}}$ and $r \in \mathcal{N}$ be a receiver lock of T . Then the first three parameters of r are sum locks, the fourth parameter is a sender lock s , and the last parameter is a translated source term name. Moreover, the third sum lock belongs to s and among the first to sum locks one belongs to r and the other one is again the sum lock of s .

Proof. There are four different outputs on receiver locks, i.e., outputs of five parameters, one in each of `procRightOutReq` and `procRightInReq` in the encoding of a parallel operator and in the encoding of a replicated input (compare to Figure 4).

$$\begin{aligned} \text{procRightOutReq} \triangleq \overline{c_o} \langle m_i \rangle \mid c_o^* (m_i) \cdot p_o (y, l_s, s, z) \cdot (\\ (\nu m_{i,up}) (m_i^* (y', l_r, r) \cdot ([y' = y] \overline{r} \langle l_r, l_s, l_s, s, z \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle) \\ \mid (\nu m_i) (m_{i,up} \twoheadrightarrow m_i \mid \overline{c_o} \langle m_i \rangle)) \\ \mid \overline{p_{o,up}} \langle y, l_s, s, z \rangle) \end{aligned}$$

In `procRightOutReq` the output $\bar{\tau} \langle l_r, l_s, l_s, s, z \rangle$ is guarded by a replicated input $m_i^* (y', l_r, r)$ of three parameters which is in turn guarded by an input $p_o (y, l_s, s, z)$ of four parameters. So to unguard the output on the receiver lock two requests—first an output request and then an input request—have to be consumed. The values of the parameters of the output $\bar{\tau} \langle l_r, l_s, l_s, s, z \rangle$ are completely determined by these two requests. Because of that the first three parameters are sum locks, the fourth parameter is a sender lock s , and the last parameter is a translated source term name. Moreover, the first parameter is the sum lock of the receiver lock and the second and third parameter are the sum lock of the sender lock.

$$\begin{aligned} \text{procRightInReq} \triangleq & \bar{c}_i \langle m_o \rangle \mid c_i^* (m_o) . p_i (y, l_r, r) . (\\ & (\nu m_{o,up}) (m_o^* (y', l_s, s, z) . ([y' = y] \bar{\tau} \langle l_s, l_r, l_s, s, z \rangle \mid \overline{m_{o,up}} \langle y', l_s, s, z \rangle) \\ & \mid (\nu m_o) (m_{o,up} \rightarrow m_o \mid \bar{c}_i \langle m_o \rangle)) \\ & \mid \overline{p_{i,up}} \langle y, l_r, r \rangle) \end{aligned}$$

The case of `procRightInReq` is similar but here the input request has to be consumed first, and the first and the third parameter are the sum lock of the sender lock and the second parameter is the sum lock of the receiver lock. $\square$

In order to ease the proof of Lemma 10 at page 21 we introduce another kind of lock. $\llbracket \cdot \rrbracket_a^m$ translates source term observables into requests, which are then combined to search for potential communication partners. In order to avoid divergence, requests can not be copied arbitrary often. To ensure that indeed each left request is combined with each possible matching right request, the right requests—in the encoding of a parallel operator as well as in the encoding of a replicated input—are linked within some kind of chain or list, along which the left requests are forwarded. Again to avoid divergence these chains or lists can not be infinitely long, so the links c_o and c_i are introduced by the encoding function to extend these chain or list by a new right request as soon as its last place is occupied. We will denote these links as *chain locks*. Similarly, the chain lock $c_{r,l}$ in the encoding of a replicated input is used to establish some kind of chain on encoded source terms—the encoded continuations of that replicated input—instead of right requests. Note that chain locks are the only links in target terms with multiplicity one.

Definition 20 (Chain Lock). *Let $T \in \mathcal{P}_a[\llbracket \cdot \rrbracket_a^m]$. Then any name c_o is a chain lock of T if $\exists T' \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \exists m_i \in \mathcal{N} . T \Longrightarrow (\nu \tilde{x}) (T' \mid \bar{c}_o \langle m_i \rangle)$.*

An instantiation of a chain lock is an output on a chain lock.

Note that the value of a chain lock used to establish a chain of right requests is always a request channel, while the value of a chain lock used to establish a chain of encoded source terms is always a translated source term name, i.e., a value never used as link. Because of that, we can easily distinguish these two kinds of chain locks by a simple type information.

2.3 Steps of an Emulation

Before we formally define receiver and sender locks in the last section we argue that they are introduced by the encoding function to guard the encoding of the continuation of a guarded source term. To mimic the behaviour of the source term, the encodings of continuations have to stay guarded until the source term step unguarding them in the source term is emulated by its encoding. As already mentioned both encodings translate a single source term step into a sequence of target term steps called emulation. However, in both encodings we can unambiguously allocate the main responsibility for an emulation to a single step of that emulation and call all the other steps pre- or postprocessing steps of that emulation. In the following we will refer to the first kind of target term steps as *core steps*, since they perform the main task of an emulation and because of that constitute the transition from the emulation of a source term to the emulation of its successor. It turns out, that for both encodings the core steps are connected to the test-statements. More precisely, in case of an emulation of a step on a term guarded by τ or a replicated input, it is the consumption of the positive instantiation of a sum lock by the corresponding test-statement that performs the main task of the emulation. In case of an emulation of a step on an input guarded source term, it is the consumption of the second positive instantiation in the nested test-statement that we call core step.

Definition 21 (Core Step). *Let $T_1, T_2 \in \mathcal{P}_a[\llbracket \cdot \rrbracket_a^m]$ (or $T_1, T_2 \in \mathcal{P}_a[\llbracket \cdot \rrbracket_a^s]$). A step $T_1 \mapsto T_2$ is a core step, denoted by $T_1 \xrightarrow{\text{core}} T_2$, if this step consumes a positive instantiation of a sum lock either within a single test-statement or within the second test of a nested test-statement.*

Note that, since negative instantiations of sum locks refer to encoded in- or outputs, that remains of a former emulation as junk, we do not consider any consummation of a negative sum lock as core step. According, test-statements consuming a negative instantiation of a sum lock only restore all consumed information. In the following we prove our intuition of core steps by showing that encoded continuations can only be unguarded after a core step.

Lemma 8. *Only core steps may lead to the unguarding of the encoding of a continuation of some source term.*

Proof. Analysing the encoding functions in Figure 3 and Figure 4 we observe that the encoded continuations of output guarded source terms appear guarded by the respective sender lock. Moreover we observe that all instantiations of sender locks are guarded by test-statements. More precisely, they are guarded by the then-case of a single test-statement (due to the encoding of a replicated input) or the then-case of the second test in a nested test-statement (due to the encoding of an input guarded term). Note that in case of $\llbracket \cdot \rrbracket_a^m$, by Lemma 7 the input on the receiver lock that guards the test-statements unambiguously identifies the following outputs of multiplicity zero as sender locks. So a core step is necessary to unguard them.

In case of a source term guarded by τ or an input guarded source term the respective encoded continuations appear directly as required in the respective then-cases of the test-statements. So, in these cases, the lemma holds directly by the Definition of the encoding functions. $\square$

Note that to our intuition for each emulation of a source term step, there is exactly one core step. However, we will need some further information to prove that statement (compare to Lemma 32 at page 48). So let us have a closer look at the remaining pre- and post processing steps. There is one step of an emulation, namely the unguarding of the encoded continuation of an output guarded source term by communication over a sender lock, that for certainty has to be performed after the core step of the corresponding emulation. Because of that we can call reductions on sender locks postprocessing steps. There are also steps, as for instance reductions over receiver locks, that for certainty have to be performed before the corresponding core step. So we can call all reductions on receiver locks preprocessing steps. However, there are some steps that may be performed before or after the corresponding core step. Moreover, the fact whether a non core step was performed before or after the corresponding core step is usually not important and often hard to prove. So pre- or postprocessing steps is not a good characterisation for our purposes. Instead we will refer to those steps as *administrative steps*, since they perform administrative tasks, that are necessary to perform an emulation, but they do not carry the main responsibility for the emulation, i.e., they do—at least for the general case—not inevitably implement the decision to emulate a specific source term step.

Definition 22 (Administrative Step). *Let $T_1, T_2 \in \mathcal{P}_a \downarrow \llbracket \cdot \rrbracket_a^m$ (or $T_1, T_2 \in \mathcal{P}_a \downarrow \llbracket \cdot \rrbracket_a^s$). A step $T_1 \mapsto T_2$ is a administrative step, denoted by $T_1 \vdash \dot{\rightarrow} T_2$, if it is no core step.*

Let $T_1 \vdash \dot{\Rightarrow} T_2$ denote a sequence of administrative steps, i.e., $\vdash \dot{\Rightarrow}$ is the transitive and reflexive closure of $\vdash \dot{\rightarrow}$.

In the easiest case, none of the administrative steps influences the decision to emulate a specific source term steps. That means: Consider a source term that can perform alternative but conflicting steps. So the encoding can perform different but conflicting emulations. In this case none of the administrative steps should influences which of the emulations may be completed, i.e., no sequence of administrative steps should be able to rule out the completion of one of these emulations.

Unfortunately, for both of the presented encodings this turns out to be wrong. It is always a core step that finally decides which of the conflicting emulations is completed by preventing any other conflicting emulation from completion. However, in case there are more than two possible conflicting emulations, a sequence of administrative steps may rule out one alternative while allowing for different still possible emulations.

Example 1. Let us consider the source term $S = (a.S_1 + a.S_2) \mid \bar{a}.S_3 \mid a.S_4$ for some $S_1, S_2, S_3, S_4 \in \mathcal{P}_s$. So $S \in \mathcal{P}_s$ as well as $S \in \mathcal{P}_m$. The encoding of S , regardless whether it is encoded by $\llbracket \cdot \rrbracket_a^s$ or $\llbracket \cdot \rrbracket_a^m$, generates three sum locks, one for each sum. Let us assume, the sum lock generated for $a.S_1 + a.S_2$ is l_1 , the sum lock for $\bar{a}.S_3$ is l_2 , and l_3 is generated for $a.S_4$. S can perform three conflicting steps leading to $S_1 \mid S_3$, $S_2 \mid S_3$, or $S_3 \mid S_4$, respectively. Each of these steps can be emulated by both of the encodings. To emulate the step to $S_1 \mid S_3$ for both encodings the positive instantiation of the sum lock l_1 is consumed first and to complete the emulation a positive instantiation of the sum lock l_2 has to be consumed. However, it is possible, that the encoded term instead performs another (nested) test-statement and consume both positive instantiations of l_2 and l_3 to emulate the step to $S_3 \mid S_4$ instead. Because of that, in case of a nested test-statement, we do not consider the first consumption of a positive instantiation of a sum lock as a core step. Even, if at this point the sum lock, that is tested next by this test-statement, is still instantiated positive, it can become negative by an interleaving other test-statement.

So after the consumption of the positive instantiation of l_1 in order to emulate the source term step to $S_1 \mid S_3$, there is still the possibility to complete instead the emulation of the source term step to $S_3 \mid S_4$. However, there

is no possibility to complete the emulation of the source term step to $S_2 \mid S_3$. Note that, to emulate the step to $S_2 \mid S_3$, a positive instantiation of each of the locks l_1 and l_2 is necessary. Here, the instantiation of l_1 is consumed. The only possibility to restore the positive instantiation is to consume a negative instantiation of l_2 (compare to the nested test-statements in the encodings of input guarded terms in Figure 3 and Figure 4). By Lemma 5, then there is no possibility to change that negative instantiation back into a positive one. So, as soon as l_1 is consumed, one of the three possible emulations is ruled out while there are still two possible emulations left.





Fig. 5. Intermediate States.

We visualise this phenomenon in Figure 5 (for the case of $\llbracket \cdot \rrbracket_a^m$). Here the red lines denote sequences of steps with (exactly) one core step, the blue lines denote sequences without core steps but with at least one impure administrative step, and the green lines denote sequences of only pure administrative steps (compare to Definition 24). Between the encoding of the source term S and the encodings of its reducts $S_1 \mid S_3$, $S_2 \mid S_3$, and $S_3 \mid S_4$ there are two *intermediate states*, i.e., two states that differ from each encoded source term within that picture. Note that the observability of such an intermediate state depends on the chosen equivalence on target terms.

Definition 23 (Intermediate State). A term T' is an intermediate state, if

$$\exists T, T_1, T_2, T_3 . T \Longrightarrow T_1 \wedge T \Longrightarrow T_2 \wedge T \Longrightarrow T_3 \wedge T \Longrightarrow T' \wedge T' \Longrightarrow T_1 \wedge T' \Longrightarrow T_2 \wedge T' \not\Longrightarrow T_3,$$

i.e. if



Remarkably, the existence of intermediate states in $\llbracket \cdot \rrbracket_a^s$ is independent of structural congruence—if two source terms are structural congruent, then their encodings have the same intermediate states—while this is not true for $\llbracket \cdot \rrbracket_a^m$. Here the locks are always tested according to a total ordering created along the structure induced by the nesting of parallel operators of the source term. Because of that, this ordering of sum locks differ for source terms, that are structural congruent but differ in the order of their subprocesses, i.e. differ by rule $P \mid Q \equiv Q \mid P$. So structural congruent source terms can differ in the number and nature of reachable intermediate states; e.g. $S' = \bar{a}.S_3 \mid (a.S_1 + a.S_2) \mid a.S_4$, which is structural congruent to S from Example 1, does not reach any of the above intermediate states. Instead, in S' the first consumption of a positive instantiation of a sum lock, which is no core step here, completely determines which emulation can be completed.

To capture that fact we further distinguish administrative steps, into pure administrative steps—that never rule out the completion of any possible emulation—and impure administrative steps—that due to the consumption of a positive instantiation of a sum lock may possibly rule out the completion of an emulation. Note that in case of $\llbracket \cdot \rrbracket_a^m$ requests are copied to ensure that each possible combination of input and output requests is checked exactly once. Because of that steps on requests are pure administrative steps. In opposite, $\llbracket \cdot \rrbracket_a^s$ does not translate source term observables into requests. To check for a potential pair of translated communication partners a communication of the translated channel names is performed. Similar to the consumption of positive instantiations of sum locks this might rule out alternative emulations. Because of that we consider steps on translated source term names as impure administrative steps of $\llbracket \cdot \rrbracket_a^s$. Also note, that in $\llbracket \cdot \rrbracket_a^m$ translated source term names are used as values only; so there are no steps on translated source term names.

Definition 24 (Pure and Impure Administrative Step). *Let $T_1, T_2 \in \mathcal{P}_{al}[\llbracket \cdot \rrbracket_a^m]$ (or $T_1, T_2 \in \mathcal{P}_{al}[\llbracket \cdot \rrbracket_a^s]$). A step $T_1 \vdash \rightarrow T_2$ is a pure administrative step, denoted by $T_1 \vdash \rightarrow T_2$, if it is neither on a sum lock nor on a translated source term name, else it is an impure administrative step, denoted by $T_1 \vdash \rightarrow T_2$.*

Let $T_1 \Longrightarrow T_2$ denote a sequence of pure administrative steps, i.e., $\Longrightarrow$ is the transitive and reflexive closure of $\vdash \rightarrow$.

To show that the definition of pure administrative steps meets our intuition, we prove some kind of local confluence property for most of the pure administrative steps. Intuitively, it states that indeed none of the pure administrative steps can rule out the completion of any emulation, because they are (in most cases) not conflicting, i.e., does not rule out any other sequence of steps.

Lemma 9. *Within target terms pure administrative steps are not conflicting, i.e.,*

$$\forall T, T_1, T_2 \in \mathcal{P}_{al}[\llbracket \cdot \rrbracket_a^s] . T \vdash \rightarrow T_1 \wedge T \vdash \rightarrow T_2 \text{ implies } \exists T' \in \mathcal{P}_{al}[\llbracket \cdot \rrbracket_a^s] . T_1 \Longrightarrow T' \wedge T_2 \vdash \rightarrow T'.$$

Proof. In comparison to $\llbracket \cdot \rrbracket_a^m$ the encoding $\llbracket \cdot \rrbracket_a^s$ introduces only a few pure administrative steps and all of them are not conflicting. First note that, since in π_a there are no sums, two target term steps can only be in conflict if one of it consumes some input or output necessary to perform the other step. So it suffice to concentrate on steps on the same channel. Analysing the encoding function in Figure 3 we discover that steps on receiver or sender locks (compare to Definitions 18 and 17) are pure administrative steps.

In case of receiver lock, since they are generated under restriction, for each receiver lock there is exactly one replicated input and no other input. Because of that it does not matter how many other steps on (the same) receiver lock may appear within the sequence $T \Longrightarrow T_2$ the step $T \vdash \rightarrow T_1$ can be performed before or after that sequence and in both cases the same term T' is reached.

In case of sender locks, there is exactly one input and no replicated input for each sender lock. Moreover, we observe that initially there is no instantiation of a sender lock, and there is exactly one output (on a translated source term name) which carries the sender lock as value. This output is consumed to unguard a test-statement and that test-statement can then unguard again at most one output which carries the sender lock as value and which can itself unguard another test-statement. The only instantiations of sender locks are due to the then-case of a single test-statement in the encoding of a replicated input or the then-case of the second test-statement in the encoding of an input guarded term, and in both cases only a single instantiation of a sender lock is unguarded. So for each target term and each sender lock there can be at most one instantiation of a sender lock. Moreover note, that the output on the translated source term names does not only carry the sender lock, but also a sum lock. In order to obtain an instantiation of the sender lock this sum lock has to be instantiated positive. But whenever a sender lock is instantiated the encoding also generates a negative instantiation of that sum lock. By Lemma 5 that negative instantiation can never be turned into a positive one again; so there is no chance to generate a second instantiation on the same sender lock. Because of that, if $T \vdash \rightarrow T_1$ is a step on a sender lock, then none of the steps in $T \Longrightarrow T_2$ is a step on that sender lock. So the lemma holds.

Besides these to steps there is another kind of pure administrative steps that is not that obvious in Figure 3 because that kind of steps is hidden by the abbreviation used to introduce booleans and test-statements (compare to Definition 5). We observe, that a test-statement is reduced within two steps. The first consumes the instantiation of the sum lock and is thus no pure administrative step. The second step unguards the corresponding then- or else-case. In both cases that step is a pure administrative step. However the names t and f are restricted for each test-statement, are not used any there else by the encoding function, and thanks to the renaming policy are different from each translated source term name. Because of that, we can again conclude that, if $T \vdash \rightarrow T_1$ is a step on a version of t or f , then none of the steps in $T \Longrightarrow T_2$ is a step on the same name. So the lemma holds. $\square$

Lemma 10. *Within target terms pure administrative steps, that either are on sender locks or booleans, or do not unguard an instantiation of a chain lock carrying a request channel, are not conflicting, i.e.,*

$$\begin{aligned}
& \forall T, T_1, T_2 \in \mathcal{P}_a[\![\cdot]\!]_a^m . T \mapsto T_1 \wedge T \Longrightarrow T_2 \\
& \wedge (T \mapsto T_1 \text{ is a step on a sender lock or booleans} \\
& \quad \vee (\forall T'_1 \in \mathcal{P}_a . \forall \tilde{x} \in \mathcal{N} . \forall c_o, m_i \in \mathcal{N} . T_1 \equiv (\nu \tilde{x}) (T'_1 \mid \overline{c_o} \langle m_i \rangle), \text{ where } m_i \text{ is a request channel} \\
& \quad \text{implies } (\exists T' \in \mathcal{P}_a . \exists \tilde{x}_1 \in \mathcal{N} . T \equiv (\nu \tilde{x}_1) (T' \mid \overline{c_o} \langle m_i \rangle))) \\
& \text{implies } \exists T_3 \in \mathcal{P}_a[\![\cdot]\!]_a^m . T_1 \Longrightarrow T_3 \wedge T_2 \mapsto T_3.
\end{aligned}$$

Proof. $[\![\cdot]\!]_a^m$ relies on much more pure administrative steps than $[\![\cdot]\!]_a^s$. First note that, the encoding of a parallel operator generates unguarded instantiations of chain locks carrying a request channel. Since a step on a sender lock and a step on t to unguard the then-case of a test-statement unguards an encoded continuation, they unguard instantiations of such chain locks, if the corresponding source term in the continuation contains a parallel operator. Nevertheless, we want to prove the condition also for steps on sender locks and booleans.

Since source term names are translated into values, never used as links, it suffice to consider steps on names introduced by the encoding function. A look at the definition of the corresponding renaming policy in Figure 4 suggests the following case split³ on the subject of the step $T \mapsto T_1$.

Case of $p_o, p_i, p_{o,up}, p_{i,up}, m_o, m_i, m_{o,up}, m_{i,up}, r_i, r_o, r_{i,up}, r_{o,up}$: All these names are request channels, i.e., there are introduced by $[\![\cdot]\!]_a^m$ to transport requests. Note that the encoding function puts much effort in the direction of requests. Usually there is exactly one way for them, namely: (1) upwards in the structure generated by the nesting of parallel operators in the corresponding source term, (2) within the encoding of a parallel operator or each branch of the encoding of a replicated input from the left side to each right request, which are linked within a chain, and (3) within the encoding of a replicated input from each branch to each next branch, where each branch represents an encoding of the continuation of that replicated input and the branches are again linked within some kind of chain.

Indeed there is only one point, at which the way of a requests is not completely determined. That is the point at which right requests are linked within a chain (compare to the encoding of a parallel operator or a replicated input). The order in which the right requests are consumed determines their order in the chain, so these steps are conflicting. They are steps on the first input on output requests in `procRightOutReq` and on the first input on input requests in `procLeftOutReq`.

$$\begin{aligned}
\text{procRightOutReq} & \triangleq \overline{c_o} \langle m_i \rangle \mid c_o^* (m_i) . p_o (y, l_s, s, z) . (\\
& \quad (\nu m_{i,up}) (m_i^* (y', l_r, r) . ([y' = y] \overline{r} \langle l_r, l_s, l_s, s, z \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle) \\
& \quad \mid (\nu m_i) (m_{i,up} \twoheadrightarrow m_i \mid \overline{c_o} \langle m_i \rangle)) \\
& \quad \mid \overline{p_{o,up}} \langle y, l_s, s, z \rangle) \\
\text{procRightInReq} & \triangleq \overline{c_i} \langle m_o \rangle \mid c_i^* (m_o) . p_i (y, l_r, r) . (\\
& \quad (\nu m_{o,up}) (m_o^* (y', l_s, s, z) . ([y' = y] \overline{r} \langle l_s, l_r, l_s, s, z \rangle \mid \overline{m_{o,up}} \langle y', l_s, s, z \rangle) \\
& \quad \mid (\nu m_o) (m_{o,up} \twoheadrightarrow m_o \mid \overline{c_i} \langle m_o \rangle)) \\
& \quad \mid \overline{p_{i,up}} \langle y, l_r, r \rangle)
\end{aligned}$$

In both cases immediately an instantiation of a chain lock carrying a request channel is unguarded. So the lemma holds, because its precondition is violated.

Let us have a look at the remaining request channels. Within the left side of the encoding of a parallel operator there are two restricted different replicated inputs on requests channels. Note that, the encoding function places all inputs or replicated inputs under restriction, i.e., for all source terms their encoding has no inputs or replicated inputs on free names. Because of that, for the request channels restricted at the left side of the parallel operator encoding there is exactly one replicated input and no other input. Thus it does not matter how many other steps on the same request channel may appear within the sequence $T \Longrightarrow T_2$, the step $T \mapsto T_1$ can be performed before or after that sequence and in both cases the same term T_3 is reached.

³ Note that in most cases the considered names are restricted, so a simple alpha conversion may change them. Because of that the use of concrete names in the following case split should not imply that we consider steps on these specific names. Instead the names refer to the meaning which is related to them by the encoding function.

Beside the already considered possibly conflicting input, there are two different replicated inputs on request channels and no other input on request channels within `procRightOutReq`. The link of the first is bounded by a guarding replicated input on a chain lock. The link of the second is restricted. So we can again apply the argumentation of the case before. The same applies to `procRightInReq`. The two links of replicated inputs in `pushReq` and the four links of replicated inputs `pushReqOut` are restricted, apart from that, this case is similar to the cases before. In opposite, in case of `pushReqIn` the links of both replicated inputs are bounded by a guarding input, apart from that, this case is similar to the cases before.

- Case of c_o, c_i :** These names are used as chain locks carrying a request channel (compare to Definition 20). Those chain locks are used by the encoding function to direct the combinations of left and right requests in the encoding of a parallel operator as well as in the encoding of a replicated input. In order to avoid divergence, requests can not be copied arbitrary often. To ensure that indeed each left request is combined with each possible matching right request, the right requests are linked within some kind of chain or list, along which the left requests are forwarded. Again to avoid divergence these chains can not be infinitely long, so c_o and c_i allow to extend these chains by a new right request as soon as its last place is occupied. Since these names are generated under restriction, for each of them there is exactly one replicated input and no other input. Because of that it does not matter how many other steps on the same names may appear within the sequence $T \Longrightarrow T_2$, the step $T \mapsto T_1$ can be performed before or after that sequence and in both cases the same term T_3 is reached.
- Case of l, l_s, l_r, l_1, l_2 :** Any of these names refer to a sum lock in the encoding given in Figure 4. By Definition 24 steps on sum locks are no pure administrative steps.
- Case of s :** s is used by the encoding function to introduce sender locks. For steps on sender locks it suffice to repeat the argumentation given in the proof of Lemma 9 for sender locks.
- Case of r :** In case of receiver lock, since they are generated under restriction, for each receiver lock there is exactly one replicated input and no other input. Because of that it does not matter how many other steps on (the same) receiver lock may appear within the sequence $T \Longrightarrow T_2$, the step $T \mapsto T_1$ can be performed before or after that sequence and in both cases the same term T_3 is reached.
- Case of c_{r1} :** c_{r1} again is a chain lock, this time carrying a translated source term name. Intuitively, it is used by the encoding function for a purpose similar to the usage of chain locks carrying a request channel. Instead of a chain of right requests, c_{r1} as well as c_{r2} are used to build up a some kind of chain of the encoded continuations of several reductions on the same encoded replicated input. As already explained our encoding $\llbracket \cdot \rrbracket_a^m$ relies on the structure which is build by the parallel operators in the corresponding source term. Each reduction of a replicated input changes this structure. To allow for different encoded continuations to communicate among each other or with the encoded replicated input we link the encodings of the continuations. This time we have to add a new member, i.e., an encoded continuation, to the chain whenever the encoded replicated input is used to emulate a step. Therefore c_{r1} is instantiated within the then-case of the test-statement in the encoding of a replicated input. Since c_{r1} is generated under restriction, for each c_{r1} there is exactly one replicated input and no other input. Because of that, it does not matter how many other steps on the same name may appear within the sequence $T \Longrightarrow T_2$, the step $T \mapsto T_1$ can be performed before or after that sequence and in both cases the same term T_3 is reached.
- Case of c_{r2} :** To link the members in the chain of right requests for each new member a new m_o or m_i is restricted and transmitted over c_o or c_i . The encoded continuations of a replicated input are linked over r_i and r_o , which are again restricted for each encoded continuation. c_{r2} is used to transmit these new restricted names to the respective next member of the chain. Note that, this kind of link is generated always under restriction. Initially there is exactly one unguarded output and one input, guarded by a replicated input on a chain lock. Reducing this input immediately unguards some instantiations of chain locks, so the lemma holds, because its precondition is violated. Also note that, due to several emulations on the encoded replicated input, there may be several unguarded inputs on c_{r2} . The order in which these inputs are consumed determines the order of the encoded continuations within the constructed chain. Because of that steps on c_{r2} can be indeed conflicting.
- Case of y, y', z :** These names are used by the encoding function as values only, but never as links. So there are no (pure administrative) steps on these names.
- Case of t, f :** These names are used only to implement the test-statements and the instantiation of sum locks. The reduction of a test-statement is performed in two steps. The first consumes the instantiation of a sum lock and is thus not a pure administrative step. For the second one—necessary to unguard the then- or else-case of a test-statement—it suffice to repeat the argumentation given in the proof of Lemma 9 for these kind of steps.

□

Note that the proof above provides a detailed explanation of the purposes of the names reserved by the encoding function $\llbracket \cdot \rrbracket_a^m$. Moreover note that the pure administrative steps that are conflicting are exactly the steps that

introduce additional causal dependencies (compare to [PSN11] and thus prevent the preservation of the degree of distribution (compare to Section 4 in [PN12])). In the following we strongly rely on the Lemmata 9 and 10, because they basically allow us to ignore all not conflicting steps while considering the reachability of success or translated observables in the next section.

In order to show that the remaining pure administrative steps do not cause any problems but in fact, as described in the proof of Lemma 10, do only influence the order of right requests in the chain of right request or the order of encoded continuations of a replicated input generated by its encoding, we prove that those steps never cause any deadlock. Note that, [Nes00] proves that the encoding $\llbracket \cdot \rrbracket_a^s$ does not introduce deadlocks.

Lemma 11. *Pure administrative steps do not introduce deadlocks.*

Proof. In case of a step on a sender lock or a step which does not unguard an instantiation of a chain lock, this lemma directly follows by Lemma 10.

In case of a step on a request channel which does unguard an instantiation of a chain lock (compare to the first case of the proof of Lemma 10), a step on the unguarded chain lock unguards another input on the same request channel. Moreover the corresponding continuations differ only on a single name free to that continuation. Let us denote the first such continuation by A and the second by B , and the free link name by p . Then it turns out, that B is connected to A by p and either A is connected in a similar way to another such continuation or A is connected to the requests from the left. The only requests travelling along p are left requests. However as soon as they arrive A they are copied and transmitted to B . Because of that the order of A and B in that chain does not matter (at least as long as we do not consider causal dependencies). Of course, the step on the chain lock unguarding B is not forced to be performed immediately after the step on the request channel, but by Lemma 10 it will eventually happen. So the step on the request channel blocks alternative steps on this request channel for some time but not for ever, i.e., it does not introduce deadlock.

In case of a step on a channel of multiplicity two—let us denote it c —which does unguard an instantiation of a chain lock (compare to case c_{r2} of the proof of Lemma 10), immediately another output on c is unguarded. As in the case before by the communication on the chain lock, the communication over c links the encodings of the continuations of the respective replicated input, in this case by two request channels. Apart from that, the situation is exactly the same as before. If there is an other encoded continuation of that replicated input—caused by another emulation—it will eventually be linked within the chain and all requests that arrive at a previous member of that chain are forwarded to that member. Note that the encoded continuations initially are all equal. So the chains resulting from different orders of two members, that were available at the same time, are equal. We conclude that a step on c can not introduce deadlock. $\square$

Lemma 12. *Impure administrative steps do not introduce deadlocks.*

Proof. In $\llbracket \cdot \rrbracket_a^m$ any impure administrative step reduces a test-statement by consuming an instantiation of a sum lock (compare to Definition 24). Deadlock occurs, if—due to interleaving of these test-statements—the instantiations of a subset of the sum locks are consumed, such that none of the involved test-statements can be resolved. As already stated in [Nes00] a total ordering on the sum locks suffice to circumvent any potential deadlock. Note that the encodings of parallel operator and replicated input implement such a total ordering on sum locks. They somehow reuse the structure generated by the parallel operators of the corresponding source term to force the nested test-statements to always test the lock first, which is according to that parallel structure left to the other one. Since the parallel operator is binary, this structure is a binary tree. So testing always the left lock first, indeed implements a total ordering. $\square$

Note that, by Lemma 32 at page 48, core steps and the source term steps of the corresponding emulations coincide. So Lemma 32 in combination with the Lemma 11 and Lemma 12 proves that the encoding $\llbracket \cdot \rrbracket_a^m$ does not introduce deadlocks.

2.4 Translated Observables and Choosing a Bisimulation

In order to prove the presented encodings correct with respect to the criteria of Gorla we have to choose an equivalence $\asymp$ for operational correspondence (compare to Definition 9). In [Gor10] Gorla describes $\asymp$ as follows:

“ $\asymp$ is a behavioural equivalence needed to describe the abstract behaviour of a process. Usually, $\asymp$ is a congruence at least with respect to parallel composition; it is often defined in the form of a barbed equivalence or can be derived directly from the reduction semantics.”

Moreover, by the criteria in Section 1.3, we know that $\asymp$ should be success respecting (compare to Definition 13). The main purpose of $\asymp$ in the definition of operational correspondence is to abstract from junk, i.e., remains left over by former emulations that do not influence the abstract behaviour of a target term. Usually, two kinds of junks are distinguished inactive junk, i.e., remains that neither can perform further reductions on its own nor interact with the surrounding target term, and active junk, i.e., remains that may be reduced or even interact with the surrounding target term. Of course, proving an encoding to be good requires to prove that its active junk does no harm, i.e., does not influence the abstract behaviour of the target term. However, the presented encodings $\llbracket \cdot \rrbracket_a^s$ and $\llbracket \cdot \rrbracket_a^m$ induce the consideration of a second dimension of junk, namely observable and inobservable junk. In most cases developers of encodings make sure that all produced junk is inobservable, i.e., using the standard notions of observables for the target language neither the steps on junk nor the junk itself is observable. Unfortunately, as for the presented encodings, it is not always possible to define the encoding function such that all produced junk is inobservable.

In the π -calculus observables are usually defined to be the unguarded input or output guards of a term, whose channel name is not restricted (compare to Definition 4). To encode sums both encodings split up the summands into parallel. Of course, while doing so, the information which of these summands originally belongs to the same sum gets lost. To recover it, the encodings introduce sum locks, which cover a boolean value to indicate whether the respective summands of that sum can still be used to complete an emulation or whether a former emulation already consume one of the summands and thus no other can be used any more. Thus the encoding functions translate a source term observable into an observable—in case of $\llbracket \cdot \rrbracket_a^s$ —or a request—in case of $\llbracket \cdot \rrbracket_a^m$ —both times augment with the information covered by the sum lock. So source term observables are not translated into single observables again.

Definition 25 (Translated Observables). *Let $T \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^s$. Then T has a translated input observables y , denoted by $T \Downarrow_y^s$, if*

$$\begin{aligned} \exists T', T'_1, T'_2 \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \exists l, l', s, z \in \mathcal{N} . \\ (T \equiv (\nu \tilde{x}) (T' \mid y(l', s, z) . \text{test } l \text{ then } T'_1 \text{ else } T'_2 \mid \bar{l} \langle \top \rangle)) \vee T \equiv (\nu \tilde{x}) (T' \mid y^*(l', s, z))) \wedge y \notin \tilde{x} \end{aligned}$$

and T has a translated output observables y , denoted by $T \Downarrow_y^s$, if

$$\exists T' \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \exists l, s, z \in \mathcal{N} . T \equiv (\nu \tilde{x}) (T' \mid \bar{y} \langle l, s, z \rangle \mid \bar{l} \langle \top \rangle) \wedge y \notin \tilde{x}.$$

Let $T \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$. Then T has a translated input observables y , denoted by $T \Downarrow_y^m$, if

$$\exists T' \in \mathcal{P}_a . \tilde{x} \subset \mathcal{N} . \exists p_i, l, r \in \mathcal{N} . T \equiv (\nu \tilde{x}) (T' \mid \bar{p}_i \langle y, l, r \rangle \mid \bar{l} \langle \top \rangle) \wedge y \notin \tilde{x}$$

and T has a translated output observables y , denoted by $T \Downarrow_y^m$, if

$$\exists T' \in \mathcal{P}_a . \tilde{x} \subset \mathcal{N} . \exists p_o, l, s, z \in \mathcal{N} . T \equiv (\nu \tilde{x}) (T' \mid \bar{p}_o \langle y, l, s, z \rangle \mid \bar{l} \langle \top \rangle) \wedge y \notin \tilde{x}.$$

Moreover for some input or output observable μ we define $T \Downarrow_\mu^s \triangleq \exists T' \in \pi_a . T \Longrightarrow T' \wedge T' \Downarrow_\mu^s$ and $T \Downarrow_\mu^m \triangleq \exists T' \in \pi_a . T \Longrightarrow T' \wedge T' \Downarrow_\mu^m$.

Note that for all target terms $T \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$ any output with three parameters is an input request and any output with four parameters is an output request. So a simple typing suffice to securely identify requests. Since requests already contain a reference to their related sum lock, the identification of the related sum lock instantiation is unambiguous as well. The condition $y \notin \tilde{x}$ is necessary to rule out translated observables that corresponds to invisible in- or outputs of the source term (compare to Definition 4 at page 3). To show that the notion of translated observables indeed captures our intuition we prove that the set of observables reachable for a source term coincides with the set of translated observables reachable for its encoding.

Lemma 13. *The set of reachable observables of a source term and of reachable translated observables of its encoding coincide, i.e.,*

$$\forall S \in \mathcal{P}_s . \forall \mu \in \mathcal{N} \cup \overline{\mathcal{N}} . S \Downarrow_\mu \text{ iff } \llbracket S \rrbracket_a^s \Downarrow_\mu^s$$

and

$$\forall S \in \mathcal{P}_m . \forall \mu \in \mathcal{N} \cup \overline{\mathcal{N}} . S \Downarrow_\mu \text{ iff } \llbracket S \rrbracket_a^m \Downarrow_\mu^m .$$

Proof. By Corollary 3 stating that initially all sum locks are instantiated positive and Figure 4 the set of observables of a source term $S \in \mathcal{P}_m$ and the set of translated observables of $\llbracket S \rrbracket_a^m$ coincide, i.e.,

$$\forall S \in \mathcal{P}_m . \forall \mu \in \mathcal{N} \cup \overline{\mathcal{N}} . S \downarrow_\mu \text{ iff } \llbracket S \rrbracket_a^m \downarrow_\mu .$$

In case of $\llbracket \cdot \rrbracket_a^s$ we obtain a similar result after reducing all instantiation of receiver locks, since they guard the respective inputs (compare to Figure 3). The lemma then follows by operational correspondence, i.e. by the Lemmata 30 at page 37, 31 at page 40, and 33 at page 49⁴. $\square$

The problem now is, that the completion of an emulation changes positive instantiations of sum locks into negative ones and so obviously influences the translated observables, but the corresponding requests—in case of $\llbracket \cdot \rrbracket_a^m$ —or in- and outputs of other summands—in case of $\llbracket \cdot \rrbracket_a^s$ —remain as observable junk. While active junk often aggravates the proof of correctness of an encoding, due to intricate proofs to show that it does no harm, observable junk turns out to be even worse for an encoding, because it prevents for the use of standard equivalences to describe the abstract behaviour of a target term.

Since the target language is the asynchronous π -calculus, it seems natural to choose weak asynchronous bisimilarity $\approx_a$ or asynchronous barbed congruence $\cong_a$. Unfortunately for both choices the presented encodings are not good. Consider for example the source term $S = (\nu x)(x + y \mid \bar{x})$. It can perform a reduction to $\mathbf{0}$. But, all derivatives of its encoding, i.e., all $T \in \mathcal{P}_a$ with $\llbracket S \rrbracket_a^s \Longrightarrow T$ or $\llbracket S \rrbracket_a^m \Longrightarrow T$, are neither asynchronous bisimilar nor synchronous barbed congruent to the encoding of $\mathbf{0}$, i.e., $T \not\approx_a (\nu l)(\bar{l} \langle \top \rangle)$ and $T \not\cong_a (\nu l)(\bar{l} \langle \top \rangle)$, where $\llbracket \mathbf{0} \rrbracket_a^s = (\nu l)(\bar{l} \langle \top \rangle) = \llbracket \mathbf{0} \rrbracket_a^m$. Note that this is not due to the encoding of $\mathbf{0}$, which is indeed weak asynchronous bisimilar to $\mathbf{0}$ again, but to the observable junk, which suffice to distinguish the remains of emulations from $\mathbf{0}$. Because of this, a proof of the correctness of these encodings with respect to $\approx_a$ or $\cong_a$ fails due to operational correspondence (compare to the Definition 9). Of course, you might argue that an encoding that can not get rid of observable junk is no good encoding. On the other side, Nestmann in [Nes00] gives some good reasons to accept $\llbracket \cdot \rrbracket_a^s$ as a good encoding. Moreover, the translation of observables into something different seems to be a quite natural manner of encoding functions. And indeed rephrasing a standard equivalence to take instead of observables translated observables into account suffice to turn it into an equivalence that describes the abstract behaviour of encoded terms. The same holds if we do not consider observables at all, but e.g. only reachability of success.

Note that to test a sum lock it has to be consumed first. Analysing the encoding function we observe that in each case an instantiation of sum lock is consumed, another instantiation of that lock is restored as soon as the respective test statement is completed. However, since there may lay many steps between the start and the completion of a test statement, instantiations of locks may temporally not be available. Because of that, we will use the notion of $P \Downarrow_\mu^m$ instead of $P \downarrow_\mu^m$ in the following.

Definition 26 (Translated Barbed Bisimilarity). *Let $P, Q \in \mathcal{P}_a$. Then P and Q are translated barbed bisimilar with respect to $\llbracket \cdot \rrbracket_a^s$, denoted by $P \approx_a^s Q$, if*

1. $P \Downarrow_\checkmark \text{ iff } Q \Downarrow_\checkmark$,
2. for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$, $P \Downarrow_\mu^s \text{ iff } Q \Downarrow_\mu^s$,
3. for all $P' \in \mathcal{P}_a$, $P \longrightarrow P'$ implies $Q \Longrightarrow \approx_a^s P'$, and
4. for all $Q' \in \mathcal{P}_a$, $Q \longrightarrow Q'$ implies $P \Longrightarrow \approx_a^s Q'$.

And P and Q are translated barbed bisimilar with respect to $\llbracket \cdot \rrbracket_a^m$, denoted by $P \approx_{a,1}^m Q$, if

1. $P \Downarrow_\checkmark \text{ iff } Q \Downarrow_\checkmark$,
2. for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$, $P \Downarrow_\mu^m \text{ iff } Q \Downarrow_\mu^m$,
3. for all $P' \in \mathcal{P}_a$, $P \longrightarrow P'$ implies $Q \Longrightarrow \approx_{a,1}^m P'$, and
4. for all $Q' \in \mathcal{P}_a$, $Q \longrightarrow Q'$ implies $P \Longrightarrow \approx_{a,1}^m Q'$.

Note that the first condition of each equivalence ensures that it is success respecting as required in Section 1.3 by Definition 13. Conditions 2. to 4. then define a version of weak barbed bisimilarity which utilises translated observables instead of standard barbs. Note that we consider the translation of input as well as output observables, although our target language is asynchronous. However, since in case of $\llbracket \cdot \rrbracket_a^m$ both kinds of source term actions are translated into requests and instantiations of sum locks, i.e., into outputs, the presented kind of barbed bisimilarity does consider barbs on outputs only. So it is an asynchronous variant of barbed bisimulation. Moreover note, that due to the definition above we do not consider any barbs except for translated barbs. However, analysing the

⁴ Note that we present this fact just to visualize our intuition. We do not use it within another proof.

encoding function $\llbracket \cdot \rrbracket_a^m$, we observe, that for all target terms all free in- or outputs are on the request channels p_i and p_o . So, since we do only consider target terms, requests are indeed the only interesting barbs of $\llbracket \cdot \rrbracket_a^m$.

Alternatively, we could decide not to consider barbs at all, by omitting the second condition of $\approx_a^s$ and $\approx_{a,1}^m$. We result then in an equivalence that considers only reachability of $\checkmark$ as abstract behaviour of a term. Note that this intuition goes along very well with the criteria defined by Gorla as they also do only require a similar reachability of $\checkmark$, because reachability of success is defined independent of a specific source or target language. An advantage of such an equivalence is the fact, that it is independent of the considered encoding function. However, the resulting equivalence is obviously strictly weaker than $\approx_a^s$ and $\approx_{a,1}^m$. Moreover, $\approx_a^s$ and $\approx_{a,1}^m$ much better describe how the encoding function proceeds source terms and emulate source term steps. So we will use these equivalences in the following.

In case of $\llbracket \cdot \rrbracket_a^m$ we are faced with an other problem concerning the choice of an appropriate equivalence, although that problem is by far not that crucial as observable junk. As explained above, the encodings of structural congruent source terms can differ in the number and nature of reachable intermediate states (compare to Example 1, Definition 23, and the following discussion above). Operational Soundness explicitly allows for intermediate states, i.e., target term states that do not map to the encodings of any of the corresponding source terms. However, if $\succ$ does distinguish target terms by reachability of intermediate states, we have a problem with the CONG rule of Figure 2 and operational completeness of Definition 9. Let us consider the source terms $S = (a.S_1 + a.S_2) \mid \bar{a}.S_3 \mid a.S_4$ and $S' = \bar{a}.S_3 \mid (a.S_1 + a.S_2) \mid a.S_4$ again. The source term $b.S \mid \bar{b}$ can reduce to S but by the CONG rule it can reduce to S' as well. $\llbracket \cdot \rrbracket_a^m$ can emulate the first step modulo $\approx_{a,1}^m$ but not the second step. Note that the CONG rule is used to shorten the presentation of the reduction semantics, but it is neither necessary nor was it the originally choice. So the most natural way to circumvent this problem is to rephrase the rules of the reduction semantics by avoiding the CONG rule and with it the possibility to arbitrary reorder the subprocesses during reductions. However we can also circumvent this problem by using an equivalence which does not distinguishes terms by the reachability of intermediate states.

Definition 27 (Translated Barbed Bisimilarity). *Let $P, Q \in \mathcal{P}_a$. Then P and Q are translated barbed bisimilar with respect to $\llbracket \cdot \rrbracket_a^m$, denoted by $P \approx_{a,2}^m Q$, if*

1. $P \Downarrow_{\checkmark} \text{ iff } Q \Downarrow_{\checkmark}$,
2. for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$, $P \Downarrow_{\mu}^m \text{ iff } Q \Downarrow_{\mu}^m$,
3. for all $P' \in \mathcal{P}_a$, $P \Longrightarrow P'$ implies that there exists some $P'' \in \mathcal{P}_a$ such that $Q \Longrightarrow \approx_{a,2}^m P''$ and $P' \Longrightarrow P''$, and
4. for all $Q' \in \mathcal{P}_a$, $Q \Longrightarrow Q'$ implies that there exists some $Q'' \in \mathcal{P}_a$ such that $P \Longrightarrow \approx_{a,2}^m Q''$ and $Q' \Longrightarrow Q''$.

Note that the second version of $\approx_a^m$ is strictly weaker than the first version and that we only use it to circumvent the problem with the CONG rule in operational completeness (and the therefore necessary Lemma 21). Because of this we prove the remaining results using the stricter equivalence; silently omitting the subscript 1.

Before we use these relations, we prove that they are indeed equivalences.

Lemma 14. *All presented translated barbed bisimulations are equivalence relations.*

Proof. We have to show that $\approx_a^s$, $\approx_{a,1}^m$, and $\approx_{a,2}^m$ are reflexive, symmetric, and transitive. Reflexivity and transitivity follow directly by definition. For transitivity of $\approx_{a,1}^m$ assume $P, Q, R \in \mathcal{P}_a$ such that $P \approx_{a,1}^m Q$ and $Q \approx_{a,1}^m R$. By the first condition we have $P \Downarrow_{\checkmark} \text{ iff } Q \Downarrow_{\checkmark} \text{ iff } R \Downarrow_{\checkmark}$. And by the second condition for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$ we have $P \Downarrow_{\mu}^m \text{ iff } Q \Downarrow_{\mu}^m \text{ iff } R \Downarrow_{\mu}^m$. So we can conclude that $P \Downarrow_{\checkmark} \text{ iff } R \Downarrow_{\checkmark}$ and $P \Downarrow_{\mu}^m \text{ iff } R \Downarrow_{\mu}^m$.

By the third condition for all $P' \in \mathcal{P}_a$ with $P \Longrightarrow P'$ there is some $Q' \in \mathcal{P}_a$ such that $Q \Longrightarrow Q'$ and $P' \approx_{a,1}^m Q'$. Without loss of generality let us assume, that the sequence $Q \Longrightarrow Q'$ is of length n , i.e., there are $Q_1, \dots, Q_n \in \mathcal{P}_a$ such that $Q_0 \Longrightarrow Q_1 \Longrightarrow \dots \Longrightarrow Q_n$, $Q_0 = Q$, and $Q_n = Q'$. Let $R = R_0$ and $R' = R_n$. Then, by the third condition, for each step in $Q \Longrightarrow Q'$, i.e., for each $Q_{i-1} \Longrightarrow Q_i$ with $0 < i \leq n$, there is some $R_i \in \mathcal{P}_a$ such that $R_{i-1} \Longrightarrow R_i$ with $R_i \approx_{a,1}^m Q_i$. So we conclude that for all $P' \in \mathcal{P}_a$ with $P \Longrightarrow P'$ there is some $R' \in \mathcal{P}_a$ such that $R \Longrightarrow R'$ and $P' \approx_{a,1}^m R'$. The argumentation for the last condition is similar.

The argumentation for $\approx_a^s$ and $\approx_{a,2}^m$ is similar. □

The observable junk does not only rule out standard equivalences but also congruences with respect to contexts, that allow for interaction with observable junk. In both encodings such an interaction can for instance lead to a positive instantiation of a formerly negative instantiation of a sum lock and so turn observable junk into a translated observable, or it can instantiate a sender lock and so complete emulations on junk.

Example 2. Let us consider the target terms $T_1 = (\nu l) (\llbracket \bar{y}.\checkmark \rrbracket_a^s \mid \bar{l}(\perp))$ and $T_2 = (\nu l) (\llbracket \bar{y}.\checkmark \rrbracket_a^m \mid \bar{l}(\perp))$. By the Lemmata 26 and 27 in the next section, we prove that both terms are junk. They be produced as remains of emulations (or a part of such a remain), e.g. for a source term $\bar{x} + \bar{y}.\checkmark \mid x$. Since neither T_1 nor T_2 reaches any translated

observables or unguarded occurrence of $\checkmark$, we have $T_1 \approx_a^s \llbracket \mathbf{0} \rrbracket_a^s$ and $T_2 \approx_a^m \llbracket \mathbf{0} \rrbracket_a^m$. However, we can distinguish T_1 from $\llbracket \mathbf{0} \rrbracket_a^s$ by the context $\mathcal{C}_1([\cdot]) = [\cdot] \mid \varphi_a^s(y)(-, s, -).\bar{s}$, because $\mathcal{C}_1(T_1) \Downarrow_{\checkmark}$ but $\mathcal{C}_1(\mathbf{0}) \not\Downarrow_{\checkmark}$. So $\mathcal{C}_1(T_1) \not\approx_a^s \mathcal{C}_1(\mathbf{0})$. Accordingly, we can distinguish T_2 from $\llbracket \mathbf{0} \rrbracket_a^m$ by the context $\mathcal{C}_2([\cdot]) = [\cdot] \mid p_o(-, -, s, -).\bar{s}$, where p_o is the free output request channel of $\llbracket \bar{y}.\checkmark \rrbracket_a^m$. Again we have $\mathcal{C}_2(T_2) \Downarrow_{\checkmark}$ but $\mathcal{C}_2(\mathbf{0}) \not\Downarrow_{\checkmark}$, i.e., $\mathcal{C}_2(T_2) \not\approx_a^m \mathcal{C}_2(\mathbf{0})$.

Because of this, in order to prove operational completeness, we have to reduce the number of contexts we consider to obtain a congruence. Intuitively, we consider only contexts that respect the protocol of the encoding function. Thus, we consider only contexts that, if their argument is a target term as for instance the encoding of $\mathbf{0}$, result in a target term.

Definition 28 (Translated Barbed Congruence). *Two terms $T_1, T_2 \in \mathcal{P}_a$ are translated barbed congruent with respect to $\llbracket \cdot \rrbracket_a^s$, denoted as $T_1 \cong_a^s T_2$, if*

$$\forall \mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a . \mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_{a \uparrow} \llbracket \cdot \rrbracket_a^s \text{ implies } \mathcal{C}(T_1) \approx_a^s \mathcal{C}(T_2).$$

Two target terms $T_1, T_2 \in \mathcal{P}_a$ are translated barbed congruent with respect to $\llbracket \cdot \rrbracket_a^m$, denoted as $T_1 \cong_{a,1}^m T_2$, if

$$\forall \mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a . \mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^m) \in \mathcal{P}_{a \uparrow} \llbracket \cdot \rrbracket_a^m \text{ implies } \mathcal{C}(T_1) \approx_{a,1}^m \mathcal{C}(T_2).$$

Two target terms $T_1, T_2 \in \mathcal{P}_a$ are translated barbed congruent with respect to $\llbracket \cdot \rrbracket_a^m$, denoted as $T_1 \cong_{a,2}^m T_2$, if

$$\forall \mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a . \mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^m) \in \mathcal{P}_{a \uparrow} \llbracket \cdot \rrbracket_a^m \text{ implies } \mathcal{C}(T_1) \approx_{a,2}^m \mathcal{C}(T_2).$$

Note that we again usually only consider the stricter first variant of the congruence $\cong_a^m$, while silently omitting the subscript 1. Operational correspondence considers only target terms, so it would suffice to define the congruence over target terms only. However, in defining it over all terms of the target language we gain more flexibility. We will use these flexibility in the proof of operational completeness to stepwise reduce junk which in some cases leads to non target terms. Since these non target terms are behavioural equivalent to the considered target terms, they serve as connecting pieces to link the target terms modulo $\cong_a^s$ or $\cong_a^m$. Moreover note that the respective congruence relations are strictly weaker than their corresponding equivalences.

Example 3. Let us consider the target terms $T_1 = \llbracket \bar{y}.\checkmark \rrbracket_a^s$, $T'_1 = \llbracket \bar{y}.\mathbf{0} \rrbracket_a^s$, $T_2 = \llbracket \bar{y}.\checkmark \rrbracket_a^m$, and $T'_2 = \llbracket \bar{y}.\mathbf{0} \rrbracket_a^m$. Obviously $T_1 \approx_a^s T'_1$ and $T_2 \approx_a^m T'_2$. But neither $T_1 \cong_a^s T'_1$ nor $T_2 \cong_a^m T'_2$, because in both cases the context has only to provide a translated input observable on $\varphi_a^s(y)$ or $\varphi_a^m(y)$, respectively. So in case of $\llbracket \cdot \rrbracket_a^s$ the context $\mathcal{C}([\cdot]) = [\cdot] \mid \llbracket x \rrbracket_a^s$ suffice to distinguish T_1 and T'_1 , because $\mathcal{C}(T_1) \Downarrow_{\checkmark}$ but $\mathcal{C}(T'_1) \not\Downarrow_{\checkmark}$. The argumentation for $\llbracket \cdot \rrbracket_a^m$ is similar, but due to the complex encoding of the parallel operator the respective distinguishing context is rather large. Because of that, intuitively, two equivalent target terms are congruent, only if the encoded continuations of their translated observables are again equivalent.

Of course, all presented congruences are again equivalences.

Lemma 15. *All presented translated barbed congruences are equivalence relations.*

Proof. Let $T_1, T_2, T_3 \in \mathcal{P}_a$. Then $\mathcal{C}(T_1) \approx_a^s \mathcal{C}(T_1)$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$; so $T_1 \cong_a^s T_1$. Moreover, if $T_1 \cong_a^s T_2$, then $\mathcal{C}(T_1) \approx_a^s \mathcal{C}(T_2)$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_{a \uparrow} \llbracket \cdot \rrbracket_a^s$. Since $\approx_a^s$ is an equivalence, then also $\mathcal{C}(T_2) \approx_a^s \mathcal{C}(T_1)$ for all such contexts, i.e., $T_2 \cong_a^s T_1$. Finally, if $T_1 \cong_a^s T_2$ and $T_2 \cong_a^s T_3$, then $\mathcal{C}(T_1) \approx_a^s \mathcal{C}(T_2)$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_{a \uparrow} \llbracket \cdot \rrbracket_a^s$, and $\mathcal{C}(T_2) \approx_a^s \mathcal{C}(T_3)$ for all such contexts. So also $\mathcal{C}(T_1) \approx_a^s \mathcal{C}(T_3)$ for all such contexts, i.e., $T_1 \cong_a^s T_3$. We conclude that $\cong_a^s$ is an equivalence.

The argumentation for $\cong_{a,1}^m$ and $\cong_{a,2}^m$ is similar. □

Moreover, the presented congruences include the structural congruence on the target language, because it is already included in the respective bisimulations.

Lemma 16. *Translated barbed bisimulation includes structural congruence, i.e.,*

$$\forall T_1, T_2 \in \mathcal{P}_a . T_1 \equiv T_2 \text{ implies } T_1 \approx_a^s T_2 \wedge T_1 \approx_a^m T_2.$$

Proof. Let us assume $T_1 \equiv T_2$. Then, by rule CONG in Figure 2, T_1 and T_2 can perform exactly the same steps such that the successors are again structural congruent. Note that this holds even in case of $\llbracket \cdot \rrbracket_a^m$ and is obviously a stronger feature than the third and fourth condition of $\approx_{a,2}^m$ (compare to Definition 27). Since, by Definition 11, reachability of success is defined modulo structural congruence, T_1 and T_2 have the same chance to reach success,

i.e., $T_1 \Downarrow_{\checkmark}$ iff $T_2 \Downarrow_{\checkmark}$. Similarly, translated observables are defined modulo structural congruence for both encodings in Definition 25. Note that we do not consider translated observables on restricted names, since the corresponding in- and outputs in the source terms are no observables as well. Because of that translated observables can not be changed by alpha conversion. So T_1 and T_2 have the same set of translated observables and the same chance to reach a translated observable, i.e., $(T_1 \Downarrow_{\mu}^s \text{ iff } T_2 \Downarrow_{\mu}^s)$, $(T_1 \Downarrow_{\mu}^m \text{ iff } T_2 \Downarrow_{\mu}^m)$, $(T_1 \Downarrow_{\mu}^s \text{ iff } T_2 \Downarrow_{\mu}^s)$, and $(T_1 \Downarrow_{\mu}^m \text{ iff } T_2 \Downarrow_{\mu}^m)$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. So $T_1 \approx_a^s T_2$ and $T_1 \approx_a^m T_2$. $\square$

Lemma 17. *Weak translated barbed congruence includes structural congruence, i.e.,*

$$\forall T_1, T_2 \in \mathcal{P}_a. T_1 \equiv T_2 \text{ implies } T_1 \cong_a^s T_2 \wedge T_1 \cong_a^m T_2.$$

Proof. By Definition 28, $\cong_a^s$ is the largest congruence on contexts restricted to target terms included in $\approx_a^s$, and $\cong_a^m$ is the largest congruence on contexts restricted to target terms included in $\approx_a^m$. Note that Definition 28 restricts only the contexts but not the considered terms. Thus, since by Lemma 16 structural congruence $\equiv$ is included in $\approx_a^s$ and $\approx_a^m$, it is included in $\cong_a^s$ and $\cong_a^m$. $\square$

Remember, that to our intuition pure administrative steps are only pre- or postprocessing steps that do not influence which emulations can be completed. To underpin that intuition, we prove that pure administrative steps do not change the state of a target term modulo the considered equivalences and congruences.

Lemma 18. *Pure administrative steps do not influence the state of a target term modulo translated barbed bisimilarity or translated barbed congruence with respect to $\llbracket \cdot \rrbracket_a^s$, i.e.,*

$$\forall T, T' \in \mathcal{P}_a \llbracket \cdot \rrbracket_a^s. T \Longrightarrow T' \text{ implies } T \approx_a^s T' \wedge T \cong_a^s T'.$$

Proof. Translated barbed bisimilarity is some kind of weak bisimilarity that takes instead of observables the reachability of $\checkmark$ and the reachability of translated observables into account. Note that it is not possible to reduce $\checkmark$. So, in case $T \Longrightarrow T'$, the only way that leads to $\neg(T \Downarrow_{\checkmark} \text{ iff } T' \Downarrow_{\checkmark})$ is that in the sequence of steps from T to T' there is a step that rules out a former possible way to unguard some occurrence of $\checkmark$. Since by Definition 25 pure administrative steps can not consume translated observables, the same holds for the consideration of translated observables. We have to show, that it not possible when using only pure administrative steps to rule out a way to a translated observable or an unguarded occurrence of $\checkmark$.

Obviously, in case none of the pure administrative steps rules out any other sequence of steps, i.e. if none of the administrative steps is in conflict to any other sequence of step, this condition holds. Because of that, by Lemma 9, $T \Longrightarrow T'$ implies $(T \Downarrow_{\checkmark} \text{ iff } T' \Downarrow_{\checkmark})$.

For the same reason, and since pure administrative steps do neither consumes positive instantiations of sum locks nor outputs on translated source terms, they do not influence the set of reachable translated observables, i.e., $T \Downarrow_{\mu}^s \text{ iff } T' \Downarrow_{\mu}^s$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. Note, that such a step can restore a positive or negative instantiation of a sum lock by resolving a test on a negative instantiated sum lock or can unguard new requests and sum lock instantiations by a step on a sender lock, so pure administrative steps influence the set of translated observables. But, since they do not rule out a run that leads to a translated observable, they do not influence the set of reachable translated observables. So $T \approx_a^s T'$.

Since pure administrative steps do not influence the state of arbitrary target terms modulo $\approx_a^s$ and since the congruence $\cong_a^s$ does only consider target term contexts (compare to Definition 28), pure administrative steps do not influence the state of target terms modulo $\cong_a^s$, i.e., $T \cong_a^s T'$. $\square$

Lemma 19. *Pure administrative steps do not influence the state of a target term modulo translated barbed bisimilarity or translated barbed congruence with respect to $\llbracket \cdot \rrbracket_a^m$, i.e.,*

$$\forall T, T' \in \mathcal{P}_a \llbracket \cdot \rrbracket_a^m. T \Longrightarrow T' \text{ implies } T \approx_a^m T' \wedge T \cong_a^m T'.$$

Proof. Translated barbed bisimilarity is some kind of weak bisimilarity that takes instead of observables the reachability of $\checkmark$ and the reachability of translated observables into account. Note that it is not possible to reduce $\checkmark$. So, in case $T \Longrightarrow T'$, the only way that leads to $\neg(T \Downarrow_{\checkmark} \text{ iff } T' \Downarrow_{\checkmark})$ is that in the sequence of steps from T to T' there is a step that rules out a former possible way to unguard some occurrence of $\checkmark$. Since by Definition 25 pure administrative steps can not consume translated observables, the same holds for the consideration of translated observables. We have to show, that it not possible when using only pure administrative steps to rule out a way to a translated observable or an unguarded occurrence of $\checkmark$.

Obviously, in case none of the pure administrative steps rules out any other sequence of steps, i.e. if none of the pure administrative steps is in conflict to any other sequence of steps, this condition holds. Fortunately, indeed

most of the pure administrative steps are not conflicting. By Lemma 10, the condition $T \approx_a^m T'$ holds for all steps that are on a sender lock or do not unguard an instantiation of a chain lock carrying a request channel.

Revisiting the argumentation in the proof of Lemma 10 we observe that the remaining steps either influence the order of requests in chains of right requests (compare to `procRightOutReq` and `procRightInReq`) or the order of encoded continuations in the chain build up by the encoding of a replicated input. By Lemma 11, these steps do not introduce deadlock, moreover revisiting the argumentation of the proof of this lemma we observe, that their impact on the ordering within the chain is indeed their only impact on the behaviour of target terms. Since all encoded continuations of a replicated input are initially the same, their order does not matter for the reachability of $\checkmark$ or translated observables. The same holds for the order of requests, because regardless of their order eventually each combination is checked. Indeed, a different order may only lead to more or less necessary invisible steps on requests channels to combine a specific pair of requests. Because of that, even the pure administrative steps that unguards an instantiation of a chain lock do not influence the state of the target term modulo $\approx_a^m$. So $T \approx_a^m T'$.

Since pure administrative steps do not influence the state of arbitrary target terms modulo $\approx_a^m$ and since the congruence $\cong_a^m$ does only consider target term contexts (compare to Definition 28), pure administrative steps do not influence the state of target terms modulo $\cong_a^m$, i.e., $T \cong_a^m T'$. $\square$

Note that due to these two lemmata we can mostly ignore pure administrative steps in the following proofs, since they are invisible modulo the considered equivalence and congruence relations. To handle the `CONG` rule in the proof of operational completeness we prove that both encodings preserve structural congruence of source terms modulo the presented equivalences and congruences.

Lemma 20. *The encoding $\llbracket \cdot \rrbracket_a^s$ preserves structural congruence of source terms modulo translated barbed bisimilarity and translated barbed congruence, i.e.,*

$$\forall S, S' \in \mathcal{P}_s . S \equiv S' \text{ implies } \llbracket S \rrbracket_a^s \approx_a^s \llbracket S' \rrbracket_a^s \wedge \llbracket S \rrbracket_a^s \cong_a^s \llbracket S' \rrbracket_a^s .$$

Proof. The strict use of the renaming policy φ_a^s , i.e., the fact that source term names are translated into single names not used by the encoding function for special purposes, ensures the preservation of equality modulo alpha conversion. Since the parallel operator, the match operator, and restriction are translated rigidly, the encoding $\llbracket \cdot \rrbracket_a^s$ preserves structural congruence of source terms for all rules except for $P \mid \mathbf{0} \equiv P$, i.e., if S and S' are structural congruent without using the rule $P \mid \mathbf{0} \equiv P$, then $\llbracket S \rrbracket_a^s \equiv \llbracket S' \rrbracket_a^s$. By Lemma 16, then $\llbracket S \rrbracket_a^s \approx_a^s \llbracket S' \rrbracket_a^s$ and, by Lemma 17, then $\llbracket S \rrbracket_a^s \cong_a^s \llbracket S' \rrbracket_a^s$.

The rule $P \mid \mathbf{0} \equiv P$ is not preserved, because the empty sum $\mathbf{0}$ is not translated rigidly, so e.g. $\mathbf{0} \mid \mathbf{0} \equiv \mathbf{0}$ but $\llbracket \mathbf{0} \mid \mathbf{0} \rrbracket_a^s = (\nu l) \bar{l} \langle \top \rangle \mid (\nu l) \bar{l} \langle \top \rangle \neq (\nu l) \bar{l} \langle \top \rangle = \llbracket \mathbf{0} \rrbracket_a^s$. Note that, because of the renaming policy φ_a^s and the rigid translation of restriction, the rule $(\nu n) \mathbf{0} \equiv \mathbf{0}$ is preserved, i.e., since $\varphi_a^s(n) \notin \text{fn}(\llbracket \mathbf{0} \rrbracket_a^s)$, we have $\llbracket (\nu n) \mathbf{0} \rrbracket_a^s = (\nu \varphi_a^s(n)) (\nu l) \bar{l} \langle \top \rangle \equiv (\nu l) \bar{l} \langle \top \rangle = \llbracket \mathbf{0} \rrbracket_a^s$. However, since $\mathbf{0}$ is translated into a closed term that can not perform any step, its encoding behaves as $\mathbf{0}$. In particular $\llbracket \mathbf{0} \rrbracket_a^s$ can not interact with any context and does not reach success or any translated observable on its own. So, even in this case, we have $\llbracket S \rrbracket_a^s \approx_a^s \llbracket S' \rrbracket_a^s$ and $\llbracket S \rrbracket_a^s \cong_a^s \llbracket S' \rrbracket_a^s$. $\square$

Since $\llbracket \cdot \rrbracket_a^m$ does not translate the parallel operator rigidly, it does not directly preserve structural congruence of source terms. But, since the encoding preserves the abstract behaviour of source terms, the encodings of structural congruent source terms are similar modulo equivalences measuring only these abstract behaviour. As already explained, to prove the following statement, the equivalence must not distinguish terms by their reachable intermediate states.

Lemma 21. *The encoding $\llbracket \cdot \rrbracket_a^m$ preserves structural congruence of source terms modulo translated barbed bisimilarity and translated barbed congruence, i.e.,*

$$\forall S, S' \in \mathcal{P}_m . S \equiv S' \text{ implies } \llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m \wedge \llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m .$$

Proof. Again, the strict use of the renaming policy φ_a^m , i.e., the fact that source term names are translated into single names not used by the encoding function for special purposes, ensures the preservation of equality modulo alpha conversion. So $S \equiv_\alpha S'$ implies $\llbracket S \rrbracket_a^m \equiv_\alpha \llbracket S' \rrbracket_a^m$. Also, the rigid translation of the match operator and restriction ensures the preservation of structural congruence modulo the rules $[a = a] P \equiv P$, $(\nu n) \mathbf{0} = \mathbf{0}$, $(\nu n) (\nu m) P \equiv (\nu m) (\nu n) P$, and $P \mid (\nu n) Q \equiv (\nu n) (P \mid Q)$ if $n \notin \text{fn}(P)$. So, if S and S' do only differ due to one or more of these four rules, then $\llbracket S \rrbracket_a^m \equiv \llbracket S' \rrbracket_a^m$. By Lemma 16, we conclude $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and, by Lemma 17, we conclude $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$ for both of the above cases.

With the preservation of these rules in mind we show the lemma by an induction over the proof tree of $S \equiv S'$, i.e., over the number of structural congruence rules which are applied to show $S \equiv S'$.

Base Case: If $S = S'$, then $\llbracket S \rrbracket_a^m = \llbracket S' \rrbracket_a^m$. So, by reflexivity, $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Induction Hypothesis: If S and S' can be proved to be structural congruent within n applications of structural congruence rules, then $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Induction Step: S and S' can be proved to be structural congruent within $n+1$ applications of structural congruence rules. Let $S'' \in \mathcal{P}_m$ be such that S and S'' can be proved to be structural congruent within n applications of structural congruence rules and S'' and S' can be proved to be structural congruent directly by one application of a structural congruence rule, i.e., $S \equiv S'' \equiv S'$. By the induction hypothesis, $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S'' \rrbracket_a^m$ and $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S'' \rrbracket_a^m$. We proceed with a case split over the rule necessary to prove $S'' \equiv S'$.

Case of Rule $P \mid \mathbf{0} \equiv P$: In this case $S'' = P \mid \mathbf{0}$ and $S' = P$ for some $P \in \mathcal{P}_m$. By Figure 4,

$$\begin{aligned} \llbracket S'' \rrbracket_a^m = & (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\ & (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\ & \mid (\nu p_o, p_i) ((\nu l) \bar{l} \langle \top \rangle \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \mid \text{pushReq}) \end{aligned}$$

and $\llbracket S' \rrbracket_a^m = \llbracket P \rrbracket_a^m$. Obviously $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$ are not structural congruent. However, $\llbracket P \rrbracket_a^m$ appears unguarded within $\llbracket S'' \rrbracket_a^m$, so if $\llbracket S' \rrbracket_a^m$ reaches $\checkmark$ or a translated observable then so does $\llbracket S'' \rrbracket_a^m$. Moreover we observe, that, since the encoding of $\mathbf{0}$ does not emit any requests, the hole right branch of $\llbracket S'' \rrbracket_a^m$

$$(\nu p_o, p_i) ((\nu l) \bar{l} \langle \top \rangle \mid \text{procRightOutReq} \mid \text{procRightInReq})$$

can do nothing but two steps on chain locks. Because of that requests of $\llbracket P \rrbracket_a^m$ are prepared to be transmitted to the right side by procLeftOutReq and procLeftInReq but they are never received at the right side. What remains is the upward pushing of all requests of $\llbracket P \rrbracket_a^m$ by the interplay of procLeftOutReq , procLeftInReq , and pushReq . Because of that, for all target term contexts $\llbracket P \mid \mathbf{0} \rrbracket_a^m$ behaves as $\llbracket P \rrbracket_a^m$, i.e., $\llbracket S'' \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and $\llbracket S'' \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$. Since $\approx_{a,2}^m$ and $\cong_{a,2}^m$ are equivalences (compare to Lemmata 14 and 15), by transitivity, we conclude $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Case of Rule $P \mid Q \equiv Q \mid P$: In this case $S'' = P \mid Q$ and $S' = Q \mid P$ for some $P, Q \in \mathcal{P}_m$. Their encodings are given by:

$$\begin{aligned} \llbracket S'' \rrbracket_a^m = & (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\ & (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\ & \mid (\nu p_o, p_i) (\llbracket Q \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \mid \text{pushReq}) \\ \llbracket S' \rrbracket_a^m = & (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\ & (\nu p_o, p_i) (\llbracket Q \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\ & \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \mid \text{pushReq}) \end{aligned}$$

Since all combinations of left and right requests are checked, $\llbracket S'' \rrbracket_a^m$ can emulate the same source term steps as $\llbracket S' \rrbracket_a^m$. However, since $\llbracket P \rrbracket_a^m$ and $\llbracket Q \rrbracket_a^m$ are exchanged at the outermost parallel operator the roles of left and right requests are exchanged. As a consequence, if a combination of requests from $\llbracket P \rrbracket_a^m$ and $\llbracket Q \rrbracket_a^m$ leads to a test on the respective sum locks, the order in which these locks are tested is different in $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$. So $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$ differ in their total ordering of sum locks. The ordering in $\llbracket S'' \rrbracket_a^m$ is based on the structure induced by the nesting of parallel operators in $P \mid Q$; while the ordering in $\llbracket S' \rrbracket_a^m$ is based on the structure induced by the parallel operator nesting in $Q \mid P$. Note that, since in both cases this structure is a binary tree, by Lemma 12, the encoding does not introduce deadlock. But as explained in Example 1 the different orderings may lead to different reachable intermediate states. Apart from intermediate states $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$ are similar, i.e., they have the same chance to reach success or translated observables.

By Definition 27, $\approx_{a,2}^m$ explicitly allows for different reachable intermediate states. Because of that, $\llbracket S'' \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$. Analysing the encoding function in Figure 4 we observe that any encoded source term has at most two free names that are used as channels—remember that translated source term names are never used as channels within $\llbracket \cdot \rrbracket_a^m$. Because of that, when placed within a target term context, $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$ can start an interaction with the context only by transmitting their requests. Because we consider only target term contexts, i.e., contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^m) \in \mathcal{P}_a \uparrow \llbracket \cdot \rrbracket_a^m$, the context

respects the protocol implemented by the encoding function. So, if $\llbracket S'' \rrbracket_a^m$ provides a translated observable and the context has the matching translated observable, then the context can interact with $\llbracket S'' \rrbracket_a^m$ to emulate a source term step. Doing so, an encoded continuation, i.e., an encoded source term, is unguarded within the continuation of $\llbracket S'' \rrbracket_a^m$. Since $S'' \equiv S'$, the same context can emulate the same source term step when interacting with $\llbracket S' \rrbracket_a^m$. Moreover, doing so, again an encoded source term is unguarded within the continuation of $\llbracket S' \rrbracket_a^m$ and the respective source terms of these continuations in case of $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$ are again structural congruent. Because of this we can prove the preservation of structural congruence of source terms is also preserved modulo $\cong_{a,2}^m$ by assuming an arbitrary context and perform an induction over the number of emulations resulting from an interaction of the context with $\llbracket S'' \rrbracket_a^m$. So we conclude $\llbracket S'' \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Since $\approx_{a,2}^m$ and $\cong_{a,2}^m$ are equivalences (compare to Lemmata 14 and 15), by transitivity, we conclude $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Case of Rule $P \mid (Q \mid R) \equiv (P \mid Q) \mid R$: In this $S'' = P(Q \mid R)$ and $S' = (P \mid Q) \mid R$ for some $P, Q, R \in \mathcal{P}_m$.

Their encodings are given by

$$\begin{aligned} \llbracket S'' \rrbracket_a^m = & (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\ & (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\ & \mid (\nu p_o, p_i) ((\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\ & \quad (\nu p_o, p_i) (\llbracket Q \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\ & \quad \mid (\nu p_o, p_i) (\llbracket R \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \quad \mid \text{pushReq}) \\ & \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \mid \text{pushReq}) \end{aligned}$$

and

$$\begin{aligned} \llbracket S' \rrbracket_a^m = & (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\ & (\nu p_o, p_i) ((\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\ & \quad (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\ & \quad \mid (\nu p_o, p_i) (\llbracket Q \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \quad \mid \text{pushReq}) \\ & \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\ & \mid (\nu p_o, p_i) (\llbracket R \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \mid \text{pushReq}). \end{aligned}$$

In $\llbracket S'' \rrbracket_a^m$ the encoding of Q appears left and the encoding of R appears right within the encoding of a parallel operator. Together they form the right branch of a surrounding encoding of a parallel operator, there the left branch is filled with $\llbracket P \rrbracket_a^m$. In opposite in $\llbracket S' \rrbracket_a^m$ the terms $\llbracket P \rrbracket_a^m$ and $\llbracket Q \rrbracket_a^m$ are left and right of a parallel operator encoding which is the left branch of a surrounding parallel operator encoding, where $\llbracket R \rrbracket_a^m$ appears right. However, since all requests are pushed upwards to each surrounding parallel operator encoding, again all combinations of requests among the three encoded subterms $\llbracket P \rrbracket_a^m$, $\llbracket Q \rrbracket_a^m$, and $\llbracket R \rrbracket_a^m$ are checked in $\llbracket S'' \rrbracket_a^m$ as well as in $\llbracket S' \rrbracket_a^m$. Moreover, we observe that in both encodings $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$ the encoding of P is always left to the encodings of Q and R , and the encoding of Q is always left to the encoding of R . So in this case $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$ do not differ by the underlying total ordering of sum locks, i.e., they reach the same intermediate states. So the behaviour of $\llbracket S'' \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m$ does only differ by pure administrative steps on requests but they have the same chance to reach $\checkmark$ and translated observables, i.e., $\llbracket S'' \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$. Revisiting the argumentation of the case before we also get $\llbracket S'' \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$. Since $\approx_{a,2}^m$ and $\cong_{a,2}^m$ are equivalences (compare to Lemmata 14 and 15), by transitivity, we conclude $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Else: For the remaining rules we can apply the above argumentation to show that $\llbracket S'' \rrbracket_a^s \equiv \llbracket S' \rrbracket_a^s$. By the Lemmata 16 and 17, we have $\llbracket S'' \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and $\llbracket S'' \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$. By Lemma 14 and Lemma 15, $\approx_{a,2}^m$ and $\cong_{a,2}^m$ are equivalences. Thus, by transitivity, we conclude $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S' \rrbracket_a^m$ and $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

□

These two lemmata finally prove that the intermediate states in combination with the application of the CONG rule on source terms do not falsify the criterion on operational completeness modulo $\approx_{a,2}^m$.

2.5 Junk

We consider remains of emulations that behave modulo $\approx_a^s$ and $\approx_a^m$ like $\mathbf{0}$ and do not influence the possibility or inability to emulate further source term steps as junk. The emulation of source term steps may leave different kinds of junk. So, e.g. in order to show operational completeness, we have to prove that junk does no harm.

Of course we are only interested in kinds of junk that appear in target terms, i.e., that are pieces of target terms. However, to ease the argumentation on the proof of operational completeness we want to allow to stepwise reduce junk. Unfortunately, as soon as we reduce a target term by the first piece of junk it is often no target term any more. So, in order to allow for a stepwise reduction of junk, we give a recursive definition of what it means to be a piece of a target term.

Definition 29 (Piece of a Target Term). A term $T \in \mathcal{P}_a$ is a piece of a target term of $\llbracket \cdot \rrbracket_a^s$, denoted by $T \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s)$, if

$$T \in \mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s \vee (\exists T', J \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . T \equiv (\nu \tilde{x}) T' \wedge T \cong_a^s (\nu \tilde{x}) (T' \mid J) \wedge (\nu \tilde{x}) (T' \mid J) \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s)).$$

Accordingly, a term $T \in \mathcal{P}_a$ is a piece of a target term of $\llbracket \cdot \rrbracket_a^m$, denoted by $T \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^m)$, if

$$T \in \mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^m \vee (\exists T', J \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . T \equiv (\nu \tilde{x}) T' \wedge T \cong_a^m (\nu \tilde{x}) (T' \mid J) \wedge (\nu \tilde{x}) (T' \mid J) \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^m)).$$

Intuitively, the definition above allows for a piece of a target term to recover the corresponding target term by stepwise restoring the reduced junk. Moreover note, that, although the relations $\cong_a^s$ and $\cong_a^m$ are not sensitive to divergence, they are sensitive to deadlock. That is why we require $T \cong_a^s (\nu \tilde{x}) (T' \mid J)$ or $T \cong_a^m (\nu \tilde{x}) (T' \mid J)$ to ensure that indeed only junk is removed and so, no deadlock is introduced.

Definition 30 (Junk). A term $J \in \mathcal{P}_a$ is called junk of the encoding $\llbracket \cdot \rrbracket_a^s$ modulo $\approx_a^s$, if J behaves modulo $\approx_a^s$ similar to $\mathbf{0}$ for all pieces of target terms, i.e.,

$$\forall \mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a . \mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s) \text{ implies } \mathcal{C}(J) \approx_a^s \mathcal{C}(\mathbf{0}).$$

A term $J \in \mathcal{P}_a$ is called junk of the encoding $\llbracket \cdot \rrbracket_a^m$ modulo $\approx_a^m$, if J behaves modulo $\approx_a^m$ similar to $\mathbf{0}$ for all pieces of target terms, i.e.,

$$\forall \mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a . \mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^m) \text{ implies } \mathcal{C}(J) \approx_a^m \mathcal{C}(\mathbf{0}).$$

Since we do not consider junk modulo equivalences different from $\approx_a^s$ and $\approx_a^m$, we omit the equivalence in the following. Moreover we omit the encoding function if the considered junk appears within both encodings.

Of course, whenever we reduce a piece of a target term by removing junk, the result is again a piece of a target term. Moreover, reducing junk does not change the behaviour of such a term modulo $\cong_a^s$ or $\cong_a^m$.

Lemma 22. Let T be a piece of a target term including some junk $J \in \mathcal{P}_a$. Then removing this junk results a piece of a target term which is congruent to T , i.e.,

$$\forall T \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s) . \forall T' \in \mathcal{P}_a . \forall \tilde{x} \subset \mathcal{N} . T \equiv (\nu \tilde{x}) (T' \mid J) \text{ implies } (\nu \tilde{x}) T' \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s) \wedge T \cong_a^s (\nu \tilde{x}) T'$$

and

$$\forall T \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^m) . \forall T' \in \mathcal{P}_a . \forall \tilde{x} \subset \mathcal{N} . T \equiv (\nu \tilde{x}) (T' \mid J) \text{ implies } (\nu \tilde{x}) T' \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^m) \wedge T \cong_a^m (\nu \tilde{x}) T'.$$

Proof. Let $J \in \mathcal{P}_a$ be junk. And let $T \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s)$, $T' \in \mathcal{P}_a$, and $\tilde{x} \subset \mathcal{N}$ such that $T \equiv (\nu \tilde{x}) (T' \mid J)$. We show the lemma for $\llbracket \cdot \rrbracket_a^s$. The argumentation for $\llbracket \cdot \rrbracket_a^m$ is then similar.

Since, by Lemma 17, $\cong_a^s$ includes structural congruence, $T \equiv (\nu \tilde{x}) (T' \mid J)$ implies $T \cong_a^s (\nu \tilde{x}) (T' \mid J)$. By Definition 28, then $\mathcal{C}(T) \approx_a^s \mathcal{C}((\nu \tilde{x}) (T' \mid J))$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s$. Let $\mathcal{C}'([\cdot]) = (\nu \tilde{x}) (T' \mid [\cdot])$. Then $\mathcal{C}'$ is a context, i.e., $\mathcal{C}'([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$, and, since $T \in \mathfrak{P}(\mathcal{P}_{a\downarrow} \llbracket \cdot \rrbracket_a^s)$ and $T = \mathcal{C}'(J)$,

we have $\mathcal{C}'(J) \in \mathfrak{P}(\mathcal{P}_{\text{al}}[\cdot]_{\mathbb{a}}^{\text{m}})$. Thus, $\mathcal{C}(T) \approx_{\text{a}}^{\text{s}} \mathcal{C}(\mathcal{C}'(J))$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_{\text{a}} \rightarrow \mathcal{P}_{\text{a}}$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_{\text{a}}^{\text{s}}) \in \mathcal{P}_{\text{al}}[\cdot]_{\text{a}}^{\text{s}}$. Moreover, $\mathcal{C}'(J) \in \mathfrak{P}(\mathcal{P}_{\text{al}}[\cdot]_{\mathbb{a}}^{\text{m}})$ implies $\mathcal{C}(\mathcal{C}'(J)) \in \mathfrak{P}(\mathcal{P}_{\text{al}}[\cdot]_{\mathbb{a}}^{\text{m}})$ for all such contexts $\mathcal{C}$. By Definition 30 of junk, then $\mathcal{C}(\mathcal{C}'(J)) \approx_{\text{a}}^{\text{s}} \mathcal{C}(\mathcal{C}'(\mathbf{0}))$ for all such contexts $\mathcal{C}$. Since $\mathcal{C}(\mathcal{C}'(\mathbf{0})) = \mathcal{C}((\nu \tilde{x})(T' \mid \mathbf{0})) \equiv \mathcal{C}((\nu \tilde{x})T')$ and since, by Lemma 16, $\approx_{\text{a}}^{\text{s}}$ includes structural congruence, we deduce $\mathcal{C}(\mathcal{C}'(J)) \approx_{\text{a}}^{\text{s}} \mathcal{C}((\nu \tilde{x})T')$ for all such contexts $\mathcal{C}$. Because $\approx_{\text{a}}^{\text{s}}$ is, by Lemma 14, an equivalence, $\mathcal{C}(T) \approx_{\text{a}}^{\text{s}} \mathcal{C}(\mathcal{C}'(J))$ for all such contexts $\mathcal{C}$ and $\mathcal{C}(\mathcal{C}'(J)) \approx_{\text{a}}^{\text{s}} \mathcal{C}((\nu \tilde{x})T')$ for all such contexts $\mathcal{C}$ implies $\mathcal{C}(T) \approx_{\text{a}}^{\text{s}} \mathcal{C}((\nu \tilde{x})T')$ for all such contexts $\mathcal{C}$. Thus, by Definition 28, we conclude $T \cong_{\text{a}}^{\text{s}} (\nu \tilde{x})T'$.

Finally, since $\cong_{\text{a}}^{\text{s}}$ includes structural congruence and is an equivalence, $T \cong_{\text{a}}^{\text{s}} (\nu \tilde{x})T'$ implies $(\nu \tilde{x})T' \cong_{\text{a}}^{\text{s}} (\nu \tilde{x})(T' \mid J)$. Thus, since $(\nu \tilde{x})(T' \mid J) \in \mathfrak{P}(\mathcal{P}_{\text{al}}[\cdot]_{\mathbb{a}}^{\text{s}})$, we conclude $(\nu \tilde{x})T' \in \mathfrak{P}(\mathcal{P}_{\text{al}}[\cdot]_{\mathbb{a}}^{\text{s}})$. $\square$

Using this lemma we can remove junk from a target term T . As result we obtain a piece of a target term T' such that $T \cong_{\text{a}}^{\text{s}} T'$ or $T \cong_{\text{a}}^{\text{m}} T'$, respectively. Then we can further reduce T' by removing junk such that we result in a piece of a target term T'' with $T' \cong_{\text{a}}^{\text{s}} T''$ or $T' \cong_{\text{a}}^{\text{m}} T''$ and so forth. Note that, we spend some effort in defining the notion of a piece of a target term to allow the stepwise remove of junk. This allows us to consider different kinds of junks separately. If we instead consider all possible junk of a target term at one go, then for the definition of junk it suffice to require that the context $\mathcal{C}$ is such that $\mathcal{C}(J)$ is a target term. However, it seems to be more efficient and more descriptive to consider the different kinds of junk separated.

In the simplest case junk is a closed process that can not perform any step, i.e., junk is invisible and inactive. Such kind of junk is produced e.g. as remain of a test-statement. By Definition 5, a test-statement and the corresponding instantiations of booleans are defined as:

$$\begin{aligned} \bar{l}\langle \top \rangle &\triangleq l(t, f) \cdot \bar{t} \\ \bar{l}\langle \perp \rangle &\triangleq l(t, f) \cdot \bar{f} \\ \text{test } l \text{ then } P \text{ else } Q &\triangleq (\nu t, f) (\bar{l}\langle t, f \rangle \mid t.P \mid f.Q) \quad \text{for some } t, f \notin \text{fn}(P) \cup \text{fn}(Q) \end{aligned}$$

Depending on whether we test a positive or a negative instantiation we result either in the then-case $(\nu t, f)(P \mid f.Q)$ or the else-case $(\nu t, f)(t.P \mid Q)$. Due to the renaming policy within target terms t and f are neither free in P nor in Q . So we can pull out the interesting cases P or Q and $(\nu t, f)f.Q$ or $(\nu t, f)t.P$ remain as inobservable and inactive junk.

Lemma 23. *For any $t, f \in \mathcal{N}$ and any $P, Q \in \mathcal{P}_{\text{a}}$ the terms $(\nu t, f)f.Q$ and $(\nu t, f)t.P$ are junk.*

Proof. Let $J_1 = (\nu t, f)f.Q$ and $J_2 = (\nu t, f)t.P$. J_1 as well as J_2 are closed terms, which can not perform any step. Moreover, they reach neither success nor any translated observable, i.e., $J_1 \not\Downarrow_{\checkmark}, J_2 \not\Downarrow_{\checkmark}, J_1 \not\Downarrow_{\mu}^{\text{s}}, J_2 \not\Downarrow_{\mu}^{\text{s}}, J_1 \not\Downarrow_{\mu}^{\text{m}},$ and $J_2 \not\Downarrow_{\mu}^{\text{m}}$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. Because of that, for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_{\text{a}} \rightarrow \mathcal{P}_{\text{a}}$ we have $\mathcal{C}(J_1) \approx_{\text{a}}^{\text{s}} \mathcal{C}(\mathbf{0}) \approx_{\text{a}}^{\text{s}} \mathcal{C}(J_2)$ and $\mathcal{C}(J_1) \approx_{\text{a}}^{\text{m}} \mathcal{C}(\mathbf{0}) \approx_{\text{a}}^{\text{m}} \mathcal{C}(J_2)$. Thus, by Definition 30, J_1 and J_2 are junk. $\square$

Note that, due to this lemma, we can securely omit the remains of test-statements in the following. An other kind of inobservable and inactive junk is produced by the translation of the empty sum $\mathbf{0}$. It results in a positive instantiation of a sum lock that is not used anywhere. However, let us generalise this case a little bit to an arbitrary instantiation of a sum lock (either positive or negative) that is not used anywhere.

Lemma 24. *For any name l the term $(\nu l)(\bar{l}\langle z \rangle)$, where $z \in \mathbb{B}$, is junk.*

Proof. Let $J = (\nu l)(\bar{l}\langle z \rangle)$. J is a closed term, which can not perform any step. Moreover, this term can reach neither success nor any translated observable, i.e., $J \not\Downarrow_{\checkmark}, J \not\Downarrow_{\mu}^{\text{s}},$ and $J \not\Downarrow_{\mu}^{\text{m}}$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. So for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_{\text{a}} \rightarrow \mathcal{P}_{\text{a}}$ we have $\mathcal{C}(J) \approx_{\text{a}}^{\text{s}} \mathcal{C}(\mathbf{0})$ and $\mathcal{C}(J) \approx_{\text{a}}^{\text{m}} \mathcal{C}(\mathbf{0})$. Thus, by Definition 30, J is junk. $\square$

Note that this lemma especially shows that the translation of the empty sum is junk, i.e., we translate nothing into nothing but junk. Moreover we will use it to reduce the remains left over by emulations. In the following lemma we prove, that requests on negative instantiations of sum locks are junk of the encoding from π_{m} into π_{a} . Note that in this case we consider potentially observable and active junk.

Lemma 25. *Requests on negative instantiations of sum locks are junk of $\llbracket \cdot \rrbracket_a^m$, i.e.,*

$$\begin{aligned} \forall \mathcal{C}_1([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a . \forall p_i, y, l, r \in \mathcal{N} . \\ \mathcal{C}_1(\overline{p_i} \langle y, l, r \rangle) \in \mathfrak{P}(\mathcal{P}_a \llbracket \cdot \rrbracket_a^m) \wedge (\exists T \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \mathcal{C}_1(\mathbf{0}) \equiv (\nu \tilde{x})(T \mid \overline{l} \langle \perp \rangle)) \\ \text{implies } \mathcal{C}_1(\overline{p_i} \langle y, l, r \rangle) \approx_a^m \mathcal{C}_1(\mathbf{0}) \end{aligned}$$

and

$$\begin{aligned} \forall \mathcal{C}_2([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a . \forall p_o, y, l, s, z \in \mathcal{N} . \\ \mathcal{C}_2(\overline{p_o} \langle y, l, s, z \rangle) \in \mathfrak{P}(\mathcal{P}_a \llbracket \cdot \rrbracket_a^m) \wedge (\exists T \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \mathcal{C}_2(\mathbf{0}) \equiv (\nu \tilde{x})(T \mid \overline{l} \langle \perp \rangle)) \\ \text{implies } \mathcal{C}_2(\overline{p_o} \langle y, l, s, z \rangle) \approx_a^m \mathcal{C}_2(\mathbf{0}) . \end{aligned}$$

Proof. Let $J_1 = \overline{p_i} \langle y, l, r \rangle$ and $J_2 = \overline{p_o} \langle y, l, s, z \rangle$.

Since we require $\mathcal{C}_1(J_1), \mathcal{C}_2(J_2) \in \mathfrak{P}(\mathcal{P}_a \llbracket \cdot \rrbracket_a^m)$, we consider only contexts that respect the protocol implemented by the encoding function $\llbracket \cdot \rrbracket_a^m$. By analysing the encoding function in Figure 4, we observe that there are many forwarders for requests, i.e., many replicated inputs that consume requests and immediately restore a request on a different channel but with exactly the same values. Note that by such forwarders requests are multiplied. Most of these copies turn out to be junk. However, note that the encoding function restricts the request channels—except for the outermost—and provides for each such channel exactly one (replicate) input and no inputs or replicated inputs for unrestricted request channels. Because of that, the way a request may travel is completely determined, i.e., given a target term there is no choice about which way a request may take.

Moreover, if the context puts the requests at the outermost position, then they can not be consumed at all, i.e., in this case the requests are observable but inactive junk. By Lemma 4, the negative instantiation of the sum lock l is the only instantiation of that lock and, by Lemma 5, it can not be changed by the context into a positive instantiation. So, by Definition 25, the requests are not considered as translated observables, i.e., $J_1 \not\Downarrow_\mu^m$ and $J_2 \not\Downarrow_\mu^m$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. Obviously, J_1 and J_2 also have no possibility to reach $\checkmark$, i.e., $J_1 \not\Downarrow_\checkmark$ and $J_2 \not\Downarrow_\checkmark$. Thus for all contexts $\mathcal{C}_1([\cdot]), \mathcal{C}_2([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}_1(J_1), \mathcal{C}_2(J_2) \in \mathfrak{P}(\mathcal{P}_a \llbracket \cdot \rrbracket_a^m)$, $p_i \in \text{fn}(\mathcal{C}_1(J_1))$, and $p_o \in \text{fn}(\mathcal{C}_2(J_2))$, we have $\mathcal{C}_1(J_1) \approx_a^m \mathcal{C}_1(\mathbf{0})$ and $\mathcal{C}_2(J_2) \approx_a^m \mathcal{C}_2(\mathbf{0})$.

Note that we consider only contexts $\mathcal{C}_1$ and $\mathcal{C}_2$, such that $\mathcal{C}_1(J_1)$ and $\mathcal{C}_2(J_2)$ are pieces of target terms. So all requests—including J_1 and J_2 —origin from the translation of input or output guarded terms or replicated inputs. All inputs on request channels, i.e., channels that can transport either three or four values, origin from the translation of the parallel operator or a replicated input. We observe that, for each request, the encoding of a parallel operator receives from one of its encoded parameters, one copy of that request is pushed upwards. Similarly, for each request of each branch of an encoded replicated input one copy is pushed to the right. Because of that, requests never vanish. As soon as a request in a target term is unguarded for the first time, there will always be a copy of that request possibly on another channel but with the same values (compare to Lemma 3).

Note that all inputs on request channels are replicated inputs except for the first inputs in the processing of right in- or output requests in the encoding of a parallel operator or a replicated input (compare to `procRightOutReq` and `procRightInReq`). However, even in these two cases the consumption of a request enables—after one internal step on a chain lock—the processing of another request in exactly the same way modulo some forwarding processes. So the order in which requests are consumed does not matter (compare to Lemma 11). Moreover note, that the step on the chain lock is completely determined again, i.e., there is no choice about eventually doing it or how to do it. Because of that, the fact, that a request was already pushed further or not, does neither influence the reachability of success nor the reachability of translated observables.

Except from transferring them the encoding function can proceed requests only by combining them. $\llbracket \cdot \rrbracket_a^m$ ensures, that each pair of requests is combined at most once and that each pair of an input and an output requests, which do not both origin from the same leaf concerning the structure of parallel operator encodings, is eventually combined. Because of that, again the order in which those combinations are performed does not matter. However, the order in which tests on sum locks are induced does indeed matter, because a test induced on only positive instantiations of sum locks turns them into negative instantiations and so a former such test may influences later tests. Since the test is always induced on the sum locks related to the respective request, all test that are induced because of the requests J_1 or J_2 are on at least one negative instantiation of a sum lock, i.e., on l in the current case. Note that, by Lemma 4, the negative instantiation of the sum lock l is the only instantiation of that lock and, by Lemma 5, it can not be changed by the context into a positive instantiation. If we now analyse the test-statements in the encodings of an input guarded term or a replicated input, we observe that this false instantiation of l reduces the test-statements to some kind of forwarders that consumes one or two instantiations of sum locks and since

there are no deadlocks on these test-statements eventually restores them on exactly the same channel and with exactly the same value. So again the processing of J_1 or J_2 do neither influence the reachability of success nor the reachability of translated observables.

So for all contexts $\mathcal{C}_1([\cdot]), \mathcal{C}_2([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$, such that $\mathcal{C}_1(J_1), \mathcal{C}_2(J_2) \in \mathfrak{P}(\mathcal{P}_a \uparrow \llbracket \cdot \rrbracket_a^m)$, we have

$$\begin{aligned} (\mathcal{C}_1(J_1) \Downarrow_{\checkmark} \text{ iff } \mathcal{C}_1(\mathbf{0}) \Downarrow_{\checkmark}) \wedge (\mathcal{C}_2(J_2) \Downarrow_{\checkmark} \text{ iff } \mathcal{C}_2(\mathbf{0}) \Downarrow_{\checkmark}) \text{ and} \\ (\mathcal{C}_1(J_1) \Downarrow_{\mu}^m \text{ iff } \mathcal{C}_1(\mathbf{0}) \Downarrow_{\mu}^m) \wedge (\mathcal{C}_2(J_2) \Downarrow_{\mu}^m \text{ iff } \mathcal{C}_2(\mathbf{0}) \Downarrow_{\mu}^m) \end{aligned}$$

for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. Since all steps that results from an interaction with J_1 and J_2 are administrative steps, that neither rule out a way leading to an unguarded occurrence of $\checkmark$ nor to a translated observable, they do not influence the state of a term modulo $\approx_a^m$. Thus, we conclude $\mathcal{C}_1(J_1) \approx_a^m \mathcal{C}_1(\mathbf{0})$ and $\mathcal{C}_2(J_2) \approx_a^m \mathcal{C}_2(\mathbf{0})$. $\square$

Next we show, that—for both encodings—encoded guarded terms linked to negative instantiations of sum locks are junk, as well. Note that such encoded guarded terms linked to negative instantiations of sum locks result from encoded sums of which already one summand was used to emulate a source term step.

Lemma 26. *For any name l , any finite index set I , all guards π_i , and all processes $P_i \in \mathcal{P}_s$ the term*

$$(\nu l) \left(\prod_{i \in I} \llbracket \pi_i.P_i \rrbracket_a^s \mid \bar{l} \langle \perp \rangle \right)$$

is junk of $\llbracket \cdot \rrbracket_a^s$.

Proof. Let $J = (\nu l) \left(\prod_{i \in I} \llbracket \pi_i.P_i \rrbracket_a^s \mid \bar{l} \langle \perp \rangle \right)$. By Definition 30, we have to show that for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_a \uparrow \llbracket \cdot \rrbracket_a^s)$ we have $\mathcal{C}(J) \approx_a^s \mathcal{C}(\mathbf{0})$.

By Lemma 4, the negative instantiation of the sum lock l is the only instantiation of that lock and, by Lemma 5, it can not be changed by the context into a positive instantiation. Analysing the encoding function in Figure 3 we observe, that all unguarded in- or outputs with three parameters in J are connected to $\bar{l} \langle \perp \rangle$. Thus J has no translated observables, i.e., $J \not\Downarrow_{\mu}^s$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. Moreover, because of the guards π_i , J has no unguarded occurrence of $\checkmark$ and can not reach some on its own, i.e., $J \not\Downarrow_{\checkmark}$.

J can perform a step on its own only if for some $j \in I$ the guard π_j is equal to τ or is an input guard. Note that in the second case J can only perform finitely many steps on receiver locks. Since l is instantiated by $\perp$, $\llbracket \tau.P_j \rrbracket_a^m$ can reduce to $\mathbf{0}$ only. Therefore, $\llbracket \tau.P_j \rrbracket_a^m$ has to consume $\bar{l} \langle \perp \rangle$ but the instantiation is always eventually restored. Because of that, we can ignore all $\llbracket \pi_i.P_i \rrbracket_a^m$ for $\pi_i = \tau$, i.e., they are junk. Let $J' = (\nu l) \left(\prod_{i \in I, \pi_i \neq \tau} \llbracket \pi_i.P_i \rrbracket_a^m \mid \bar{l} \langle \perp \rangle \right)$. Moreover, obtain J'' from J' by reducing all free inputs on receiver locks.

Then J'' can not perform any step, since either all remaining guards are output guards and so all unguarded inputs in the encoded subterms are on not instantiated sender locks, or all remaining guards are input guards and so the encoded subterms are input guarded, i.e., $J'' \not\rightarrow$. In case the index set $\{i \mid i \in I \wedge \pi_i \neq \tau\}$ is empty, we can apply Lemma 24. Else, there are either free outputs or free inputs on translated source term names. So J'' can communicate with the context over these translated source term names. As a result of such a communication a test-statement is unguarded. In case this test-statement is within J'' , the sum lock l is tested first. Since l is instantiated by $\perp$, the test-statement restores both, the consumed negative instantiation of l and the output on the translated source term name, which was consumed to unguard this test-statement. Else, if the unguarded test-statement is not within J'' , then—besides the negative instantiation of the sum lock— J'' includes only encodings of output guarded source terms. In this case all these encodings of output guarded source terms provide exactly one output on a translated source term name, which sends as first value the sum lock l . In the communication with the context one of these outputs was consumed and, because of that, the unguarded test-statement is either a nested test-statement testing l as second lock or it is a single test-statement testing only l . In both cases all information necessary to unguard and to reduce the test-statement except for the output on the source term name is restored. Because of that, each such output can be used as most once. In both cases no step that results from an interaction with J'' influences the reachability of success or of translated observables. Moreover each such step is either a pure administrative step, which by Lemma 18 do not influence the state of a term modulo $\approx_a^s$, or it is an impure administrative step. Since reachability of $\checkmark$ is not influenced at all and all translated observables of the context which are consumed to unguard the test-statement are eventually restored, i.e., reachability of translated observables is not affected, even these impure administrative steps do not influence the state of the context modulo $\approx_a^s$ here.

Thus for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$, such that $\mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_a \uparrow \llbracket \cdot \rrbracket_a^s)$, we have $(\mathcal{C}(J) \Downarrow_\checkmark \text{ iff } \mathcal{C}(\mathbf{0}) \Downarrow_\checkmark)$ and $(\mathcal{C}(J) \Downarrow_\mu^s \text{ iff } \mathcal{C}(\mathbf{0}) \Downarrow_\mu^s)$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. Moreover no step of J on its own or that results from an interaction with J does influence the state of the context modulo $\approx_a^s$. So, $\mathcal{C}(J) \approx_a^s \mathcal{C}(\mathbf{0})$. $\square$

Lemma 27. *For any name l , any finite index set I , all guards π_i , and all processes $P_i \in \mathcal{P}_m$ the term*

$$(\nu l) \left(\prod_{i \in I} \llbracket \pi_i.P_i \rrbracket_a^m \mid \bar{l} \langle \perp \rangle \right)$$

is junk of $\llbracket \cdot \rrbracket_a^m$.

Proof. Let $J = (\nu l) \left(\prod_{i \in I} \llbracket \pi_i.P_i \rrbracket_a^m \mid \bar{l} \langle \perp \rangle \right)$. By Definition 30, we have to show that for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_a \uparrow \llbracket \cdot \rrbracket_a^m)$ we have $\mathcal{C}(J) \approx_a^m \mathcal{C}(\mathbf{0})$.

By Lemma 4, the negative instantiation of the sum lock l is the only instantiation of that lock and, by Lemma 5, it can not be changed by the context into a positive instantiation. Analysing the encoding function in Figure 4 we observe, that all unguarded requests in J are connected to $\bar{l} \langle \perp \rangle$ (compare to Definition 19 and Lemma 6). Thus J has no translated observables, i.e., $J \not\Downarrow_\mu^s$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. Moreover, because of the guards π_i , J has no unguarded occurrence of $\checkmark$ and can not reach some on its own, i.e., $J \not\Downarrow_\checkmark$.

J can perform a step on its own only if for some $j \in I$ the guard π_j is equal to τ . Since l is instantiated by $\perp$, $\llbracket \tau.P_j \rrbracket_a^m$ can reduce to $\mathbf{0}$ only. Therefore, $\llbracket \tau.P_j \rrbracket_a^m$ has to consume $\bar{l} \langle \perp \rangle$ but the instantiation is always eventually restored. Because of that, we can ignore all $\llbracket \pi_i.P_i \rrbracket_a^m$ for $\pi_i = \tau$, i.e., they are junk. Let $J' = (\nu l) \left(\prod_{i \in I, \pi_i \neq \tau} \llbracket \pi_i.P_i \rrbracket_a^m \mid \bar{l} \langle \perp \rangle \right)$.

Then J' can not perform any step, i.e., $J' \not\rightarrow$. There are no unguarded inputs on free names of J' . In case the index set $\{i \mid i \in I \wedge \pi_i \neq \tau\}$ is empty, we can apply Lemma 24. Else, there are free requests, i.e., free outputs on requests channels. So J' can communicate with the context by transmitting its requests. By Lemma 25 these requests are junk. Moreover by revisiting the argumentation in the proof of Lemma 25 we observe, that the false instantiation of l reduces all tests on that lock to simple forwarders. As a consequence no such test can unguard the encoding of a guarded source term, i.e., no such test can unguard new requests or former unguarded occurrences of success. So again we observe that no interaction with J or J' can influence the ability of the context to reach success or translated observables and no step that results from an interaction with J or J' influences the state of the context modulo $\approx_a^m$.

Thus for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$, such that $\mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_a \uparrow \llbracket \cdot \rrbracket_a^m)$, we have $(\mathcal{C}(J) \Downarrow_\checkmark \text{ iff } \mathcal{C}(\mathbf{0}) \Downarrow_\checkmark)$ and $(\mathcal{C}(J) \Downarrow_\mu^m \text{ iff } \mathcal{C}(\mathbf{0}) \Downarrow_\mu^m)$ for all $\mu \in \mathcal{N} \cup \overline{\mathcal{N}}$. Moreover no step of J on its own or that results from an interaction with J does influence the state of the context modulo $\approx_a^m$. So, $\mathcal{C}(J) \approx_a^m \mathcal{C}(\mathbf{0})$. $\square$

Analysing the encoding function we observe, that the input on a receiver lock of an encoded input guarded source term, that guards a test-statement, is a replicated input. Of course, such a test-statement can only be used once to emulate a source term step. After such an emulation this replicated input becomes junk.

Lemma 28. *For any $l_1, l_2, r, s, \varphi_a^m(x) \in \mathcal{N}$ and any $P \in \mathcal{P}_m$ the term*

$$J = r^*(l_1, l_2, -, s, \varphi_a^m(x)).\text{test } l_1 \text{ then test } l_2 \text{ then } \bar{l}_1 \langle \perp \rangle \mid \bar{l}_2 \langle \perp \rangle \mid \bar{s} \mid \llbracket P \rrbracket_a^m \text{ else } \bar{l}_1 \langle \top \rangle \mid \bar{l}_2 \langle \perp \rangle \text{ else } \bar{l}_1 \langle \perp \rangle$$

in combination with a negative instantiation of the sum lock that belongs to r is junk of $\llbracket \cdot \rrbracket_a^m$, i.e.,

$$\forall \mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a. \forall l_1, l_2, r, s, \varphi_a^m(x) \in \mathcal{N}. \forall P \in \mathcal{P}_m. \forall J \in \mathcal{P}_a.$$

$$\begin{aligned} J &= r^*(l_1, l_2, -, s, \varphi_a^m(x)).\text{test } l_1 \text{ then test } l_2 \text{ then } \bar{l}_1 \langle \perp \rangle \mid \bar{l}_2 \langle \perp \rangle \mid \bar{s} \mid \llbracket P \rrbracket_a^m \text{ else } \bar{l}_1 \langle \top \rangle \mid \bar{l}_2 \langle \perp \rangle \text{ else } \bar{l}_1 \langle \perp \rangle \\ &\wedge \mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_a \uparrow \llbracket \cdot \rrbracket_a^m) \wedge (\exists T \in \mathcal{P}_a. \exists \tilde{x} \subset \mathcal{N}. \exists p_i, y, l \in \mathcal{N}. \mathcal{C}(\mathbf{0}) \equiv (\nu \tilde{x}) (T \mid \bar{p}_i \langle y, l, r \rangle \mid \bar{l} \langle \perp \rangle)) \\ &\text{implies } \mathcal{C}(J) \approx_a^m \mathcal{C}(\mathbf{0}) \end{aligned}$$

Proof. Analysing the encoding function in Figure 4 we observe that the request $\bar{p}_i \langle y, l, r \rangle$ implies that each test induced on r tests the sum lock l (compare to Lemma 6). Since that lock is already instantiated by false, we can revisit the argumentation of the proof of Lemma 27 to conclude that each test induced on r reduces to a simple forwarder, which restores all consumed information. So J can be ignored, i.e., J is Junk. $\square$

Another remain of an emulation, which we can simply consider as junk, is the preparation of a test on a negative instantiated sum lock.

Lemma 29. *The preparation of a test on a negative instantiation of a sum lock is junk of $\llbracket \cdot \rrbracket_a^m$, i.e.,*

$$\begin{aligned} & \forall \mathcal{C} ([\cdot]) \in \pi_a \rightarrow \pi_a . \forall m_i, m_{i,up}, y, y', l, l_r, r, s, z \in \mathcal{N} . \forall J \in \mathcal{P}_a . \\ & J = m_i^* (y', l_r, r) . ([y' = y] \bar{\tau} \langle l_r, l, l, s, z \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle) \wedge \mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_{al} \llbracket \cdot \rrbracket_a^m) \\ & \wedge (\exists T \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \mathcal{C}(\mathbf{0}) \equiv (\nu \tilde{x}) (T \mid \bar{l} \langle \perp \rangle)) \\ & \text{implies } \mathcal{C}(J) \approx_a^m \mathcal{C}(m_i \twoheadrightarrow m_{i,up}) \end{aligned}$$

and

$$\begin{aligned} & \forall \mathcal{C} ([\cdot]) \in \pi_a \rightarrow \pi_a . \forall m_o, m_{o,up}, y, y', l, l_s, r, s, z \in \mathcal{N} . \forall J \in \mathcal{P}_a . \\ & J = m_o^* (y', l_s, s, z) . ([y' = y] \bar{\tau} \langle l_s, l, l_s, s, z \rangle \mid \overline{m_{o,up}} \langle y', l_s, s, z \rangle) \wedge \mathcal{C}(J) \in \mathfrak{P}(\mathcal{P}_{al} \llbracket \cdot \rrbracket_a^m) \\ & \wedge (\exists T \in \mathcal{P}_a . \exists \tilde{x} \subset \mathcal{N} . \mathcal{C}(\mathbf{0}) \equiv (\nu \tilde{x}) (T \mid \bar{l} \langle \perp \rangle)) \\ & \text{implies } \mathcal{C}(J) \approx_a^m \mathcal{C}(m_o \twoheadrightarrow m_{o,up}) \end{aligned}$$

Proof. First note that here not J but only $[y' = y] \bar{\tau} \langle l_r, l, l, s, z \rangle$ and $[y' = y] \bar{\tau} \langle l_s, l, l_s, s, z \rangle$ are considered as junk. If these terms are omitted then the respective J reduces to the forwarder $m_i \twoheadrightarrow m_{i,up}$ or $m_o \twoheadrightarrow m_{o,up}$.

In the first case—regardless whether the receiver lock r belongs to an encoded input guarded term or an encoded replicated input—the output $\bar{\tau} \langle l_s, l, l_s, s, z \rangle$ induces a test on the sum lock l . Since that lock is already instantiated by false we can revisit the argumentation of the proof of Lemma 27 to conclude that we can ignore this induced test. So we can also ignore the inducing output $\bar{\tau} \langle l_s, l, l_s, s, z \rangle$. The remaining term $m_i^* (y', l_r, r) . \overline{m_{i,up}} \langle y', l_r, r \rangle$ is equal to the forwarder $m_i \twoheadrightarrow m_{i,up}$.

For the second case, since there is a negative instantiation of l , the receiver lock r was not created by the encoding of a replicated input. So again the output $\bar{\tau} \langle l_s, l, l_s, s, z \rangle$ induces a test on the sum lock l . The rest of that case is similar to the case before. $\square$

Unfortunately, we can not declare any remains of emulations as junk, because we can not ignore the forwarding of left requests in the chains of right requests which is left over by former considered right requests. However, after extracting the junk, by Lemma 29, there is indeed nothing more left, than a simple forwarder, which can not influence the state of the process modulo $\approx_a^m$. That suffice to prove operational completeness.

2.6 Semantical Criteria

Among the semantical criteria operational correspondence is the most elaborate to prove. Therefore we show the both its conditions, operational completeness and operational soundness, separately. In order to show operational completeness, we have to show how source terms steps are emulated by the encodings.

Lemma 30 (Operational Completeness). *The encoding $\llbracket \cdot \rrbracket_a^s$ fulfils operational completeness.*

Proof. By Definition 9 it suffice to show that:

$$\forall S, S' \in \mathcal{P}_s . S \mapsto S' \text{ implies } \exists T \in \mathcal{P}_a . \llbracket S \rrbracket_a^s \Longrightarrow T \wedge T \cong_a^s \llbracket S' \rrbracket_a^s$$

The lemma then holds by induction over the number of steps in $S \Longrightarrow S'$. To prove the condition above, we perform an induction over the proof tree that leads to the step $S \mapsto S'$.

Base Case: By the rules in Figure 2 each step on S is based either on Rule $\text{TAU}_{m,s}$, $\text{COM}_{m,s}$, or $\text{REP}_{m,s}$.

Case of Rule $\text{TAU}_{m,s}$: In this case S is a single sum, of which one summand is guarded by τ , and S' is the continuation of this τ guarded summand, i.e., there are some finite index set I , some guards π_i , and some processes $P_i \in \mathcal{P}_s$ such that $S = \sum_{i \in I} \pi_i . P_i$ with $\pi_j = \tau$ for some $j \in I$ and $S' = P_j$. The corresponding encodings are given by the following terms:

$$\begin{aligned} \llbracket S \rrbracket_a^s & \equiv (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I, i \neq j} \llbracket \pi_i . P_i \rrbracket_a^s \mid \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \llbracket P_j \rrbracket_a^s \text{ else } \bar{l} \langle \perp \rangle \right) \\ \llbracket S' \rrbracket_a^s & = \llbracket P_j \rrbracket_a^s \end{aligned}$$

We observe that $\llbracket S \rrbracket_a^s$ can emulate the step $S \mapsto S'$ by reducing the test-statement in the encoding of the j 's summand, i.e., by

$$\llbracket S \rrbracket_a^s \mapsto^2 (\nu l) \left(\prod_{i \in I, i \neq j} \llbracket \pi_i.P_i \rrbracket_a^s \mid \bar{l} \langle \perp \rangle \mid \llbracket P_j \rrbracket_a^s \right) = T.$$

Note that, since the test-statement and the implementation of booleans are no native π -terms but abbreviations for π -constructs, this reduction indeed requires two steps. Moreover note, that we silently omit junk that results from the reduction of test-statements (compare to Lemma 23) here and in the following proofs. Further, we observe that $T \equiv (\nu l) \left(\prod_{i \in I, i \neq j} \llbracket \pi_i.P_i \rrbracket_a^s \mid \bar{l} \langle \perp \rangle \right) \mid \llbracket P_j \rrbracket_a^s$, since, due to the renaming policy φ_a^s , the name l is not free in $\llbracket P_j \rrbracket_a^s$. So the emulation leaves over the term $(\nu l) \left(\prod_{i \in I, i \neq j} \llbracket \pi_i.P_i \rrbracket_a^s \mid \bar{l} \langle \perp \rangle \right)$, which is by Lemma 26 junk. By Lemma 22, we conclude that $T \cong_a^s \llbracket S' \rrbracket_a^s$.

Case of Rule COM_{m,s}: Here S is a parallel composition of two sums and S' is the parallel composition of the continuations of an input guarded summand of the first and a matching output guarded summand of the second sum, i.e., there are two finite index sets I_1, I_2 , some guards π_i , and some processes $P_i, Q_i \in \mathcal{P}_s$ such that $S = \sum_{i \in I_1} \pi_i.P_i \mid \sum_{i \in I_2} \pi_i.Q_i$ with $\pi_{j_1} = y(x)$ and $\pi_{j_2} = \bar{y} \langle z \rangle$ for some $j_1 \in I_1$, some $j_2 \in I_2$, and $x, y, z \in \mathcal{N}$ and $S' = \{z/x\} P_{j_1} \mid Q_{j_2}$. The encodings of S and S' are given by the following terms:

$$\begin{aligned} \llbracket S \rrbracket_a^s &\equiv (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^s \right. \\ &\quad \mid (\nu r) \left(\bar{r} \mid r^*. \varphi_a^s(y) (l', s, \varphi_a^s(x)) . \text{test } l \text{ then test } l' \text{ then } \bar{l} \langle \perp \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \mid \llbracket P_{j_1} \rrbracket_a^s \right. \\ &\quad \quad \quad \left. \text{else } \bar{l} \langle \top \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{r} \right. \\ &\quad \quad \quad \left. \text{else } \bar{l} \langle \top \rangle \mid \overline{\varphi_a^s(y)} \langle l', s, \varphi_a^s(x) \rangle \right) \\ &\quad \mid (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.Q_i \rrbracket_a^s \mid (\nu s) \left(\overline{\varphi_a^s(y)} \langle l, s, \varphi_a^s(z) \rangle \mid s. \llbracket Q_{j_2} \rrbracket_a^s \right) \right) \\ \llbracket S' \rrbracket_a^s &= \llbracket \{z/x\} (P_{j_1}) \rrbracket_a^s \mid \llbracket Q_{j_2} \rrbracket_a^s \end{aligned}$$

To emulate the source term step $S \mapsto S'$ first the receiver lock has to be reduced to enable a communication over $\varphi_a^s(y)$. Then the test-statement and the sender lock are reduced to complete the emulation of the source term step.

$$\begin{aligned} \llbracket S \rrbracket_a^s &\mapsto^2 (\nu l_1, l_2, s) \left(\bar{l}_1 \langle \top \rangle \mid \{l_1/l\} \left(\prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^s \right) \right. \\ &\quad \mid (\nu r) \left(\text{test } l_1 \text{ then test } l_2 \text{ then } \bar{l}_1 \langle \perp \rangle \mid \bar{l}_2 \langle \perp \rangle \mid \bar{s} \mid \left\{ \varphi_a^s(z) / \varphi_a^s(x) \right\} (\llbracket P_{j_1} \rrbracket_a^s) \right. \\ &\quad \quad \quad \text{else } \bar{l}_1 \langle \top \rangle \mid \bar{l}_2 \langle \perp \rangle \mid \bar{r} \\ &\quad \quad \quad \text{else } \bar{l}_1 \langle \perp \rangle \mid \overline{\varphi_a^s(y)} \langle l_2, s, \varphi_a^s(z) \rangle \\ &\quad \quad \quad \left. r^*. \varphi_a^s(y) (l', s, \varphi_a^s(x)) . \text{test } l_1 \text{ then test } l' \text{ then } \bar{l}_1 \langle \perp \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{s} \mid \llbracket P_{j_1} \rrbracket_a^s \right. \\ &\quad \quad \quad \left. \text{else } \bar{l}_1 \langle \top \rangle \mid \bar{l}' \langle \perp \rangle \mid \bar{r} \right. \\ &\quad \quad \quad \left. \text{else } \bar{l}_1 \langle \perp \rangle \mid \overline{\varphi_a^s(y)} \langle l', s, \varphi_a^s(x) \rangle \right) \\ &\quad \mid \bar{l}_2 \langle \top \rangle \mid \{l_2/l\} \left(\prod_{i \in I_1, i \neq j_2} \llbracket \pi_i.Q_i \rrbracket_a^s \right) \mid s. \llbracket Q_{j_2} \rrbracket_a^s \end{aligned}$$

$$\begin{aligned}
& \mapsto^5 (\nu l_1, l_2, s) \left(\{l_1/l\} \left(\prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^s \right) \right. \\
& \quad | (\nu r) \left(\overline{l_1} \langle \perp \rangle | \overline{l_2} \langle \perp \rangle | \left\{ \varphi_a^s(z)/\varphi_a^s(x) \right\} \left(\llbracket P_{j_1} \rrbracket_a^s \right) \right. \\
& \quad \quad r^*.\varphi_a^s(y)(l', s, \varphi_a^s(x)).\text{test } l_1 \text{ then test } l' \text{ then } \overline{l_1} \langle \perp \rangle | \overline{l'} \langle \perp \rangle | \overline{s} | \llbracket P_{j_1} \rrbracket_a^s \\
& \quad \quad \quad \text{else } \overline{l_1} \langle \top \rangle | \overline{l'} \langle \perp \rangle | \overline{r} \\
& \quad \quad \quad \text{else } \overline{l_1} \langle \perp \rangle | \overline{\varphi_a^s(y)} \langle l', s, \varphi_a^s(x) \rangle \left. \right) \\
& \quad \left. | \{l_2/l\} \left(\prod_{i \in I_1, i \neq j_2} \llbracket \pi_i.Q_i \rrbracket_a^s \right) | \llbracket Q_{j_2} \rrbracket_a^s \right) = T
\end{aligned}$$

By Corollary 1, $\{\varphi_a^s(z)/\varphi_a^s(x)\} \llbracket P_{j_1} \rrbracket_a^s \equiv_\alpha \llbracket \{z/x\} P_{j_1} \rrbracket_a^s$. To show that $T \cong_a^s \llbracket S' \rrbracket_a^m$ we stepwise reduce T by ignoring junk. Since $l_1, l_2, r, s \notin \text{fn}(\llbracket \{z/x\} P_{j_1} \rrbracket_a^m) \cup \text{fn}(\llbracket Q_{j_2} \rrbracket_a^m)$, we can reorder the term according to the restrictions on l_1, l_2, r and the restriction on s can be omitted. The term

$$\begin{aligned}
& (\nu r) \left(r^*.\varphi_a^s(y)(l', s, \varphi_a^s(x)).\text{test } l_1 \text{ then test } l' \text{ then } \overline{l_1} \langle \perp \rangle | \overline{l'} \langle \perp \rangle | \overline{s} | \llbracket P_{j_1} \rrbracket_a^s \right. \\
& \quad \quad \text{else } \overline{l_1} \langle \top \rangle | \overline{l'} \langle \perp \rangle | \overline{r} \\
& \quad \quad \text{else } \overline{l_1} \langle \perp \rangle | \overline{\varphi_a^s(y)} \langle l', s, \varphi_a^s(x) \rangle \left. \right)
\end{aligned}$$

is obviously junk, since it is closed and can not perform any step. Moreover, by Lemma 26, the terms $(\nu l) \left(\prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^s | \overline{l} \langle \perp \rangle \right)$ and $(\nu l) \left(\prod_{i \in I_1, i \neq j_2} \llbracket \pi_i.Q_i \rrbracket_a^s | \overline{l} \langle \perp \rangle \right)$ are junk. So, by Lemma 22, we conclude $T \cong_a^s \llbracket S' \rrbracket_a^s$.

Case of Rule $\text{REP}_{m,s}$: Here S is a parallel composition of a replicated input and a sum and S' is the parallel composition of the replicated input, the continuation of the replicated input, and the continuation of a matching output guarded summand, i.e., there is a finite index sets I , some guards π_i , and some processes $P, Q_i \in \mathcal{P}_s$ such that $S = y^*(x).P | \sum_{i \in I} \pi_i.Q_i$ with $\pi_j = \overline{y} \langle z \rangle$ for some $j \in I$ and $x, y, z \in \mathcal{N}$, and $S' = \{z/x\}P | Q_j | y^*(x).P$. The encodings of S and S' are given by the following terms:

$$\begin{aligned}
& \llbracket S \rrbracket_a^s \equiv \varphi_a^s(y)^*(l, s, \varphi_a^s(x)).\text{test } l \text{ then } \overline{l} \langle \perp \rangle | \overline{s} | \llbracket P \rrbracket_a^s \text{ else } \overline{l} \langle \perp \rangle \\
& \quad | (\nu l) \left(\overline{l} \langle \top \rangle | \prod_{i \in I_1, i \neq j} \llbracket \pi_i.Q_i \rrbracket_a^s | (\nu s) \left(\overline{\varphi_a^s(y)} \langle l, s, \varphi_a^s(z) \rangle | s.\llbracket Q_j \rrbracket_a^s \right) \right) \\
& \llbracket S' \rrbracket_a^s = \llbracket \{z/x\}(P) \rrbracket_a^s | \llbracket Q_j \rrbracket_a^s | \llbracket y^*(x).P \rrbracket_a^s
\end{aligned}$$

To emulate the source term step $S \mapsto S'$, first the two subprocesses of $\llbracket S \rrbracket_a^s$ communicate over $\varphi_a^s(y)$. Then the test-statement and the sender lock are reduced to complete the emulation of the source term step.

$$\begin{aligned}
& \llbracket S \rrbracket_a^s \mapsto (\nu l, s) \left(\text{test } l \text{ then } \overline{l} \langle \perp \rangle | \overline{s} | \left\{ \varphi_a^s(z)/\varphi_a^s(x) \right\} (\llbracket P \rrbracket_a^s) \text{ else } \overline{l} \langle \perp \rangle \right. \\
& \quad | \varphi_a^s(y)^*(l, s, \varphi_a^s(x)).\text{test } l \text{ then } \overline{l} \langle \perp \rangle | \overline{s} | \llbracket P \rrbracket_a^s \text{ else } \overline{l} \langle \perp \rangle \\
& \quad | \overline{l} \langle \top \rangle | \prod_{i \in I_1, i \neq j} \llbracket \pi_i.Q_i \rrbracket_a^s | s.\llbracket Q_j \rrbracket_a^s \left. \right) \\
& \mapsto^3 (\nu l, s) \left(\overline{l} \langle \perp \rangle | \left\{ \varphi_a^s(z)/\varphi_a^s(x) \right\} (\llbracket P \rrbracket_a^s) \right. \\
& \quad | \varphi_a^s(y)^*(l, s, \varphi_a^s(x)).\text{test } l \text{ then } \overline{l} \langle \perp \rangle | \overline{s} | \llbracket P \rrbracket_a^s \text{ else } \overline{l} \langle \perp \rangle \\
& \quad | \prod_{i \in I_1, i \neq j} \llbracket \pi_i.Q_i \rrbracket_a^s | \llbracket Q_j \rrbracket_a^s \left. \right) = T
\end{aligned}$$

By Corollary 1, $\{\varphi_a^s(z)/\varphi_a^s(x)\} \llbracket P \rrbracket_a^s \equiv_\alpha \llbracket \{z/x\}P \rrbracket_a^s$. To show that $T \cong_a^s \llbracket S' \rrbracket_a^m$ we stepwise reduce T by ignoring junk. Since $l, s \notin \text{fn}(\llbracket \{z/x\}P \rrbracket_a^m) \cup \text{fn}(\llbracket Q_j \rrbracket_a^m)$, we can reorder the term according to the restriction on l and the restriction on s can be omitted. By Lemma 26, then $(\nu l) \left(\prod_{i \in I_1, i \neq j} \llbracket \pi_i.Q_i \rrbracket_a^s | \overline{l} \langle \perp \rangle \right)$ is junk. Note that, by Lemma 17, the relation $\cong_a^s$ includes structural congruence. Thus, by Lemma 22, we conclude $T \cong_a^s \llbracket S' \rrbracket_a^s$.

Induction Hypothesis: $S_1 \mapsto S'_1$ implies $\exists T_1 \in \mathcal{P}_a . \llbracket S_1 \rrbracket_a^s \Longrightarrow T_1 \wedge T_1 \cong_a^s \llbracket S'_1 \rrbracket_a^s$

Induction Step: We have to consider the remaining three rules PAR, RES, and CONG of Figure 2.

Case of Rule PAR: Then $S = S_1 \mid S_2$ for some $S_1, S_2 \in \mathcal{P}_s$, $S_1 \mapsto S'_1$, and $S' = S'_1 \mid S_2$. By the induction hypothesis there is some $T_1 \in \mathcal{P}_a$ such that $\llbracket S_1 \rrbracket_a^s \Longrightarrow T_1$ and $T_1 \cong_a^s \llbracket S'_1 \rrbracket_a^s$. Since the encoding of the parallel operator is rigid, i.e., $\llbracket S \rrbracket_a^s = \llbracket S_1 \rrbracket_a^s \mid \llbracket S_2 \rrbracket_a^s$ and $\llbracket S' \rrbracket_a^s = \llbracket S'_1 \rrbracket_a^s \mid \llbracket S_2 \rrbracket_a^s$, we can apply rule PAR to conclude from $\llbracket S_1 \rrbracket_a^s \Longrightarrow T_1$ to $\llbracket S \rrbracket_a^s \Longrightarrow T_1 \mid \llbracket S_2 \rrbracket_a^s = T$. By Definition 28, $T_1 \cong_a^s \llbracket S'_1 \rrbracket_a^s$ implies $\mathcal{C}(T_1) \approx_a^s \mathcal{C}(\llbracket S'_1 \rrbracket_a^s)$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_a \upharpoonright_{\llbracket \cdot \rrbracket_a^s}$. Since $\llbracket \mathbf{0} \rrbracket_a^s \mid \llbracket S_2 \rrbracket_a^s \in \mathcal{P}_a \upharpoonright_{\llbracket \cdot \rrbracket_a^s}$, the quantification over $\mathcal{C}$ includes all contexts $\mathcal{C}$ such that $\mathcal{C}([\cdot]) = \mathcal{C}'([\cdot] \mid \llbracket S_2 \rrbracket_a^s)$. Because of that, we have $\mathcal{C}'(T_1 \mid \llbracket S_2 \rrbracket_a^s) \approx_a^s \mathcal{C}'(\llbracket S'_1 \rrbracket_a^s \mid \llbracket S_2 \rrbracket_a^s)$ for all contexts $\mathcal{C}'([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}'(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_a \upharpoonright_{\llbracket \cdot \rrbracket_a^s}$. By Definition 28, we conclude $T \cong_a^s \llbracket S' \rrbracket_a^s$.

Case of Rule RES: Then $S = (\nu x) S_1$ for some $x \in \mathcal{N}$ and some $S_1 \in \mathcal{P}_s$, $S_1 \mapsto S'_1$, and $S' = (\nu x) S'_1$. By the induction hypothesis there is some $T_1 \in \mathcal{P}_a$ such that $\llbracket S_1 \rrbracket_a^s \Longrightarrow T_1$ and $T_1 \cong_a^s \llbracket S'_1 \rrbracket_a^s$. Since the encoding of restriction is rigid, i.e., $\llbracket S \rrbracket_a^s = (\nu \varphi_a^s(x)) \llbracket S_1 \rrbracket_a^s$ and $\llbracket S' \rrbracket_a^s = (\nu \varphi_a^s(x)) \llbracket S'_1 \rrbracket_a^s$, we can apply rule RES to conclude from $\llbracket S_1 \rrbracket_a^s \Longrightarrow T_1$ to $\llbracket S \rrbracket_a^s \Longrightarrow (\nu \varphi_a^s(x)) T_1 = T$. By Definition 28, $T_1 \cong_a^s \llbracket S'_1 \rrbracket_a^s$ implies $\mathcal{C}(T_1) \approx_a^s \mathcal{C}(\llbracket S'_1 \rrbracket_a^s)$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_a \upharpoonright_{\llbracket \cdot \rrbracket_a^s}$. Since $(\nu \varphi_a^s(x)) \llbracket \mathbf{0} \rrbracket_a^s \in \mathcal{P}_a \upharpoonright_{\llbracket \cdot \rrbracket_a^s}$, the quantification over $\mathcal{C}$ includes all contexts $\mathcal{C}$ such that $\mathcal{C}([\cdot]) = \mathcal{C}'((\nu \varphi_a^s(x)) [\cdot])$. Because of that, we have $\mathcal{C}'((\nu \varphi_a^s(x)) T_1) \approx_a^s \mathcal{C}'((\nu \varphi_a^s(x)) \llbracket S'_1 \rrbracket_a^s)$ for all contexts $\mathcal{C}'([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}'(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_a \upharpoonright_{\llbracket \cdot \rrbracket_a^s}$. By Definition 28, we conclude $T \cong_a^s \llbracket S' \rrbracket_a^s$.

Case of Rule CONG: Then $S \equiv S_1$ for some $S_1 \in \mathcal{P}_s$, $S_1 \mapsto S'_1$, and $S'_1 \equiv S'$. By Lemma 20, the encoding $\llbracket \cdot \rrbracket_a^s$ preserves structural congruence of source terms modulo $\cong_a^s$. So $S \equiv S_1$ and $S'_1 \equiv S'$ implies $\llbracket S \rrbracket_a^s \cong_a^s \llbracket S_1 \rrbracket_a^s$ and $\llbracket S'_1 \rrbracket_a^s \cong_a^s \llbracket S' \rrbracket_a^s$. By Definition 28, for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^s) \in \mathcal{P}_a \upharpoonright_{\llbracket \cdot \rrbracket_a^s}$ we have $\mathcal{C}(\llbracket S \rrbracket_a^s) \approx_a^s \mathcal{C}(\llbracket S_1 \rrbracket_a^s)$, i.e., especially $\llbracket S \rrbracket_a^s \approx_a^s \llbracket S_1 \rrbracket_a^s$. Thus, by Definition 26, for each sequence $\llbracket S \rrbracket_a^s \Longrightarrow T$ there is a sequence $\llbracket S_1 \rrbracket_a^s \Longrightarrow T_1$ for some $T_1 \in \mathcal{P}_a$ such that $T \approx_a^s T_1$. The same holds for all Contexts $\mathcal{C}$, i.e., since $\mathcal{C}(\llbracket S \rrbracket_a^s) \approx_a^s \mathcal{C}(\llbracket S_1 \rrbracket_a^s)$, for each sequence $\mathcal{C}(\llbracket S \rrbracket_a^s) \Longrightarrow \mathcal{C}(T)$ there is a sequence $\mathcal{C}(\llbracket S_1 \rrbracket_a^s) \Longrightarrow \mathcal{C}(T_1)$ for some $T_1 \in \mathcal{P}_a$ such that $\mathcal{C}(T) \approx_a^s \mathcal{C}(T_1)$. So, by Definition 28, $T \cong_a^s T_1$. By the induction hypothesis $T_1 \cong_a^s \llbracket S'_1 \rrbracket_a^s$. Since, by Lemma 15, $\cong_a^s$ is an equivalence, $T \cong_a^s T_1$, $T_1 \cong_a^s \llbracket S'_1 \rrbracket_a^s$, and $\llbracket S'_1 \rrbracket_a^s \cong_a^s \llbracket S' \rrbracket_a^s$ implies $T \cong_a^s \llbracket S' \rrbracket_a^s$.

□

Lemma 31 (Operational Completeness). *The encoding $\llbracket \cdot \rrbracket_a^m$ fulfils operational completeness.*

Proof. By Definition 9 it suffice to show that:

$$\forall S, S' \in \mathcal{P}_m . S \mapsto S' \text{ implies } \exists T \in \mathcal{P}_a . \llbracket S \rrbracket_a^m \Longrightarrow T \wedge T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$$

The lemma then holds by induction over the number of steps in $S \mapsto S'$. To prove the condition above, we perform an induction over the proof tree that leads to the step $S \mapsto S'$.

Base Case: By the rules in Figure 2 each step on S is based either on Rule $\text{TAU}_{m,s}$, $\text{COM}_{m,s}$, or $\text{REP}_{m,s}$.

Case of Rule $\text{TAU}_{m,s}$: In this case S is a single sum, of which one summand is guarded by τ , and S' is the continuation of this τ guarded summand, i.e., there are some finite index set I , some guards π_i , and some processes $P_i \in \mathcal{P}_m$ such that $S = \sum_{i \in I} \pi_i . P_i$ with $\pi_j = \tau$ for some $j \in I$ and $S' = P_j$. The corresponding encodings are given by the following terms:

$$\begin{aligned} \llbracket S \rrbracket_a^m &\equiv (\nu l) \left(\bar{l} \langle \top \rangle \mid \prod_{i \in I, i \neq j} \llbracket \pi_i . P_i \rrbracket_a^m \mid \text{test } l \text{ then } \bar{l} \langle \perp \rangle \mid \llbracket P_j \rrbracket_a^m \text{ else } \bar{l} \langle \perp \rangle \right) \\ \llbracket S' \rrbracket_a^m &= \llbracket P_j \rrbracket_a^m \end{aligned}$$

We observe that $\llbracket S \rrbracket_a^m$ can emulate the step $S \mapsto S'$ by reducing the test-statement in the encoding of the j 's summand, i.e., by

$$\llbracket S \rrbracket_a^m \mapsto^2 (\nu l) \left(\prod_{i \in I, i \neq j} \llbracket \pi_i . P_i \rrbracket_a^m \mid \bar{l} \langle \perp \rangle \mid \llbracket P_j \rrbracket_a^m \right) = T.$$

We observe that $T \equiv (\nu l) \left(\prod_{i \in I, i \neq j} \llbracket \pi_i . P_i \rrbracket_a^m \mid \bar{l} \langle \perp \rangle \right) \mid \llbracket P_j \rrbracket_a^m$, since, due to the renaming policy φ_a^m , the name l is not free in $\llbracket P_j \rrbracket_a^m$. So the term $(\nu l) \left(\prod_{i \in I, i \neq j} \llbracket \pi_i . P_i \rrbracket_a^m \mid \bar{l} \langle \perp \rangle \right)$ is leftover, which is by Lemma 27 junk. By Lemma 22, we conclude that $T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Case of Rule $\text{COM}_{m,s}$: Here S is a parallel composition of two sums and S' is the parallel composition of the continuations of an input guarded summand of the first and a matching output guarded summand of the second sum, i.e., there are two finite index sets I_1, I_2 , some guards π_i , and some processes $P_i, Q_i \in \mathcal{P}_m$ such that $S = \sum_{i \in I_1} \pi_i.P_i \mid \sum_{i \in I_2} \pi_i.Q_i$ with $\pi_{j_1} = y(x)$ and $\pi_{j_2} = \overline{y}\langle z \rangle$ for some $j_1 \in I_1$, some $j_2 \in I_2$, and $x, y, z \in \mathcal{N}$, and $S' = \{^z/x\}P_{j_1} \mid Q_{j_2}$. Unfortunately the encodings of these terms are rather long:

$$\begin{aligned}
\llbracket S \rrbracket_a^m &\equiv (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad (\nu p_o, p_i) ((\nu l) (\overline{l}\langle \top \rangle \mid \prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^m \\
&\quad \mid (\nu r) (\overline{p_i}\langle \varphi_a^m(y), l, r \rangle \mid r^*(l_1, l_2, -, s, \varphi_a^m(x)). \\
&\quad \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1}\langle \perp \rangle \mid \overline{l_2}\langle \perp \rangle \mid \overline{s} \mid \llbracket P_{j_1} \rrbracket_a^m \\
&\quad \text{else } \overline{l_1}\langle \top \rangle \mid \overline{l_2}\langle \perp \rangle \\
&\quad \text{else } \overline{l_1}\langle \perp \rangle)) \\
&\quad \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \\
&\quad \mid (\nu p_o, p_i) ((\nu l) (\overline{l}\langle \top \rangle \mid \prod_{i \in I_2, i \neq j_2} \llbracket \pi_i.Q_i \rrbracket_a^m \mid (\nu s) (\overline{p_o}\langle \varphi_a^m(y), l, s, \varphi_a^m(z) \rangle \mid s. \llbracket Q_{j_2} \rrbracket_a^m)) \\
&\quad \mid \text{procRightOutReq} \mid \text{procRightInReq} \\
&\quad \mid \text{pushReq}) \\
\llbracket S' \rrbracket_a^m &= (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad (\nu p_o, p_i) (\llbracket \{^z/x\}P_{j_1} \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \mid (\nu p_o, p_i) (\llbracket Q_{j_2} \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid \text{pushReq})
\end{aligned}$$

To emulate the source term step $S \mapsto S'$, the endings of the two sums in S have to interact with the encoding of the parallel operator between them. At first the input and output register themselves to the encoding of the parallel operator by pushing requests. These requests are then combined and a test on the respective sum locks⁵ is induced by providing an output on the receiver lock. At least the test-statement is reduced to complete the emulation of the source term step.

$$\begin{aligned}
\llbracket S \rrbracket_a^m &\mapsto^3 (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up, l_a, l_b, r, s) (\\
&\quad (\nu p_o, p_i) (\overline{l_a}\langle \top \rangle \mid \{\overline{l_a}/l\} \left(\prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^m \right) \mid r^*(l_1, l_2, -, s, \varphi_a^m(x)). \\
&\quad \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1}\langle \perp \rangle \mid \overline{l_2}\langle \perp \rangle \mid \overline{s} \mid \llbracket P_{j_1} \rrbracket_a^m \text{ else } \overline{l_1}\langle \top \rangle \mid \overline{l_2}\langle \perp \rangle \text{ else } \overline{l_1}\langle \perp \rangle \\
&\quad \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \mid \overline{m_i}\langle \varphi_a^m(y), l_a, r \rangle \mid \overline{p_i, up}\langle \varphi_a^m(y), l_a, r \rangle) \\
&\quad \mid (\nu p_o, p_i) (\overline{l_b}\langle \top \rangle \mid \{\overline{l_b}/l\} \left(\prod_{i \in I_2, i \neq j_2} \llbracket \pi_i.Q_i \rrbracket_a^m \right) \mid s. \llbracket Q_{j_2} \rrbracket_a^m \\
&\quad \mid (\nu m_i, up) (m_i^*(y', l_r, r). ([y' = \varphi_a^m(y)] \overline{T}\langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_i, up}\langle y', l_r, r \rangle) \\
&\quad \mid (\nu m_i) (m_i, up \rightarrow m_i \mid \text{procRightOutReq})) \\
&\quad \mid \overline{p_o, up}\langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle \mid \text{procRightInReq} \\
&\quad \mid \text{pushReq})
\end{aligned}$$

⁵ In order to avoid a deadlock caused by multiple simultaneous such tests on sum locks, the sum locks are ordered by ensuring that always the left one is checked first.

$$\begin{aligned}
& \mapsto (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up, l_a, l_b, r, s) (\\
& \quad (\nu p_o, p_i) (\overline{l_a} \langle \top \rangle \mid \{l_a/l\} \left(\prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^m \right) \mid r^*(l_1, l_2, -, s, \varphi_a^m(x)). \\
& \quad \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1} \langle \perp \rangle \mid \overline{l_2} \langle \perp \rangle \mid \overline{s} \mid \llbracket P_{j_1} \rrbracket_a^m \text{ else } \overline{l_1} \langle \top \rangle \mid \overline{l_2} \langle \perp \rangle \text{ else } \overline{l_1} \langle \perp \rangle \\
& \quad \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \mid \overline{p_{i,up}} \langle \varphi_a^m(y), l_a, r \rangle) \\
& \quad \mid (\nu p_o, p_i) (\overline{l_b} \langle \top \rangle \mid \{l_b/l\} \left(\prod_{i \in I_2, i \neq j_2} \llbracket \pi_i.Q_i \rrbracket_a^m \right) \mid s. \llbracket Q_{j_2} \rrbracket_a^m \\
& \quad \mid (\nu m_{i,up}) (m_i^*(y', l_r, r) \cdot ([y' = \varphi_a^m(y)] \overline{r} \langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle) \\
& \quad \mid \overline{r} \langle l_a, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_{i,up}} \langle \varphi_a^m(y), l_a, r \rangle) \\
& \quad \mid (\nu m_i) (m_{i,up} \twoheadrightarrow m_i \mid \text{procRightOutReq}) \\
& \quad \mid \overline{p_{o,up}} \langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle \mid \text{procRightInReq}) \\
& \quad \mid \text{pushReq}) \\
& \mapsto^6 (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up, l_a, l_b, r, s) (\\
& \quad (\nu p_o, p_i) (\{l_a/l\} \left(\prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^m \right) \mid \overline{l_a} \langle \perp \rangle \mid \overline{l_b} \langle \perp \rangle \mid \{\varphi_a^m(z)/\varphi_a^m(x)\} \llbracket P_{j_1} \rrbracket_a^m \\
& \quad \mid r^*(l_1, l_2, -, s, \varphi_a^m(x)). \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1} \langle \perp \rangle \mid \overline{l_2} \langle \perp \rangle \mid \overline{s} \mid \llbracket P_{j_1} \rrbracket_a^m \\
& \quad \text{else } \overline{l_1} \langle \top \rangle \mid \overline{l_2} \langle \perp \rangle \\
& \quad \text{else } \overline{l_1} \langle \perp \rangle \\
& \quad \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \mid \overline{p_{i,up}} \langle \varphi_a^m(y), l_a, r \rangle) \\
& \quad \mid (\nu p_o, p_i) (\{l_b/l\} \left(\prod_{i \in I_2, i \neq j_2} \llbracket \pi_i.Q_i \rrbracket_a^m \right) \mid \llbracket Q_{j_2} \rrbracket_a^m \\
& \quad \mid (\nu m_{i,up}) (m_i^*(y', l_r, r) \cdot ([y' = \varphi_a^m(y)] \overline{r} \langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle) \\
& \quad \mid \overline{m_{i,up}} \langle \varphi_a^m(y), l_a, r \rangle \mid (\nu m_i) (m_{i,up} \twoheadrightarrow m_i \mid \text{procRightOutReq}) \\
& \quad \mid \overline{p_{o,up}} \langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle \mid \text{procRightInReq}) \\
& \quad \mid \text{pushReq}) = T
\end{aligned}$$

By Corollary 1, $\{\varphi_a^m(z)/\varphi_a^m(x)\} \llbracket P_{j_1} \rrbracket_a^m \equiv_\alpha \llbracket \{z/x\} P_{j_1} \rrbracket_a^m$. To show that $T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$, we stepwise reduce T by ignoring junk. By Lemma 25, we can ignore the requests $\overline{p_{i,up}} \langle \varphi_a^m(y), l_a, r \rangle$, $\overline{m_{i,up}} \langle \varphi_a^m(y), l_a, r \rangle$, and $\overline{p_{o,up}} \langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle$. Next, by Lemma 28, we can ignore the term

$$\begin{aligned}
& r^*(l_1, l_2, -, s, \varphi_a^m(x)). \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1} \langle \perp \rangle \mid \overline{l_2} \langle \perp \rangle \mid \overline{s} \mid \llbracket P_{j_1} \rrbracket_a^m \text{ else } \overline{l_1} \langle \top \rangle \mid \overline{l_2} \langle \perp \rangle \\
& \text{else } \overline{l_1} \langle \perp \rangle.
\end{aligned}$$

And, by Lemma 29, we can also ignore $[y' = \varphi_a^m(y)] \overline{r} \langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle$, so

$$m_i^*(y', l_r, r) \cdot ([y' = \varphi_a^m(y)] \overline{r} \langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle)$$

becomes $m_i \twoheadrightarrow m_{i,up}$. Note that this forwarder and the following forwarder $m_{i,up} \twoheadrightarrow m_i$ for an other instance of m_i may be necessary to emulate further source term steps, but, since they perform only invisible steps, they do not influence the state of T modulo $\cong_{a,2}^m$ in comparison to a fresh chain of right requests as in $\llbracket S' \rrbracket_a^m$. At least, since $l_a, l_b, r, s \notin \text{fn}(\llbracket P_{j_1} \rrbracket_a^m) \cup \text{fn}(\llbracket P_{j_2} \rrbracket_a^m)$, we can reorder the term according to the restrictions on l_a, l_b, r and the restriction on s can be omitted. By Lemma 27, then $(\nu l) \left(\prod_{i \in I_1, i \neq j_1} \llbracket \pi_i.P_i \rrbracket_a^m \mid \overline{l} \langle \perp \rangle \right)$ and $(\nu l) \left(\prod_{i \in I_1, i \neq j_2} \llbracket \pi_i.Q_i \rrbracket_a^m \mid \overline{l} \langle \perp \rangle \right)$ are junk. So, by Lemma 22, we conclude $T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Case of Rule REP_{m,s}: Here S is a parallel composition of a replicated input and a sum and S' is the parallel composition of the replicated input, the continuation of the replicated input, and the continuation of a

matching output guarded summand, i.e., there is a finite index sets I , some guards π_i , and some processes $P, Q_i \in \mathcal{P}_m$ such that $S = y^*(x).P \mid \sum_{i \in I} \pi_i.Q_i$ with $\pi_j = \overline{y}\langle z \rangle$ for some $j \in I$ and $x, y, z \in \mathcal{N}$, and $S' = \{z/x\}P \mid Q_j \mid y^*(x).P$. Unfortunately, the encodings of S and S' are again long:

$$\begin{aligned}
\llbracket S \rrbracket_a^m &\equiv (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad (\nu p_o, p_i) ((\nu l, r, c_{r1}, c_{r2}, r_o, r_i) (\\
&\quad \quad r^*(-, -, l_s, s, \varphi_a^m(x)).\text{test } l_s \text{ then } \overline{l_s}\langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}}\langle \varphi_a^m(x) \rangle \text{ else } \overline{l_s}\langle \perp \rangle \\
&\quad \quad \overline{p_i}\langle \varphi_a^m(y), l, r \rangle \mid \overline{r_i}\langle \varphi_a^m(y), l, r \rangle \mid \overline{l}\langle \top \rangle \overline{c_{r2}}\langle r_o, r_i \rangle \\
&\quad \quad \mid c_{r1}^*(\varphi_a^m(x)).c_{r2}(r_o, r_i).(\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad \quad \quad \text{pushReqIn} \\
&\quad \quad \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \quad \mid (\nu r_o, r_i) (\overline{c_{r2}}\langle r_o \mid r_i \rangle \mid \text{pushReqOut})) \\
&\quad \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad (\nu p_o, p_i) ((\nu l) \left(\overline{l}\langle \top \rangle \mid \prod_{i \in I_2, i \neq j} \llbracket \pi_i.Q_i \rrbracket_a^m \mid (\nu s) (\overline{p_o}\langle \varphi_a^m(y), l, s, \varphi_a^m(z) \rangle \mid s. \llbracket Q_j \rrbracket_a^m) \right) \\
&\quad \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \text{pushReq}) \\
\llbracket S' \rrbracket_a^m &= (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad (\nu p_o, p_i) ((\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad \quad (\nu p_o, p_i) (\llbracket \{z/x\}(P) \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \quad (\nu p_o, p_i) (\llbracket Q_j \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \quad \text{pushReq}) \\
&\quad \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad (\nu p_o, p_i) (\llbracket y^*(x).P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \text{pushReq})
\end{aligned}$$

To emulate the source term step $S \mapsto S'$, the two subterms of $\llbracket S \rrbracket_a^m$ have to interact with the encoding of the parallel operator between them. At first the replicated input and the output register themselves to the encoding of the parallel operator by pushing requests. There the requests are combined and a test on the sum lock of the sender is induced by providing an output on the receiver lock. Next the test-statement is reduced. To complete the emulation of the source term step, at least the continuation of the replicated input encoding is unguarded and placed within an adoption of the parallel operator encoding.

$$\begin{aligned}
\llbracket S \rrbracket_a^m &\mapsto^3 (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up, l_a, l_b, r, s) (\\
&\quad (\nu p_o, p_i) ((\nu c_{r1}, c_{r2}, r_o, r_i) (\\
&\quad \quad r^*(-, -, l_s, s, \varphi_a^m(x)).\text{test } l_s \text{ then } \overline{l_s}\langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}}\langle \varphi_a^m(x) \rangle \text{ else } \overline{l_s}\langle \perp \rangle \\
&\quad \quad \mid \overline{r_i}\langle \varphi_a^m(y), l_a, r \rangle \mid \overline{l_a}\langle \top \rangle \mid \overline{c_{r2}}\langle r_o, r_i \rangle \mid c_{r1}^*(\varphi_a^m(x)).c_{r2}(r_o, r_i). \\
&\quad \quad (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\text{pushReqIn} \\
&\quad \quad \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \quad \mid (\nu r_o, r_i) (\overline{c_{r2}}\langle r_o \mid r_i \rangle \mid \text{pushReqOut})) \\
&\quad \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \mid \overline{m_i}\langle \varphi_a^m(y), l_a, r \rangle \mid \overline{p_i, up}\langle \varphi_a^m(y), l_a, r \rangle) \\
&\quad \mid (\nu p_o, p_i) (\overline{l_b}\langle \top \rangle \mid \{l_b/l\} \left(\prod_{i \in I_2, i \neq j} \llbracket \pi_i.Q_i \rrbracket_a^m \right) \mid s. \llbracket Q_j \rrbracket_a^m \\
&\quad \mid (\nu m_i, up) (m_i^*(y', l_r, r).([y' = \varphi_a^m(y)] \mid \overline{r}\langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_i, up}\langle y', l_r, r \rangle) \\
&\quad \mid (\nu m_i) (m_i, up \twoheadrightarrow m_i \mid \text{procRightOutReq})) \\
&\quad \mid \overline{p_o, up}\langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle \mid \text{procRightInReq} \mid \text{pushReq})
\end{aligned}$$

$$\begin{aligned}
& \mapsto (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up, l_a, l_b, r, s) (\\
& \quad (\nu p_o, p_i) ((\nu c_{r1}, c_{r2}, r_o, r_i) (\\
& \quad \quad r^* (-, -, l_s, s, \varphi_a^m(x)) . \text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x) \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\
& \quad \mid \overline{r_i} \langle \varphi_a^m(y), l_a, r \rangle \mid \overline{l_a} \langle \top \rangle \mid \overline{c_{r2}} \langle r_o, r_i \rangle \mid c_{r1}^* (\varphi_a^m(x)) . c_{r2} (r_o, r_i) . \\
& \quad (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\text{pushReqIn} \\
& \quad \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
& \quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o \mid r_i \rangle \mid \text{pushReqOut})) \\
& \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \mid \overline{p_i, up} \langle \varphi_a^m(y), l_a, r \rangle) \\
& \mid (\nu p_o, p_i) (\overline{l_b} \langle \top \rangle \mid \{l_b/l\} \left(\prod_{i \in I_2, i \neq j} \llbracket \pi_i . Q_i \rrbracket_a^m \right) \mid s . \llbracket Q_j \rrbracket_a^m \\
& \quad \mid (\nu m_i, up) (m_i^* (y', l_r, r) . ([y' = \varphi_a^m(y)] \overline{r} \langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_i, up} \langle y', l_r, r \rangle) \\
& \quad \mid \overline{r} \langle l_a, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_i, up} \langle \varphi_a^m(y), l_a, r \rangle \\
& \quad \mid (\nu m_i) (m_i, up \twoheadrightarrow m_i \mid \text{procRightOutReq})) \\
& \mid \overline{p_o, up} \langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle \mid \text{procRightInReq} \mid \text{pushReq}) \\
& \mapsto^4 (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up, l_a, l_b, r, s) (\\
& \quad (\nu p_o, p_i) ((\nu c_{r1}, c_{r2}, r_o, r_i) (\overline{l_b} \langle \perp \rangle \mid \overline{c_{r1}} \langle \varphi_a^m(z) \rangle \\
& \quad \mid r^* (-, -, l_s, s, \varphi_a^m(x)) . \text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x) \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\
& \quad \mid \overline{r_i} \langle \varphi_a^m(y), l_a, r \rangle \mid \overline{l_a} \langle \top \rangle \mid \overline{c_{r2}} \langle r_o, r_i \rangle \mid c_{r1}^* (\varphi_a^m(x)) . c_{r2} (r_o, r_i) . \\
& \quad (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\text{pushReqIn} \\
& \quad \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
& \quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o \mid r_i \rangle \mid \text{pushReqOut})) \\
& \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \mid \overline{p_i, up} \langle \varphi_a^m(y), l_a, r \rangle) \\
& \mid (\nu p_o, p_i) (\{l_b/l\} \left(\prod_{i \in I_2, i \neq j} \llbracket \pi_i . Q_i \rrbracket_a^m \right) \mid \llbracket Q_j \rrbracket_a^m \\
& \quad \mid (\nu m_i, up) (m_i^* (y', l_r, r) . ([y' = \varphi_a^m(y)] \overline{r} \langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_i, up} \langle y', l_r, r \rangle) \\
& \quad \mid \overline{m_i, up} \langle \varphi_a^m(y), l_a, r \rangle \mid (\nu m_i) (m_i, up \twoheadrightarrow m_i \mid \text{procRightOutReq})) \\
& \mid \overline{p_o, up} \langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle \mid \text{procRightInReq} \mid \text{pushReq})
\end{aligned}$$

$$\begin{aligned}
& \mapsto^2 (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up, l_a, l_b, r, s) (\\
& \quad (\nu p_o, p_i) ((\nu c_{r1}, c_{r2}, r_o, r_i) (\\
& \quad \quad \overline{l_b} \langle \perp \rangle \mid r^* (-, -, l_s, s, \varphi_a^m(x)).\text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x) \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\
& \quad \quad \mid \overline{r_i} \langle \varphi_a^m(y), l_a, r \rangle \mid \overline{l_a} \langle \top \rangle \mid c_{r1}^* (\varphi_a^m(x)).c_{r2} (r_o, r_i) . \\
& \quad \quad (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\text{pushReqIn} \\
& \quad \quad \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
& \quad \quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o \mid r_i \rangle \mid \text{pushReqOut})) \\
& \quad \mid (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\text{pushReqIn} \\
& \quad \mid (\nu p_o, p_i) (\left\{ \varphi_a^m(z) / \varphi_a^m(x) \right\} (\llbracket P \rrbracket_a^m) \\
& \quad \quad \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
& \quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o \mid r_i \rangle \mid \text{pushReqOut}))) \\
& \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \mid \overline{p_{i,up}} \langle \varphi_a^m(y), l_a, r \rangle) \\
& \mid (\nu p_o, p_i) (\{ l_b / l \} \left(\prod_{i \in I_2, i \neq j} \llbracket \pi_i.Q_i \rrbracket_a^m \right) \mid \llbracket Q_j \rrbracket_a^m \\
& \quad \mid (\nu m_{i,up}) (m_i^* (y', l_r, r) . ([y' = \varphi_a^m(y)] \overline{r} \langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle) \\
& \quad \mid \overline{m_{i,up}} \langle \varphi_a^m(y), l_a, r \rangle \mid (\nu m_i) (m_{i,up} \rightarrow m_i \mid \text{procRightOutReq})) \\
& \quad \mid \overline{p_{o,up}} \langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle \mid \text{procRightInReq}) \\
& \mid \text{pushReq}) = T
\end{aligned}$$

By Corollary 1, $\{ \varphi_a^m(z) / \varphi_a^m(x) \} \llbracket P \rrbracket_a^m \equiv_\alpha \llbracket \{z/x\} P \rrbracket_a^m$. Unfortunately, this time it does not suffer to ignore junk to prove that $T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$, because in $\llbracket S' \rrbracket_a^m$ there are two encoded parallel operators whereas in T there is only one. Nevertheless, we start reducing T by omitting junk. Since the sum lock l_b is instantiated by false, by Lemma 25, the request $\overline{p_{o,up}} \langle \varphi_a^m(y), l_b, s, \varphi_a^m(z) \rangle$ is junk. Moreover, by Lemma 29, the term

$$m_i^* (y', l_r, r) . ([y' = \varphi_a^m(y)] \overline{r} \langle l_r, l_b, l_b, s, \varphi_a^m(z) \rangle \mid \overline{m_{i,up}} \langle y', l_r, r \rangle)$$

reduces to the forwarder $m_i \rightarrow m_{i,up}$. Since $l_a, l_b, r, s \notin \text{fn}(\llbracket \{z/x\} P \rrbracket_a^m) \cup \text{fn}(\llbracket Q_j \rrbracket_a^m)$, we can reorder the term according to the restrictions on l_a, l_b , and r and the restriction on s can be omitted. By Lemma 27, then $(\nu l) \left(\prod_{i \in I, i \neq j} \llbracket \pi_i.Q_i \rrbracket_a^m \mid \overline{l} \langle \perp \rangle \right)$ is junk. By Lemma 22, we deduce $T \cong_{a,2}^m T'$, where T' is:

$$\begin{aligned}
T \cong_{a,2}^m & (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
& (\nu p_o, p_i) ((\nu l, r, c_{r1}, c_{r2}, r_o, r_i) (\\
& \quad r^* (-, -, l_s, s, \varphi_a^m(x)).\text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x) \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\
& \quad \mid \overline{r_i} \langle \varphi_a^m(y), l, r \rangle \mid \overline{l} \langle \top \rangle \\
& \quad \mid c_{r1}^* (\varphi_a^m(x)).c_{r2} (r_o, r_i) . (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\\
& \quad \quad \text{pushReqIn} \\
& \quad \quad \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
& \quad \quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o \mid r_i \rangle \mid \text{pushReqOut})) \\
& \quad \mid (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\text{pushReqIn} \\
& \quad \mid (\nu p_o, p_i) (\llbracket \{z/x\} P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
& \quad \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o \mid r_i \rangle \mid \text{pushReqOut}))) \\
& \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \mid \overline{p_{i,up}} \langle \varphi_a^m(y), l, r \rangle) \\
& \mid (\nu p_o, p_i) (\llbracket Q_j \rrbracket_a^m \mid \text{procRightInReq} \\
& \quad \mid (\nu m_{i,up}) (m_i \rightarrow m_{i,up} \mid \overline{m_{i,up}} \langle \varphi_a^m(y), l, r \rangle \mid (\nu m_i) (m_{i,up} \rightarrow m_i \mid \text{procRightOutReq}))) \\
& \mid \text{pushReq}) = T'
\end{aligned}$$

Analysing T' we observe that in comparison to $\llbracket S' \rrbracket_a^m$ the encoded subterms $\llbracket \{z/x\}P \rrbracket_a^m$, $\llbracket Q_j \rrbracket_a^m$, and the term representing $\llbracket y^*(x).P \rrbracket_a^m$ appear in the wrong order. However, since $S' \equiv S'' = (y^*(x).P \mid \{z/x\}P) \mid Q_j$ and $\cong_{a,2}^m$, by Lemma 21, preserves structural congruence of source terms, we have $\llbracket S' \rrbracket_a^m \cong_{a,2}^m \llbracket S'' \rrbracket_a^m$, i.e., the order of these subterms does not matter. As in the case before, on the right side of the parallel operator encoding there are the two forwarders $m_i \rightarrow m_{i,up}$ and $m_{i,up} \rightarrow m_i$ (for different instances of m_i). Again they are necessary to emulate further source term steps on the continuation $\llbracket Q_j \rrbracket_a^m$, but, since they perform only invisible steps, they do not influence the state of T' modulo $\cong_{a,2}^m$.

Moreover there is the request $\overline{m_{i,up}} \langle \varphi_a^m(y), l, r \rangle$, to enable an emulation of a communication of Q_j and $y^*(x).P$. Note that there is also the request $\overline{p_{i,up}} \langle \varphi_a^m(y), l, r \rangle$ at the right side of the parallel operator encoding, but the request $\overline{p_i} \langle \varphi_a^m(y), l, r \rangle$, which belongs to $\llbracket y^*(x).P \rrbracket_a^m$, is missing. However, since by $m_{i,up} \rightarrow m_i$ the request $\overline{p_{i,up}} \langle \varphi_a^m(y), l, r \rangle$ is forwarded to $\overline{m_i} \langle \varphi_a^m(y), l, r \rangle$ within a pure administrative step and since this configuration is equal to one application of `procLeftInReq` on $\overline{p_i} \langle \varphi_a^m(y), l, r \rangle$, which is again a pure administrative step, these two requests in comparison to $\overline{p_i} \langle \varphi_a^m(y), l, r \rangle$ do not influence the state of T' modulo $\cong_{a,2}^m$.

What remains as difference of T' and $\llbracket S'' \rrbracket_a^m$ is the fact, that in T' the encoding of $\{z/x\}P$ appears within a branch of the replicated input encoding whereas in $\llbracket S'' \rrbracket_a^m$ it appears as right branch of a parallel operator encoding, i.e., it remains to show that $T'' \cong_{a,2}^m \llbracket y^*(x).P \mid \{z/x\}P \rrbracket_a^m$, where

$$\begin{aligned} T'' = & (\nu l, r, c_{r1}, c_{r2}, r_o, r_i) (\\ & r^*(-, -, l_s, s, \varphi_a^m(x)).\text{test } l_s \text{ then } \overline{l_s} \langle \perp \rangle \mid \overline{s} \mid \overline{c_{r1}} \langle \varphi_a^m(x) \rangle \text{ else } \overline{l_s} \langle \perp \rangle \\ & \mid \overline{r_i} \langle \varphi_a^m(y), l, r \rangle \mid \overline{l} \langle \top \rangle \\ & \mid c_{r1}^*(\varphi_a^m(x)).c_{r2}(r_o, r_i) \cdot (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\text{pushReqIn} \\ & \mid (\nu p_o, p_i) (\llbracket P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o \mid r_i \rangle \mid \text{pushReqOut}) \\ & \mid (\nu m_o, m_i, p_o, up, p_i, up, r_o, up, r_i, up, c_o, c_i, m_o, up, m_i, up) (\text{pushReqIn} \\ & \mid (\nu p_o, p_i) (\llbracket \{z/x\}P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\ & \mid (\nu r_o, r_i) (\overline{c_{r2}} \langle r_o \mid r_i \rangle \mid \text{pushReqOut})) \end{aligned}$$

First, note that the term

$$(\nu p_o, p_i) (\llbracket \{z/x\}P \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq})$$

exactly corresponds to the right branch of $\llbracket y^*(x).P \mid \{z/x\}P \rrbracket_a^m$. If we compare `pushReqIn` with `procLeftOutReq` and `procLeftInReq`, then we observe that the former includes exactly the same forwarders as the later but also some additional forwarders. The same holds for `pushReqOut` and `pushReq`. Note that the additional forwarders ensures that each requests of each branch of the replicated input encoding is forwarded to each next right branch, and so these additional forwarders are necessary in case there is more than one branch. Also note that the given forwarders guarantee that each pair of requests, such that one is an input and the other one an output request and both requests do not origin from the same sum, can be combined. Moreover, note that the only request from the left side, i.e., of the encoding of the replicated input, is transmitted to the right side, i.e., the only branch of the replicated input, by the request $\overline{r_i} \langle \varphi_a^m(y), l, r \rangle$ and `pushReqIn`. So these forwarders do not distinguish T' and $\llbracket S'' \rrbracket_a^m$ modulo $\cong_{a,2}^m$.

Since T'' and $\llbracket y^*(x).P \mid \{z/x\}P \rrbracket_a^m$ do only differ by the forwarding of requests but nevertheless allow for the same combinations, we deduce that $T'' \cong_{a,2}^m \llbracket y^*(x).P \mid \{z/x\}P \rrbracket_a^m$. Thus, by Lemma 15, we conclude $T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Induction Hypothesis: $S_1 \mapsto S'_1$ implies $\exists T_1 \in \mathcal{P}_a \cdot \llbracket S_1 \rrbracket_a^m \Longrightarrow T_1 \wedge T_1 \cong_{a,2}^m \llbracket S'_1 \rrbracket_a^m$

Induction Step: We have to consider the remaining three rules `PAR`, `RES`, and `CONG` of Figure 2.

Case of Rule `PAR`: Then $S = S_1 \mid S_2$ for some $S_1, S_2 \in \mathcal{P}_m$, $S_1 \mapsto S'_1$, and $S' = S'_1 \mid S_2$. By the induction hypothesis there is some $T_1 \in \mathcal{P}_a$ such that $\llbracket S_1 \rrbracket_a^m \Longrightarrow T_1$ and $T_1 \cong_{a,2}^m \llbracket S'_1 \rrbracket_a^m$. The corresponding encodings

are given by the following terms:

$$\begin{aligned}
\llbracket S \rrbracket_a^m &= (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad (\nu p_o, p_i) (\llbracket S_1 \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \mid (\nu p_o, p_i) (\llbracket S_2 \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid \text{pushReq}) \\
\llbracket S' \rrbracket_a^m &= (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad (\nu p_o, p_i) (\llbracket S'_1 \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \mid (\nu p_o, p_i) (\llbracket S'_2 \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid \text{pushReq})
\end{aligned}$$

Since $\llbracket S_1 \rrbracket_a^m \Longrightarrow T_1$ and since $\llbracket S_1 \rrbracket_a^m$ is not guarded in $\llbracket S \rrbracket_a^m$, we can use the rules PAR, RES, and CONG in the asynchronous calculus to show that:

$$\begin{aligned}
\llbracket S \rrbracket_a^m &\Longrightarrow (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad (\nu p_o, p_i) (T_1 \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \mid (\nu p_o, p_i) (\llbracket S_2 \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid \text{pushReq}) = T
\end{aligned}$$

By Definition 28, $T_1 \cong_{a,2}^m \llbracket S'_1 \rrbracket_a^m$ implies $\mathcal{C}(T_1) \approx_{a,2}^m \mathcal{C}(\llbracket S'_1 \rrbracket_a^m)$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^m) \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$. Since $\llbracket \mathbf{0} \mid S_2 \rrbracket_a^m \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$, the quantification over $\mathcal{C}$ includes all contexts $\mathcal{C}$ such that:

$$\begin{aligned}
\mathcal{C}([\cdot]) &= \mathcal{C}'((\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\
&\quad (\nu p_o, p_i) ([\cdot] \mid \text{procLeftOutReq} \mid \text{procLeftInReq}) \\
&\quad \mid (\nu p_o, p_i) (\llbracket S_2 \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq}) \\
&\quad \mid \text{pushReq})) \\
&= \mathcal{C}'(\mathcal{C}''([\cdot]))
\end{aligned}$$

Because of that, we have $\mathcal{C}'(\mathcal{C}''(T_1)) \approx_{a,2}^m \mathcal{C}'(\mathcal{C}''(\llbracket S'_1 \rrbracket_a^m))$ for all contexts $\mathcal{C}'([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}'(\llbracket \mathbf{0} \rrbracket_a^m) \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$. By Definition 28, we conclude $T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Case of Rule RES: Then $S = (\nu x) S_1$ for some $x \in \mathcal{N}$ and some $S_1 \in \mathcal{P}_m$, $S_1 \mapsto S'_1$, and $S' = (\nu x) S'_1$.

By the induction hypothesis there is some $T_1 \in \mathcal{P}_a$ such that $\llbracket S_1 \rrbracket_a^m \Longrightarrow T_1$ and $T_1 \cong_{a,2}^m \llbracket S'_1 \rrbracket_a^m$. Since the encoding of restriction is rigid, i.e., $\llbracket S \rrbracket_a^m = (\nu \varphi_a^m(x)) \llbracket S_1 \rrbracket_a^m$ and $\llbracket S' \rrbracket_a^m = (\nu \varphi_a^m(x)) \llbracket S'_1 \rrbracket_a^m$, we can apply rule RES to conclude from $\llbracket S_1 \rrbracket_a^m \Longrightarrow T_1$ to $\llbracket S \rrbracket_a^m \Longrightarrow (\nu \varphi_a^s(x)) T_1 = T$. By Definition 28, $T_1 \cong_{a,2}^m \llbracket S'_1 \rrbracket_a^m$ implies $\mathcal{C}(T_1) \approx_{a,2}^m \mathcal{C}(\llbracket S'_1 \rrbracket_a^m)$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^m) \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$. Since $(\nu \varphi_a^m(x)) \llbracket \mathbf{0} \rrbracket_a^m \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$, the quantification over $\mathcal{C}$ includes all contexts $\mathcal{C}$ such that $\mathcal{C}([\cdot]) = \mathcal{C}'((\nu \varphi_a^m(x)) [\cdot])$. Because of that, we have $\mathcal{C}'((\nu \varphi_a^m(x)) T_1) \approx_{a,2}^m \mathcal{C}'((\nu \varphi_a^m(x)) \llbracket S'_1 \rrbracket_a^m)$ for all contexts $\mathcal{C}'([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}'(\llbracket \mathbf{0} \rrbracket_a^m) \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$. By Definition 28, we conclude $T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

Case of Rule CONG: Then $S \equiv S_1$ for some $S_1 \in \mathcal{P}_m$, $S_1 \mapsto S'_1$, and $S'_1 \equiv S'$. By Lemma 21, the encoding $\llbracket \cdot \rrbracket_a^m$ preserves structural congruence of source terms modulo $\cong_{a,2}^m$. So $S \equiv S_1$ and $S'_1 \equiv S'$ implies $\llbracket S \rrbracket_a^m \cong_{a,2}^m \llbracket S_1 \rrbracket_a^m$ and $\llbracket S'_1 \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$. By Definition 28, for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket \mathbf{0} \rrbracket_a^m) \in \mathcal{P}_a \upharpoonright \llbracket \cdot \rrbracket_a^m$ we have $\mathcal{C}(\llbracket S \rrbracket_a^m) \approx_{a,2}^m \mathcal{C}(\llbracket S_1 \rrbracket_a^m)$, i.e., especially $\llbracket S \rrbracket_a^m \approx_{a,2}^m \llbracket S_1 \rrbracket_a^m$. Thus, by Definition 26, for each sequence $\llbracket S \rrbracket_a^m \Longrightarrow T$ there is a sequence $\llbracket S_1 \rrbracket_a^m \Longrightarrow T_1$ for some $T_1 \in \mathcal{P}_a$ such that $T \approx_{a,2}^m T_1$. The same holds for all Contexts $\mathcal{C}$, i.e., since $\mathcal{C}(\llbracket S \rrbracket_a^m) \approx_{a,2}^m \mathcal{C}(\llbracket S_1 \rrbracket_a^m)$, for each sequence $\mathcal{C}(\llbracket S \rrbracket_a^m) \Longrightarrow \mathcal{C}(T)$ there is a sequence $\mathcal{C}(\llbracket S_1 \rrbracket_a^m) \Longrightarrow \mathcal{C}(T_1)$ for some $T_1 \in \mathcal{P}_a$ such that $\mathcal{C}(T) \approx_{a,2}^m \mathcal{C}(T_1)$. So, by Definition 28, $T \cong_{a,2}^m T_1$. By the induction hypothesis $T_1 \cong_{a,2}^m \llbracket S'_1 \rrbracket_a^m$. Since, by Lemma 15, $\cong_{a,2}^m$ is an equivalence, $T \cong_{a,2}^m T_1$, $T_1 \cong_{a,2}^m \llbracket S'_1 \rrbracket_a^m$, and $\llbracket S'_1 \rrbracket_a^m \cong_{a,2}^m \llbracket S' \rrbracket_a^m$ implies $T \cong_{a,2}^m \llbracket S' \rrbracket_a^m$.

□

If we analyse the proofs of the Lemmata 30 and 31, we observe that for each emulation there is exactly one core step, i.e., there is exactly one core step for each of the rules $\text{TAU}_{m,s}$, $\text{COM}_{m,s}$, and $\text{REP}_{m,s}$ and the emulation

of the remaining rules do not introduce additional core steps. This underpins our intuition of core steps (compare to Section 2.3) that any emulation of a source term step is connected to exactly one core step. Moreover, any core step marks exactly one emulation of a source term step by steering the emulation to the “point of no return”, i.e., to a point, from where no other sequence of steps can disable the completion of that emulation and from where any possibility to emulate a conflicting source term step is ultimately withdrawn.

Lemma 32. *Any emulation of a source term step includes exactly one core step and any core step steers the emulation of a source term step to a point, from where it eventually has to be completed.*

Proof. If we analyse the reduction rules in Figure 2, we observe that the result of a source term step is the unguarding of one or two former guarded subterms. If we rely on this fact to mark the essence of a step, then an emulation is characterised by the unguarding of the respective encoded continuations. Analysing the encoding functions in Figure 3 and Figure 4 we observe that such encoded continuations are guarded either by a sender lock or a test-statement. Note that, as proved in [Nes00] for $\llbracket \cdot \rrbracket_a^s$ and by the Lemma 11 and Lemma 12, neither pure nor impure administrative steps can introduce deadlock.

The reduction of a summand guarded by τ is the only case of a reduction step that does not require the interaction of a receiver and a sender (compare to rule $\text{TAU}_{m,s}$). Both encodings introduce a sum lock to encode a sum and translate summands guarded by τ into a single test-statement, that tests the corresponding sum lock and in case of success unguards the encoded continuation and provides a negative instantiation of the sum lock. Note that to emulate such a source term for both encodings only two steps are necessary to reduce the test-statement. The first consumes the instantiation of the sum lock. If this instantiation is positive we call that step a core step. Note that before this step, an emulation of a conflicting source term step may change the instantiation of the sum lock into a negative instantiation and thus withdraw the possibility to emulate the step. On the other side as soon as the positive instantiation of the sum lock is consumed, there is, by Lemma 9 and Lemma 10, no possibility to prevent that the second step necessary to complete the emulation eventually happens. So, whenever such core step is performed, eventually the encoded continuation is unguarded. Moreover, the only way to instantiate the consumed sum lock is to complete the emulation, which leads to a negative instantiation of that sum lock. By Lemma 5, there is no chance to unguard a positive instantiation of that sum lock afterwards. Note that any source term step, that is in conflict to the considered step on the τ guarded summand, have to reduce another summand of the same sum. Remember that, by Lemma 26 and 27, encoded summands connected to a negative instantiation of a sum lock are junk. So the consumption of the positive instantiation of the sum lock immediately rules out any emulation of a conflicting source term step. Moreover, since there is no possibility to reach a positive instantiation of that sum lock again, there is no possibility to emulate this source term step twice and any translated observable connected to this sum lock, i.e., to this sum, is immediately withdrawn by the consumption of the positive instantiation. Because of that, for any emulation of a source term step based on rule $\text{TAU}_{m,s}$ there is exactly one core step and for any such core step exactly one source term step is emulated.

In case of rule $\text{COM}_{m,s}$ the source term step is on an interaction of an input guarded and an output guarded summand. The encoding of the continuation of the receiver is guarded by the second of a nested test-statement, while the encoded continuation of the sender is guarded by a sender lock, which in turn is guarded by the nested test-statement. In Example 1 we explain that reducing the first test-statement does not ensure, that the emulation can be completed. However, as soon as the positive instantiation of the second sum lock is consumed we can repeat the argumentation of the case above to show that the point of no return of that emulation is reached. We observe that the consumption of the second positive sum lock instantiation is indeed the only core step necessary to emulate this source term step. It immediately withdraw any possibility to complete the emulation of a conflicting source term step, because it ensures that both consumed positive instantiations of sum lock are never restored. With that it also immediately withdraws all translated observables on the summands of these to sums. Moreover, by Lemma 9 and Lemma 10, the encoded continuations of the respective sender and receiver have eventually to become unguarded. Thus again for any emulation of a source term step based on rule $\text{COM}_{m,s}$ there is exactly one core step and for any such core step exactly one source term step is emulated.

In case of rule $\text{REP}_{m,s}$ the source term step is on an interaction of a replicated input and an output guarded summand. The encoding of the continuation of the receiver is guarded by a single test-statement, while the encoded continuation of the sender is guarded by a sender lock, which in turn is guarded by the single test-statement. As soon as the positive instantiation of the second sum lock is consumed we can repeat the argumentation of the first case to show that the point of no return of that emulation is reached. We observe that the consumption of the positive sum lock instantiation is indeed the only core step necessary to emulate this source term step. It immediately withdraw any possibility to complete the emulation of a conflicting source term step, because it ensures that the consumed positive instantiation of the sum lock is never restored. With that it also immediately withdraws all translated

observables on the summands of that sum. Moreover, by Lemma 9 and Lemma 10, the encoded continuations of the respective sender and receiver have eventually to become unguarded. Thus again for any emulation of a source term step based on rule $\text{REP}_{m,s}$ there is exactly one core step and for any such core step exactly one source term step is emulated. $\square$

Based on this Lemma we prove operational soundness, by showing that each target term is part of an emulation of some source term step.

Lemma 33 (Operational Soundness). *The encodings $\llbracket \cdot \rrbracket_a^s$ and $\llbracket \cdot \rrbracket_a^m$ fulfil operational soundness.*

Proof. We start with $\llbracket \cdot \rrbracket_a^s$. By Definition 9, we have to show that:

$$\forall S \in \mathcal{P}_s . \forall T \in \mathcal{P}_a . \llbracket S \rrbracket_a^s \Longrightarrow T \text{ implies } \exists S' \in \mathcal{P}_s . \exists T' \in \mathcal{P}_a . S \Longrightarrow S' \wedge T \Longrightarrow T' \wedge T' \cong_a^s \llbracket S' \rrbracket_a^s$$

Note that T is a target term, i.e., $T \in \mathcal{P}_{al} \llbracket \cdot \rrbracket_a^s$. By Lemma 18, pure administrative steps do not influence the state of a target term modulo $\cong_a^s$, i.e., $\forall T, T' \in \mathcal{P}_{al} \llbracket \cdot \rrbracket_a^s . T \Longrightarrow T' \text{ implies } T \cong_a^s T'$. Because of that, it suffice to consider impure administrative and core steps, i.e., steps on translated source term names or sum locks. Moreover note, that steps on negative instantiations of sum locks reduce the corresponding test-statements to simple forwarders, that immediately restore the information consumed to resolve this test-statement. Thus impure administrative steps on negative instantiations of sum locks do not change the state of a target term modulo $\cong_a^s$.

By Lemma 32, core steps indicate the border between the encoding of one source term and the encoding of its reduction. While, pure administrative steps do not influence the state of a source term modulo $\cong_a^s$, the core steps do. Core steps finally rule out each way to reach one of the consumed translated observables and all translated observables connected to the same sums. With that, they also rule out each emulation of conflicting source term steps and accordingly the reachability of the corresponding translated observables and occurrences of $\checkmark$. On the other hand, since all post-processing steps of all emulations are pure administrative steps, they ensure that eventually the respective encoded continuations are unguarded. Because of that immediately after the core step all translated observables and all reachable occurrences of $\checkmark$ of the encoded continuations are reachable. Because of that, source term steps and their emulations handle source term observables and their translated observables in exactly the same way, i.e., they remove old and unguard new in the same way. So, if we consider only pure administrative steps and a single core step, i.e., the sequence $\llbracket S \rrbracket_a^s \Longrightarrow T \xrightarrow{\text{core}} T' \Longrightarrow T''$ for a source term $S \in \mathcal{P}_s$, then each target term in the sequence $\llbracket S \rrbracket_a^s \Longrightarrow T$, including T , is congruent to $\llbracket S \rrbracket_a^s$ modulo $\cong_a^s$ and each target term in the sequence $T' \Longrightarrow T''$, including T' , is congruent to T'' modulo $\cong_a^s$. By Lemma 32, the step $T \xrightarrow{\text{core}} T'$ marks the emulation of a source term step. Thus, S must be able to perform a step, i.e., $\exists S' \in \mathcal{P}_s$ such that $S \Longrightarrow S'$, and the sequence $\llbracket S \rrbracket_a^s \Longrightarrow T \xrightarrow{\text{core}} T' \Longrightarrow T''$ emulates this step by unguarding the encodings of the subterms of S' and removing the translated observables that refer to the observables removed from S during the step to S' . Moreover, note that, since all post-processing steps are pure administrative steps, it is always possible to complete the emulation after the core step. Thus $\exists T''' \in \mathcal{P}_a$ such that T''' is the result of the completion of the emulation of $S \Longrightarrow S'$, i.e., $T' \Longrightarrow T'''$ and $T''' \cong_a^s \llbracket S' \rrbracket_a^s$.

Unfortunately, impure administrative steps complicate the situation. As described in Example 1 they can already rule out some emulations on conflicting source term steps by disabling the reachability of some translated observables (e.g. by consuming their respective positive instantiations of sum locks). If they rule out all emulations on conflicting source term steps, then they behave like core steps and we are back to the situation described above. But, if they only rule out some emulations on conflicting source term steps, we result in what we denote as intermediate state (compare to Definition 23). Intermediate states are in general not congruent to any of the surrounding encoded source terms modulo $\cong_a^s$; neither to the encoded source term there we start our emulation attempt nor to any encoding of the possible reductions. Note that the Definition 9 of operational soundness explicitly allows for the presence of such intermediate states as long as we can ensure, that from each intermediate state a state, that is congruent modulo $\cong_a^s$ to an encoded source term, is reachable. So let us have a closer look on these impure administrative steps. By Definition 24, impure administrative steps are steps on translated source term names or on sum locks. They prepare an emulation by unguarding and/or partially reducing a test-statement. Since for all sum locks eventually an instantiation is restored, each of these test-statements is eventually resolved (compare to the proof in [Nes00] that the encoding $\llbracket \cdot \rrbracket_a^s$ does not introduce deadlock).

So let us consider a sequence $\llbracket S \rrbracket_a^s \Longrightarrow T \xrightarrow{\text{core}} T' \Longrightarrow T''$. If the core step $T \xrightarrow{\text{core}} T'$ rules out any emulation attempt except for the one it steers to the point of no return, then we can use the same argumentation as in the case without impure administrative steps to show that $\exists S' \in \mathcal{P}_s$ and $\exists T''' \in \mathcal{P}_a$ such that $S \Longrightarrow S'$, $T' \Longrightarrow T'''$, i.e., $T \Longrightarrow T'''$, and $T''' \cong_a^s \llbracket S' \rrbracket_a^s$.

However, by performing several impure administrative steps in $\llbracket S \rrbracket_a^s \mapsto T$, several emulations can be started by unguarding and/or partially reducing test-statements before a single of them is resolved. In this case, the resolution of one of these test-statements may not directly lead to a term congruent modulo $\cong_a^s$ to an encoded source term. This can happen, if the source term can perform several sets of conflicting steps, i.e., there are at least two non conflicting but parallel steps and for each of these steps there can be some conflicting alternatives. To reach again a term, that is congruent modulo $\cong_a^s$ to an encoded source term, T has to finally decide on which of the started emulations are completed and rule out all conflicting emulations. Note that, therefore in general it is not necessary to resolve all unguarded or partially reduced test-statements. However, since the $\llbracket \cdot \rrbracket_a^s$ does not introduce deadlock, all unguarded and partially reduced test-statements in T can be resolved, which definitely completes some of the started emulations by core steps and rules out the completion of any remaining started emulation⁶. Thus $\exists T' \in \mathcal{P}_a$ such that T' is the target term that is reached after all unguarded or started test-statements of T are resolved and all necessary post-processing steps to complete the respective emulations are performed, i.e., $T \mapsto T'$. Then for each core step in the sequence $T \mapsto T'$ there is one source term step of S or a reduction of S . Note that in $\llbracket S \rrbracket_a^s \mapsto T$ several emulations are started, but, since there are no core steps, none of these emulations is completed. So S must be able to perform all source term step, that correspond to an emulation completed in $T \mapsto T'$, in parallel. Because of that, we can split up S into n parallel subterms $S_1, \dots, S_n$, where n is the number of emulations completed in $T \mapsto T'$. Then we can prove the lemma for the subterms using the cases above, i.e., we have $\llbracket S_i \rrbracket_a^s \mapsto T_i$ implies $\exists S'_i \in \mathcal{P}_s$ and $\exists T'_i \in \mathcal{P}_a$ such that $S_i \mapsto S'_i$, $T_i \mapsto T'_i$, and $T'_i \cong_a^s \llbracket S'_i \rrbracket_a^s$. Since S can perform all these source term steps in parallel, it can also perform them arbitrarily ordered in a sequence, i.e., $\exists S' \in \mathcal{P}_s$ such that $S \mapsto S'$ and S' is structural congruent to the parallel composition of the reductions $S'_1, \dots, S'_n$. Then we use an argumentation similar to the case of the PAR rule in the proof of Lemma 30 to conclude that $\exists T' \in \mathcal{P}_a$ such that $T \mapsto T'$ and $T'_i \cong_a^s \llbracket S'_i \rrbracket_a^s$ for all i with $1 \leq i \leq n$ implies $T' \cong_a^s \llbracket S' \rrbracket_a^s$.

Finally, let us consider an arbitrary sequence $\llbracket S \rrbracket_a^s \mapsto T$, which may even include core steps. Note that, in opposite two the cases before, this sequence covers the case there already some emulations are completed while for other emulations—possibly of parallel source term steps—up to now only test-statements are unguarded and/or partially reduced. However, revisiting the argumentation of the case before, $\exists T' \in \mathcal{P}_a$ such that $T \mapsto T'$ and T' is the result from resolving all unguarded and partially reduced test-statements in T and performing all post-processing steps necessary to complete all emulations in $\llbracket S \rrbracket_a^s \mapsto T \mapsto T'$, that are already driven beyond their point of no return by the respective core step. By concentrating again only on the impure administrative and core steps—and ignoring impure administrative steps that do not lead to a completed emulation in $\llbracket S \rrbracket_a^s \mapsto T'$ —we can split up this sequence into subsequences of subsequent bundles of completed emulations, such that each such bundle can not be further subdivided into such bundles. Then, if necessary, we split up these bundles into the parallel branches of the corresponding source terms as in the case before. Repeating this, we result in a tree of completed emulation of subsequently and parallel source term steps, where for each parallel source term step there is a branch in the respective subtree. Now each line between a parent and its direct child node within this tree represents one of the above considered cases. So we can conclude the proof by an induction over this tree. Thus, $\exists S' \in \mathcal{P}_s$ such that $S \mapsto S'$ and $T \cong_a^s \llbracket S' \rrbracket_a^s$.

The argumentation for $\llbracket \cdot \rrbracket_a^m$ is similar to the argumentation for $\llbracket \cdot \rrbracket_a^s$ above. Of course, the Lemmata 18 and 30 have to be replaced in the argumentation by 19 and 31, respectively. Moreover note, that the combination of the Lemmata 11, 12, and 32 proves that $\llbracket \cdot \rrbracket_a^m$ does not introduce deadlock. Finally, in $\llbracket \cdot \rrbracket_a^m$ there are no steps on translated source term names, so there are less impure administrative steps. $\square$

Lemma 34 (Divergence Reflection). *The encoding $\llbracket \cdot \rrbracket_a^s$ reflects divergence.*

Proof. By Lemma 32, emulations and core steps corresponds. Because of that, an infinite sequence $\llbracket S \rrbracket_a^s \mapsto^\omega$ with infinite many core steps implies that infinitely many source term steps are emulated, i.e., that $S \mapsto^\omega$. Because of that, it suffice to show that each sequence $T \mapsto T'$ on target terms $T, T' \in \mathcal{P}_a[\llbracket \cdot \rrbracket_a^s]$ between two core steps is finite. The argumentation for the sequence of administrative steps $\llbracket S \rrbracket_a^s \mapsto T'$ before the first core step and for the sequence of administrative steps after the last core step—in case of a terminating process—is then similar.

⁶ Note that the completion of emulations, that are up to now only started by performing some pure administrative steps, possibly might not be ruled out by resolving these test-statements. However, since pure administrative steps do not influence the state of a target term modulo $\cong_a^s$, such emulations can be ignored.

A look at the definition of the corresponding renaming policy in Figure 3 suggests the following case split⁷ on the links of the steps in $T \dot{\Rightarrow} T'$.

Case of s : The name s is used by the encoding function to denote sender locks. By Definition 17, sender locks are channels of multiplicity one, that are used as input but not as replicated input channels and within the continuation of such an input there is no unguarded and unrestricted instantiation of a sum lock. Their purpose is to guard the encoded continuations within the encoding of output guarded source terms. Since we consider only terms with finite representation, there are only finitely many unguarded instantiations on sender locks in T . Analysing the encoding function in Figure 4 we observe, that new instantiations on sender locks appear only in the then-case of the (nested) test-statement in the encoding of input guarded source terms and in the encoding of a replicated input. Because of that, new instantiations on sender locks can be unguarded only by a core step followed by a pure administrative step to reduce the test-statement to the then-case. Some of these core steps may have happened before T , but of course only finitely many. So within the sequence $T \dot{\Rightarrow} T'$ only finitely many new instantiations on sender locks can be unguarded. We conclude that within the sequence $T \dot{\Rightarrow} T'$ there are only finitely many steps on sender locks.

Note that the encoded continuation of input guarded source terms or a replicated input appears in parallel to such an instantiation of a sender lock within the then-case of a (nested) test-statement. Because of that, within the sequence $T \dot{\Rightarrow} T'$ only finitely many encoded source terms, i.e., continuations, can be unguarded.

Case of Outputs on Translated Source Term Names: Since we consider only terms with finite representations, there are only finitely many unguarded outputs on translated source term names in T . Analysing the encoding function in Figure 3 we observe that there are only two ways to unguard a new output on a translated source term name. First, they can be unguarded by unguarding an encoded source term as continuation of an emulation. By the case before, within the sequence $T \dot{\Rightarrow} T'$ only finitely many encoded source terms can be unguarded, so there can only finitely many new outputs on translated source term names can be unguarded that way. Second, in the else-case of the first test-statement in the encoding of an input guarded source term there is such an unguarded output. To unguard this test-statement an instantiation of a receiver lock is consumed, but no new is unguarded by the else-case of the first test-statement. Analysing the encoding function we observe that all receiver locks are generated under restriction and initially there is exactly one instantiation of each receiver lock. Moreover, receiver locks are never transmitted over these restriction and to unguard a new instantiation (in the else-case of the second test-statement) a former instantiation of that receiver lock has to be consumed. Because of that, in each target term there is at most one instantiation of each receiver lock. Thus, reducing the nested test-statement to the else-case of the first test-statements, prevents any further unguarding of this test-statement. Since in T there are only finitely many different guarded or unguarded replicated inputs on receiver locks guarding such a nested test-statement, it is not possible to unguard initially many new outputs on translated source term names that way. We conclude that within the sequence $T \dot{\Rightarrow} T'$ only finitely many outputs on translated source term names can be unguarded.

Case of r : The name r is used by $\llbracket \cdot \rrbracket_a^s$ to introduce receiver locks. Since we consider only terms with finite representations, there are only finitely many unguarded instantiations on receiver locks in T . Analysing the encoding in Figure 3 we observe that there are only two ways to unguard new instantiations on receiver locks. First, they can be unguarded by unguarding an encoded source term as continuation of an emulation. By the first case, within the sequence $T \dot{\Rightarrow} T'$ only finitely many encoded source terms can be unguarded, so there can only finitely many new instantiations on receiver locks be unguarded that way. Second, in the else-case of the second test-statement in the encoding of an input guarded source term there is such an unguarded instantiation on a receiver lock. However, to unguard such a nested test-statement an output on a translated source term name has to be consumed. Since by the case before there are only finitely many such outputs, there is no possibility to unguard infinity many instantiations on receiver lock this way. We conclude that within the sequence $T \dot{\Rightarrow} T'$ there are only finitely many steps on receiver locks.

Note that in T there are only finitely many unguarded test-statements and new test-statements can only be unguarded by unguarding an encoded source term or by a step on a receiver lock. Thus, since by the first two cases only finitely many encoded source terms can be unguarded and by the current case there are only finitely many steps on receiver locks, within the sequence $T \dot{\Rightarrow} T'$ only finitely many new test-statements can be unguarded.

⁷ Note that in most cases the considered names are restricted, so a simple alpha conversion may change them. Because of that, as already in the proof of Lemma 9, the use of concrete names in the following case split should not imply that we consider steps on these specific names. Instead the names refer to the meaning which is related to them by the encoding function.

Case of Inputs on Translated Source Term Names: Since we consider only terms with finite representations, there are only finitely many unguarded inputs on translated source term names in T . New inputs on source terms names can only be unguarded by a step on a receiver lock. Since by the case before the number of steps on receiver locks is finite, within the sequence $T \Rightarrow T'$ only finitely many inputs on translated source term names can be unguarded. Moreover, since by the second case the number of outputs on translated source term names is finite as well, there are only finitely many steps on translated source term names within the sequence $T \Rightarrow T'$.

Case of l, l' : Both names are used by the encoding function to refer to sum locks. The only steps on sum locks are to reduce a test-statement. Note that in case of a nested test-statement two sum locks are reduced, i.e., there are two steps on sum locks. However, since by the third case there are only finitely many test-statements, within the sequence $T \Rightarrow T'$ there are only finitely many steps on sum locks.

Case of t, f : t and f are used by the encoding function to implement booleans. As in the case of sum locks, all steps on these names are used to reduce a test-statement. So again, since there are only finitely many test-statements, within the sequence $T \Rightarrow T'$ there are only finitely many steps on t and f .

□

Lemma 35 (Divergence Reflection). *The encoding $\llbracket \cdot \rrbracket_a^m$ reflects divergence.*

Proof. By Lemma 32, emulations and core steps corresponds. Because of that, an infinite sequence of target term steps $\llbracket S \rrbracket_a^m \mapsto^\omega$ with infinite many core steps implies that infinitely many source term steps are emulated, i.e., that $S \mapsto^\omega$. Because of that, it suffice to show that each sequence $T \Rightarrow T'$ on target terms $T, T' \in \mathcal{P}_{al} \llbracket \cdot \rrbracket_a^m$ between two core steps is finite. The argumentation for the sequence of administrative steps $\llbracket S \rrbracket_a^m \Rightarrow T'$ before the first core step and for the sequence of administrative steps after the last core step—in case of a terminating process—is then similar.

Since source term names are translated into values, never used as links, it suffice to consider steps on names introduced by the encoding function. A look at the definition of the corresponding renaming policy in Figure 4 suggests the following case split⁸ on the links of the steps in $T \Rightarrow T'$.

Case of s : The name s is used by the encoding function to denote sender locks. By Definition 17, sender locks are carried as third value of output requests. Their purpose is to guard the encoded continuations within the encoding of output guarded source terms. Since we consider only terms with finite representation, there are only finitely many unguarded instantiations on sender locks in T . Analysing the encoding function in Figure 4 we observe, that new instantiations on sender locks appear only in the then-case of the (nested) test-statement in the encoding of input guarded source terms and in the encoding of a replicated input. Because of that, new instantiations on sender locks can be unguarded only by a core step followed by a pure administrative step to reduce the test-statement to the then-case. Some of these core steps may have happened before T , but of course only finitely many. So within the sequence $T \Rightarrow T'$ only finitely many new instantiations on sender locks can be unguarded. We conclude that within the sequence $T \Rightarrow T'$ there are only finitely many steps on sender locks. Note that the encoded continuation of input guarded source terms appears in parallel to such an instantiation of a sender lock within the then-case of a nested test-statement. Because of that, within the sequence $T \Rightarrow T'$ only finitely many encoded continuations of encodings of input or output guarded source terms can be unguarded.

Case of c_{r1}, c_{r2} : These two names are used to link the encoded continuations of several reductions of the same replicated input within a chain. Note that the first name denotes a chain lock carrying a translated source term name (compare to Definition 20). Again, since we consider only terms with finite representations, there are only finitely many instances, i.e., outputs, on these names. For each step on the chain lock a new output on an instance of c_{r2} is unguarded. So the number of steps on instances of c_{r2} is bounded by the number of steps on chain lock carrying a translated source term name. New instantiations of such chain locks are unguarded as instantiations of sender locks only in the then-case of the test-statement in the encoding of a replicated input. Because of that, new instantiations on such chain locks can be unguarded only by a core step followed by a pure administrative step to reduce the test-statement to the then-case. Some of these core steps may have happened before T , but of course only finitely many. So within the sequence $T \Rightarrow T'$ only finitely many new instantiations on such chain locks can be unguarded. We conclude that within the sequence $T \Rightarrow T'$ there are only finitely many steps on such chain locks and instances of c_{r2} .

⁸ Note that in most cases the considered names are restricted, so a simple alpha conversion may change them. Because of that, as already in the proof of Lemma 10, the use of concrete names in the following case split should not imply that we consider steps on these specific names. Instead the names refer to the meaning which is related to them by the encoding function.

Because of that, within the sequence $T \mapsto T'$ only finitely many encoded continuations of encodings of replicated inputs can be unguarded.

Case of $p_o, p_i, p_{o,up}, p_{i,up}, m_o, m_i, m_{o,up}, m_{i,up}, r_i, r_o, r_{i,up}, r_{o,up}$: All these names are request channels, i.e., there are introduced by $\llbracket \cdot \rrbracket_a^m$ to transport requests. Since we consider only terms with finite representations, there are only finitely many unguarded requests in T . Moreover, by the two cases above, only finitely new requests can be unguarded within the sequence $T \mapsto T'$ by unguarding source term encodings. Thus there are only finitely many different unguarded requests within the sequence $T \mapsto T'$. We have already argued that the encoding $\llbracket \cdot \rrbracket_a^m$ puts much effort in restricting the way a request may take. We underpin this fact here, by proving that these ways do not include cycles. Note that inputs on requests channels do only appear within the encoding of the parallel operator or a replicated input (compare to Figure 4).

Let us consider the encoding of a parallel operator first. The terms `procLeftOutReq` and `procLeftInReq` transmit all requests of the left side of a parallel operator encoding to the right side and upwards over the restriction on the request channels. In `procRightOutReq` and `procRightInReq` the requests of the right side of the parallel operator encoding are linked in two chains, one for input and one for output requests. Therefore the requests of the right side are consumed, but a single copy of them is pushed upwards over the restriction on the request channels again. Then all left requests can be received by the respective first member of the chain of requests of opposite kind to the left request. Within these first members all left requests are consumed to combine them with the respective request behind this member and a copy of this left requests is further pushed along the chain. Now each member of that chain subsequently receives the left requests from its predecessor and sends a copy to its successor. Since the chains have no cycles and can not be infinitely long, each left request is only finitely often transmitted within each of these chains. In `pushReq` for each left and right requests, that was pushed over the restriction on request channels at the left and right side of a parallel operator, a single copy either under the restriction of a surrounding parallel operator encoding or on free source term names is generated. Note that the requests on free source term names can never be consumed. Moreover, for each parallel operator encoding there is a parallel operator in the corresponding source term. Thus the parallel operator encodings cause the structure of a finite binary tree, i.e., there are only finitely many instances of the terms `procLeftOutReq`, `procLeftInReq`, `procRightOutReq`, `procRightInReq`, and `pushReq`. Note that because of the two first cases only finitely many new encodings of parallel operators can be unguarded. Because of that and since a tree is free of cycles, within the sequence $T \mapsto T'$ there are only finitely many steps on requests, that are induced by a parallel operator encoding.

In the last case we prove, that only within $T \mapsto T'$ only finitely many encoded continuations of encodings of replicated inputs can be unguarded. Because of that, there are only finitely many instances of `encodedContinuations`. Within each of these instances all requests originate from the respective replicated input or a more left instance of `encodedContinuations` of the same replicated input encoding are copied twice by `pushReqIn`; one copy is generated under a restriction of this instance of `encodedContinuations` to be combined with the requests within this branch and one copy is prepared to be transmitted to the respective next right branch of that encoded replicated input. All these first copies are proceed by `procRightOutReq` and `procRightInReq` as a request of the left side of a parallel operator encoding, while each requests of the respective encoded continuation is proceed by these terms as a right request. For each such right request in `pushReqOut` a single copy is generated and the restriction of the surrounding parallel operator encoding. Moreover for each such left and each such right request a single copy is generated under the binding of the `encodedContinuations`, that is the next one in the chain. Since again there are no cycles, there are only finitely many steps on requests, that are induced by a `encodedContinuations`. We conclude, that within the sequence $T \mapsto T'$ there are only finitely many steps on requests.

Case of c_o, c_i : These names implement chain locks carrying a request channel. They are used to allow for a new request at the right side of a parallel operator encoding to be linked in the corresponding chain. By the third case there are only finitely many such right requests and chains, so within the sequence $T \mapsto T'$ there are only finitely many steps on such chain locks.

Case of r : The name r is used by $\llbracket \cdot \rrbracket_a^m$ to introduce receiver locks. Since we consider only terms with finite representations, there are only finitely many unguarded instantiations on receiver locks in T . Anything the encoding in Figure 4 we observe that new instantiations on receiver locks are only unguarded due to a matching pair of requests. By the third case, there are only finitely many different requests and steps on request channels within the sequence $T \mapsto T'$. Moreover we observe that no request is ever combined with itself and no pair is combined twice. Because of that, within the sequence $T \mapsto T'$ only finitely many new instantiations on receiver locks can be unguarded, i.e., there are only finitely many steps on receiver locks.

Note that in T there are only finitely many unguarded test-statements and new test-statements can only be unguarded by unguarding an encoded source term or by a step on a receiver lock. Thus, since by the first

two cases only finitely many encoded source terms can be unguarded and by the current case there are only finitely many steps on receiver locks, within the sequence $T \xRightarrow{\vdash} T'$ only finitely many new test-statements can be unguarded.

Case of l, l_s, l_r, l_1, l_2 : All these names are used by the encoding function to refer to sum locks. The only steps on sum locks are to reduce a test-statement. Note that in case of a nested test-statement two sum locks are reduced, i.e., there are two steps on sum locks. However, since by the case before there are only finitely many test-statements, within the sequence $T \xRightarrow{\vdash} T'$ there are only finitely many steps on sum locks.

Case of t, f : t and f are used by the encoding function to implement booleans. As in the case of sum locks, all steps on these names are used to reduce a test-statement. So again, since there are only finitely many test-statements, within the sequence $T \xRightarrow{\vdash} T'$ there are only finitely many steps on t and f .

Case of y, y', z : These names are used by the encoding function as values only, but never as links. So there are no (administrative) steps on these names.

□

Lemma 36 (Success Sensitiveness). *The encodings $\llbracket \cdot \rrbracket_a^s$ and $\llbracket \cdot \rrbracket_a^m$ are success sensitive.*

Proof. We start with $\llbracket \cdot \rrbracket_a^s$. By Definition 12, we have to show that $\forall S \in \mathcal{P}_s. S \Downarrow_\checkmark$ iff $\llbracket S \rrbracket_a^s \Downarrow_\checkmark$. Let $S \in \mathcal{P}_s$ be an arbitrary source term. We prove both directions separately.

Case of $S \Downarrow_\checkmark$ implies $\llbracket S \rrbracket_a^s \Downarrow_\checkmark$: By Definition 11, $S \Downarrow_\checkmark$ implies that there are some $S', S'' \in \mathcal{P}_s$ such that $S \xRightarrow{\vdash} S'$ and $S' \equiv S'' \mid \checkmark$. By operational completeness (Lemma 30), the sequence $S \xRightarrow{\vdash} S'$ can be emulated by $\llbracket S \rrbracket_a^s$, i.e., there exists some $T \in \mathcal{P}_a \llbracket \cdot \rrbracket_a^s$ such that $\llbracket S \rrbracket_a^s \xRightarrow{\vdash} T$ and $T \cong_a^s \llbracket S' \rrbracket_a^s$. By Figure 3, $\llbracket S'' \mid \checkmark \rrbracket_a^s = \llbracket S'' \rrbracket_a^s \mid \checkmark$. Thus $\llbracket S'' \mid \checkmark \rrbracket_a^s \Downarrow_\checkmark$. Since by Lemma 20 the encoding $\llbracket \cdot \rrbracket_a^s$ preserves structural congruence of source terms modulo $\cong_a^s$, $S' \equiv S'' \mid \checkmark$ implies $\llbracket S' \rrbracket_a^s \cong_a^s \llbracket S'' \mid \checkmark \rrbracket_a^s$. By Definition 28, then for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket 0 \rrbracket_a^s) \in \mathcal{P}_a \llbracket \cdot \rrbracket_a^s$ we have $\mathcal{C}(\llbracket S' \rrbracket_a^s) \approx_a^s \mathcal{C}(\llbracket S'' \mid \checkmark \rrbracket_a^s)$. Then, by the first condition of Definition 26, $\mathcal{C}(\llbracket S' \rrbracket_a^s) \Downarrow_\checkmark$ iff $\mathcal{C}(\llbracket S'' \mid \checkmark \rrbracket_a^s) \Downarrow_\checkmark$ for all such contexts $\mathcal{C}$. Thus $\llbracket S'' \mid \checkmark \rrbracket_a^s \Downarrow_\checkmark$ implies $\llbracket S' \rrbracket_a^s \Downarrow_\checkmark$. By the same argumentation we conclude that $\llbracket S' \rrbracket_a^s \Downarrow_\checkmark$ implies $T \Downarrow_\checkmark$. Since $\llbracket S \rrbracket_a^s \xRightarrow{\vdash} T$, we conclude $\llbracket S \rrbracket_a^s \Downarrow_\checkmark$.

Case of $\llbracket S \rrbracket_a^s \Downarrow_\checkmark$ implies $S \Downarrow_\checkmark$: By Definition 11, $\llbracket S \rrbracket_a^s \Downarrow_\checkmark$ implies that either there is an unguarded occurrence of $\checkmark$ in $\llbracket S \rrbracket_a^s$ or there are some $T, T' \in \mathcal{P}_a$ such that $\llbracket S \rrbracket_a^s \xRightarrow{\vdash} T$ and $T \equiv T' \mid \checkmark$. In the first case, since the only way to obtain an occurrence of success in a target term is by $\llbracket \checkmark \rrbracket_a^s = \checkmark$, we conclude that there is an unguarded occurrence of success in $\llbracket S \rrbracket_a^s$. In the other case, by operational soundness (Lemma 33), then there are some $S' \in \mathcal{P}_s$ and $T' \in \mathcal{P}_a$ such that $S \xRightarrow{\vdash} S'$, $T \xRightarrow{\vdash} T'$, and $T' \cong_a^s \llbracket S' \rrbracket_a^s$. Since $T \Downarrow_\checkmark$ and $\checkmark$ can not be reduced, we have $T' \Downarrow_\checkmark$. By Definition 28, $T' \cong_a^s \llbracket S' \rrbracket_a^s$ implies $\mathcal{C}(T') \approx_a^s \mathcal{C}(\llbracket S' \rrbracket_a^s)$ for all contexts $\mathcal{C}([\cdot]) \in \mathcal{P}_a \rightarrow \mathcal{P}_a$ such that $\mathcal{C}(\llbracket 0 \rrbracket_a^s) \in \mathcal{P}_a \llbracket \cdot \rrbracket_a^s$. By the first condition of Definition 26, $\mathcal{C}(T) \Downarrow_\checkmark$ iff $\mathcal{C}(\llbracket S' \rrbracket_a^s) \Downarrow_\checkmark$ for all such contexts $\mathcal{C}$. Thus $T' \Downarrow_\checkmark$ implies $\llbracket S' \rrbracket_a^s \Downarrow_\checkmark$. Moreover, since T' includes an unguarded occurrence of success and since all occurrences of $\checkmark$ in target terms are due to the encoding $\llbracket \checkmark \rrbracket_a^s = \checkmark$, the sequence $\llbracket S \rrbracket_a^s \xRightarrow{\vdash} T'$ emulates a sequence $S \xRightarrow{\vdash} S'$ of target terms unguarding an occurrence of $\checkmark$. So S' has an unguarded occurrence of $\checkmark$, i.e., $S' \Downarrow_\checkmark$. We conclude $S \Downarrow_\checkmark$.

The argumentation in case of $\llbracket \cdot \rrbracket_a^m$ is similar to the argumentation of $\llbracket \cdot \rrbracket_a^s$ above. For the first case note that, by Figure 4, the parallel operator is not translated rigidly but since $\llbracket \checkmark \rrbracket_a^m = \checkmark$ and the encodings of the parameters of a parallel operator appear unguarded within the encoding of the parallel operator, the unguarded occurrence of $\checkmark$ in $S'' \mid \checkmark$ implies that there is an unguarded occurrence of $\checkmark$ in $\llbracket S'' \mid \checkmark \rrbracket_a^m$. □

Theorem 1. *The encodings $\llbracket \cdot \rrbracket_a^s$ and $\llbracket \cdot \rrbracket_a^m$ are good.*

Proof. By Figure 3 and Figure 4, both encodings are compositional. Name invariance is proved in the Lemmata 1 and 2. Operational correspondence follows by the Lemmata 30, 31, and 33. Lemma 34 proves that $\llbracket \cdot \rrbracket_a^s$ do not introduce divergence, while Lemma 35 proves the same condition for $\llbracket \cdot \rrbracket_a^m$. Finally, by Lemma 36, both encodings are success sensitive. Thus both encodings are good with respect to the five criteria introduced by Gorla. □

3 Degree of Distribution

In the following we prove that $\llbracket \cdot \rrbracket_a^s$ preserves the degree of distribution of its source terms, while $\llbracket \cdot \rrbracket_a^m$ does not. For a definition what it means to preserve the degree of distribution have a look at Definition 5 in [PN12]. Moreover, we present an encoding function from π_m (without replicated input) into π_a^2 , the asynchronous π -calculus augmented with a two-level polyadic synchronisation.

Note that for simplicity we omit in Figure 1 a structural congruence rule for replicated input. However, of course a replicated input represents a not determined number of instances of the corresponding input guarded term in parallel. In order to allow for the distribution of replicated inputs, we augment structural congruence by an additional rule, i.e., $\equiv^*$ is structural congruence $\equiv$ augmented with the additional rule $y^*(x).P \equiv^* y^*(x).P \mid y^*(x).P$ to split up replicated inputs.

Lemma 37. *The encoding $\llbracket \cdot \rrbracket_a^s$ preserves the degree of distribution.*

Proof. Let $S, S_1, \dots, S_n, S'_1, \dots, S'_n \in \mathcal{P}_s$ such that $S \equiv^* S_1 \mid \dots \mid S_n$ and $S_i \Longrightarrow S'_i$ for all i with $1 \leq i \leq n$. Then, by Definition 5 in [PN12], we have to show that:

$$\exists T_1, \dots, T_n \in \mathcal{P}_a. \exists \mathcal{C}([\cdot]_1, \dots, [\cdot]_n) \in \mathcal{P}_a^n \rightarrow \mathcal{P}_a. \llbracket S \rrbracket_a^s \equiv^* \mathcal{C}(T_1, \dots, T_n) \wedge (\forall i \in [1, \dots, n]. T_i \Longrightarrow_a^s \llbracket S'_i \rrbracket_a^s)$$

Revisiting the argumentation in the proof of Lemma 20, the encoding $\llbracket \cdot \rrbracket_a^s$ preserves structural congruence of source terms except for the rule $P \mid \mathbf{0} \equiv P$, because it translates restriction, the parallel operator, and the match operator rigidly. Moreover, because of the rigid translation of the parallel operator, even the additional rule $y^*(x).P \equiv^* y^*(x).P \mid y^*(x).P$ is preserved. Thus $S \equiv^* S_1 \mid \dots \mid S_n$ implies $\llbracket S \rrbracket_a^s \equiv^* \llbracket S_1 \mid \dots \mid S_n \rrbracket_a^s = \llbracket S_1 \rrbracket_a^s \mid \dots \mid \llbracket S_n \rrbracket_a^s$, i.e., we can choose $T_i = \llbracket S_i \rrbracket_a^s$ for all i with $1 \leq i \leq n$ and $\mathcal{C}([\cdot]_1, \dots, [\cdot]_n) = [\cdot]_1 \mid \dots \mid [\cdot]_n$. By operational completeness (compare to Lemma 30), then $S_i \Longrightarrow S'_i$ implies $\llbracket S_i \rrbracket_a^s \Longrightarrow_a^s \llbracket S'_i \rrbracket_a^s$ for all i with $1 \leq i \leq n$, i.e., $T_i \Longrightarrow_a^s \llbracket S'_i \rrbracket_a^s$. $\square$

Lemma 38. *Any good encoding, that translates the parallel operator rigidly and preserves enough of the structural congruence on source terms to ensure that $S \equiv_1 S_1 \mid \dots \mid S_n$ implies $\llbracket S \rrbracket \equiv_2 \llbracket S_1 \mid \dots \mid S_n \rrbracket$, preserves the degree of distribution.*

Proof. Let $S, S_1, \dots, S_n, S'_1, \dots, S'_n$ be terms of the source language such that $S \equiv_1 S_1 \mid \dots \mid S_n$ and $S_i \Longrightarrow S'_i$ for all i with $1 \leq i \leq n$. Then, by Definition 5 in [PN12], we have to show that:

$$\exists T_1, \dots, T_n \in \mathcal{P}_a. \exists \mathcal{C}([\cdot]_1, \dots, [\cdot]_n) \in \mathcal{P}_a^n \rightarrow \mathcal{P}_a. \llbracket S \rrbracket \equiv_2 \mathcal{C}(T_1, \dots, T_n) \wedge (\forall i \in [1, \dots, n]. T_i \Longrightarrow \times \llbracket S'_i \rrbracket)$$

Since the encoding translates the parallel operator rigidly and preserves enough of the structural congruence on source terms to ensure that $S \equiv_1 S_1 \mid \dots \mid S_n$ implies $\llbracket S \rrbracket \equiv_2 \llbracket S_1 \mid \dots \mid S_n \rrbracket$, we have $\llbracket S \rrbracket \equiv_2 \llbracket S_1 \mid \dots \mid S_n \rrbracket = \llbracket S_1 \rrbracket \mid \dots \mid \llbracket S_n \rrbracket$, i.e., we can choose $T_i = \llbracket S_i \rrbracket$ for all i with $1 \leq i \leq n$ and $\mathcal{C}([\cdot]_1, \dots, [\cdot]_n) = [\cdot]_1 \mid \dots \mid [\cdot]_n$. By operational completeness (compare to Definition 9), then $S_i \Longrightarrow S'_i$ implies $\llbracket S_i \rrbracket \Longrightarrow_a^s \llbracket S'_i \rrbracket$ for all i with $1 \leq i \leq n$, i.e., $T_i \Longrightarrow \times \llbracket S'_i \rrbracket$. $\square$

Lemma 39. *The encoding $\llbracket \cdot \rrbracket_a^m$ does not preserve the degree of distribution.*

Proof. Consider the counter example $S = (\bar{a} \mid \bar{b}) \mid (a \mid b)$. S can perform two different reductions, which are independent of each other. So $S \equiv S_1 \mid S_2$ with $S_1 = (\bar{a} \mid a)$ and $S_2 = (\bar{b} \mid b)$ such that $S_1 \mapsto \mathbf{0}$ and $S_2 \mapsto \mathbf{0}$. Of course, since $\llbracket \cdot \rrbracket_a^m$ is good, $\llbracket S \rrbracket_a^m$ can emulate both steps in either order. But it can not emulate both truly in parallel.

To prove this fact, let us assume the contrary, i.e., let us assume the encoding $\llbracket \cdot \rrbracket_a^m$ preserves the degree of distribution of S . Then, by Definition 5 in [PN12], we have:

$$\exists T_1, T_2 \in \mathcal{P}_a. \exists \mathcal{C}([\cdot]_1, [\cdot]_2) \in \mathcal{P}_a \times \mathcal{P}_a \rightarrow \mathcal{P}_a. \llbracket S \rrbracket_a^m \equiv^* \mathcal{C}(T_1, T_2) \wedge T_1 \Longrightarrow_a^m \llbracket S'_1 \rrbracket_a^m \wedge T_2 \Longrightarrow_a^m \llbracket S'_2 \rrbracket_a^m$$

The encoding of S is given by:

$$\begin{aligned} \llbracket S \rrbracket_a^m = & (\nu m_o, m_i, p_o, up, p_i, up, c_o, c_i, m_o, up, m_i, up) (\\ & (\nu p_o, p_i) \left(\llbracket \bar{a} \mid \bar{b} \rrbracket_a^m \mid \text{procLeftOutReq} \mid \text{procLeftInReq} \right) \\ & \mid (\nu p_o, p_i) \left(\llbracket a \mid b \rrbracket_a^m \mid \text{procRightOutReq} \mid \text{procRightInReq} \right) \\ & \mid \text{pushReq}) \end{aligned}$$

We observe that for both source term steps their emulations require that the corresponding requests are combined at the outermost parallel operator encoding, i.e., the one given above. Moreover, in both emulations the output

requests arrive at the left and the input requests arrive at the right side of this parallel operator encoding. Thus, for both emulations the requests are proceed by `procRightInReq`.

$$\begin{aligned} \text{procRightInReq} = & \overline{c_i} \langle m_o \rangle \mid c_i^* (m_o) . p_i (y, l_r, r) . (\\ & (\nu m_{o,up}) (m_o^* (y', l_s, s, z) . ([y' = y] \overline{r} \langle l_s, l_r, l_s, s, z \rangle \mid \overline{m_{o,up}} \langle y', l_s, s, z \rangle) \\ & \mid (\nu m_o) (m_{o,up} \rightarrow m_o \mid \overline{c_i} \langle m_o \rangle)) \\ & \mid \overline{p_{i,up}} \langle y, l_r, r \rangle) \end{aligned}$$

Note that, since $\llbracket \overline{a} \rrbracket_a^m$ and $\llbracket \overline{b} \rrbracket_a^m$ appear unguarded in $\llbracket \overline{a} \mid \overline{b} \rrbracket_a^m$, it is not difficult to distribute $\llbracket \overline{a} \mid \overline{b} \rrbracket_a^m$ over T_1 and T_2 , because the respective context introduced by the corresponding parallel operator encoding is not used within the considered emulations, i.e., they can be proved to be junk. The same holds for $\llbracket a \mid b \rrbracket_a^m$. Moreover, since none of the terms `procLeftInReq`, `procRightOutReq`, and `pushReq` of the outermost parallel operator encoding is of any importance for the considered emulations, it does not matter whether we put them within T_1 or T_2 . Note that for each of the considered emulations it is necessary to transmit one left output request to the right side of the outermost parallel operator encoding by the forwarder in `procLeftOutReq`. However, since this forwarder is guarded by a replicated input we can use the rule $y^*(x).P \equiv^* y(x).P \mid y^*(x).P$ to distribute this forwarder, e.g. by placing $p_o(y, l, s, z) . (\overline{m_o} \langle y, l, s, z \rangle \mid \overline{p_{o,up}} \langle y, l, s, z \rangle)$ within T_1 and the rest of the forwarder within T_2 . The only remaining term to distribute is `procRightInReq`.

Since $T_1 \xRightarrow{m} \llbracket S'_1 \rrbracket_a^m$ and $T_2 \xRightarrow{m} \llbracket S'_2 \rrbracket_a^m$, both T_1 and T_2 need the ability to proceed a request from $\llbracket a \mid b \rrbracket_a^m$. Since the respective right requests are restricted the only possibility to process them is `procRightInReq`. We observe that the main part of `procRightInReq` is guarded by a replicated input and can thus be distributed as `procLeftOutReq` before. But there is only one unguarded instantiation of the corresponding chain lock $\overline{c_i} \langle m_o \rangle$ and without it the remaining term guarded by the replicated input on this chain lock is useless. Because of that `procRightInReq` can not be distributed, i.e., it is not possible to distribute the encoding of S such that $\llbracket S \rrbracket_a^m \equiv^* (\nu \tilde{x})(T_1 \mid T_2)$, $T_1 \xRightarrow{m} \llbracket S'_1 \rrbracket_a^m$, and $T_2 \xRightarrow{m} \llbracket S'_2 \rrbracket_a^m$.

Because of that $\llbracket S \rrbracket_a^m$ can not emulate both source term steps without sequentialising the linking of the respective right requests within the required chain. So $\llbracket S \rrbracket_a^m$ can not completely emulate the independent source terms steps in parallel. $\square$

Lemma 40. *Any good encoding $\llbracket \cdot \rrbracket$ preserves the criterion: For every S such that $S = S_1 \mid \dots \mid S_n$ and $S_i \xRightarrow{} S'_i$ for all i with $1 \leq i \leq n$, there exists $T_1, \dots, T_n$ and a context $\mathcal{C}$ with n holes such that $\llbracket S \rrbracket \equiv_2 \mathcal{C}(T_1, \dots, T_n)$ and $T_i \xRightarrow{} \llbracket S'_i \rrbracket$ for all i with $1 \leq i \leq n$.*

Proof. Assume $n \in \mathbb{N}$ and $S, S_1, \dots, S_n, S'_1, \dots, S'_n$ are terms of the source language such that $S = S_1 \mid \dots \mid S_n$ and $(\forall i \in [1, \dots, n] . S_i \xRightarrow{} S'_i)$. Moreover, for simplicity, let us assume, that $S_1 \mid \dots \mid S_n = (S_1 \mid (\dots (S_{n-1} \mid S_n) \dots))$, but note that the actually orientation of the brackets is not import for the rest of the proof. Let $\mathcal{C}_1([\cdot]_1, [\cdot]_2)$ be the context introduced by the encoding of the parallel operator, i.e., $\llbracket P \mid Q \rrbracket = \mathcal{C}_1(\llbracket P \rrbracket, \llbracket Q \rrbracket)$ for all P, Q in the source language. Then $\llbracket S \rrbracket = \mathcal{C}_1(\llbracket S_1 \rrbracket, \mathcal{C}_1(\dots \mathcal{C}_1(\llbracket S_{n-1} \rrbracket, \llbracket S_n \rrbracket) \dots))$. So we can choose $T_i = \llbracket S_i \rrbracket$ for all $i \in [1, \dots, n]$ and $\mathcal{C}(T_1, \dots, T_n) = \llbracket S \rrbracket$. By operational completeness (compare to Definition 9), then $T_i \xRightarrow{} \llbracket S'_i \rrbracket$ for all i with $1 \leq i \leq n$. $\square$

Theorem 2. *There is no good encoding from π_m into π_a that preserves the degree of distribution.*

Proof. By the Theorem in [PSN11], any good encoding from π_m into π_a introduces additional causal dependencies. Note that in [PSN11] slightly different definitions of π_m and π_a are used, i.e., they use $!P$ instead of replicated input, have no match in the source language, and no τ -prefix. However, revisiting the argumentation on the proof of the Theorem in [PSN11] we observe that these details are not crucial.

A closer look at the definition of additional causal dependencies used in [PSN11] reveals, that they show that any good encoding from π_m into π_a introduces causal dependencies between some emulations of independent source term steps. As already stated in the discussion of [PSN11], because of this causal dependency some emulations of independent source terms steps have to be sequentialised, i.e., the emulations can still be performed in either order and even somehow overlapping but not completely independent. Note that this is exactly what we observe in Lemma 39. Because of that, there is no good encoding from π_m into π_a that preserves the degree of distribution. $\square$

Let π_a^2 be the asynchronous π -culus augmented with poliadic synchronisation on channels composed by up to two names as introduced by [CM03].

Definition 31 (π_a^2). *The set of process terms of the asynchronous π -calculus with two-level poliadic synchronisation, denoted by $\mathcal{P}_{a^2}$, is given by*

$$P ::= \mathbf{0} \mid (\nu n) P \mid P_1 \mid P_2 \mid [a = b] P \mid \bar{y} \langle \tilde{z} \rangle . P \mid y(\tilde{x}) . P \mid y^*(\tilde{x}) . P$$

for some names $n, a, b \in \mathcal{N}$, some finite sequences of names $\tilde{x}, \tilde{z} \subset \mathcal{N}$, and either $y \in \mathcal{N}$ or $y = y_1 \cdot y_2$ for some $y_1, y_2 \in \mathcal{N}$.

$$\begin{aligned} \llbracket P \mid Q \rrbracket_{a^2}^m &\triangleq (\nu p_o, up, p_i, up, i, o) (\\ &(\nu p_o, p_i) (\llbracket P \rrbracket_{a^2}^m \\ &\quad | p_o^*(y, l, s_1, s_2, z) \cdot (\overline{y \cdot o} \langle l, s_1, s_2, z \rangle | \overline{p_o, up} \langle y, l, s_1, s_2, z \rangle) \\ &\quad | p_i^*(y, l, r) \cdot (\overline{y \cdot i} \langle l, r \rangle | \overline{p_i, up} \langle y, l, r \rangle)) \\ &| (\nu p_o, p_i) (\llbracket Q \rrbracket_{a^2}^m \\ &\quad | p_o^*(y, l_s, s_1, s_2, z) \cdot (y \cdot i(l_r, r) \cdot \bar{r} \langle l_r, l_s, l_s, s_1, s_2, z, \top \rangle | \overline{p_o, up} \langle y, l_s, s_1, s_2, z \rangle) \\ &\quad | p_i^*(y, l_r, r) \cdot (y \cdot o(l_s, s_1, s_2, z) \cdot \bar{r} \langle l_s, l_r, l_s, s_1, s_2, z, \perp \rangle | \overline{p_i, up} \langle y, l_r, r \rangle)) \\ &\quad | p_o, up \rightarrow p_o \mid p_i, up \rightarrow p_i) \\ \llbracket \bar{y} \langle z \rangle . P \rrbracket_{a^2}^m &\triangleq (\nu s_1, s_2) (\overline{s_1} \mid s_1^* \cdot \overline{p_o} \langle y, l, s_1, s_2, z \rangle \mid s_2 \cdot \llbracket P \rrbracket_{a^2}^m) \\ \llbracket y(x) . P \rrbracket_{a^2}^m &\triangleq (\nu r) (\overline{p_i} \langle y, l, r \rangle \mid r^*(l_1, l_2, -, s_1, s_2, x, b) \cdot \\ &\quad \text{test } l_1 \text{ then test } l_2 \text{ then } \overline{l_1} \langle \perp \rangle \mid \overline{l_2} \langle \perp \rangle \mid \overline{s_2} \mid \llbracket P \rrbracket_{a^2}^m \\ &\quad \text{else } \overline{l_1} \langle \top \rangle \mid \overline{l_2} \langle \perp \rangle \mid \text{test } b \text{ then } \overline{p_i} \langle y, l, r \rangle \text{ else } \overline{s_1} \\ &\quad \text{else } \overline{l_1} \langle \perp \rangle \mid \text{test } b \text{ then } \overline{s_1} \text{ else } \overline{p_i} \langle y, l, r \rangle) \end{aligned}$$

Here $\varphi_{a^2}^m$ is some arbitrary injective substitution such that $\forall n \in \mathcal{N} . \varphi_{a^2}^m(n) \notin N$, where $N = \{p_o, p_i, p_o, up, p_i, up, l, l_s, l_r, l_1, l_2, s_1, s_2, r, o, i, y, y, z, t, f, b\}$. The remaining operators restriction, sum, τ guarded terms, and $\checkmark$ are translated as in $\llbracket \cdot \rrbracket_a^s$ or $\llbracket \cdot \rrbracket_a^m$ again.

Fig. 6. Encoding $\llbracket \cdot \rrbracket_{a^2}^m$ from π_m without replicated input into π_a^2 .

For simplicity, we do not consider replicated input on the source language. Then the encoding $\llbracket \cdot \rrbracket_{a^2}^m$, given in Figure 6, is a good encoding from π_m without replicated input into π_a^2 . Note that, to prove that $\llbracket \cdot \rrbracket_{a^2}^m$ is correct with respect to the criteria presented in Section 1.3, we can argument very similar as for $\llbracket \cdot \rrbracket_a^m$, because the main feature, i.e., the way in which sum locks are ordered, is the same for both encodings. On the other side, as already stated by [CM03], there is no good encoding from π_m into π_a^2 , that translates the parallel operator rigidly. Note that the separation result in [CM03] does not rely on replication, i.e., it also implies that there is no such encoding from π_m without replicated input into π_a^2 .

References

- Bou92. G. Boudol. Asynchrony and the π -calculus (note). Note, INRIA, Mai 1992.
- CM03. M. Carbone and S. Maffei. On the Expressive Power of Polyadic Synchronisation in π -Calculus. *Nordic Journal of Computing*, 10:1–29, 2003.
- Gor10. D. Gorla. Towards a Unified Approach to Encodability and Separation Results for Process Calculi. *Information and Computation*, 208(9):1031–1053, 2010.
- HT91. K. Honda and M. Tokoro. An Object Calculus for Asynchronous Communication. In *Proceedings of ECOOP’91*, volume 512 of *Lecture Notes in Computer Science*, pages 133–147. Springer Berlin / Heidelberg, 1991.
- Nes00. U. Nestmann. What is a “Good” Encoding of Guarded Choice? *Information and Computation*, 156(1-2):287–319, 2000.
- NP00. U. Nestmann and B. C. Pierce. Decoding Choice Encodings. *Information and Computation*, 163(1):1–59, 2000. An extended abstract appeared in the *Proceedings of CONCUR’96*, volume 1119 of *Lecture Notes in Computer Science*.
- Pal03. C. Palamidessi. Comparing the Expressive Power of the Synchronous and the Asynchronous π -calculi. *Mathematical Structures in Computer Science*, 13(5):685–719, 2003.
- PN12. K. Peters and U. Nestmann. Is it a “Good” Encoding of Mixed Choice? In *ETAPS*, 2012. To appear at FoSSaCS.

- PSN11. K. Peters, J.-W. Schicke-Uffmann, and U. Nestmann. Synchrony vs Causality in the Asynchronous Pi-Calculus. In Bas Luttik and Frank D. Valencia, editors, *EXPRESS*, volume 64 of *EPTCS*, pages 89–103, 2011.
- SW01. D. Sangiorgi and D. Walker. *The π -calculus: A Theory of Mobile Processes*. Cambridge University Press New York, NY, USA, 2001.